

ADDENDUM TO THE TENDER DOCUMENT

TENDER No. CJG 1677 P12 for 3-D Vibroseis Seismic Data Acquisition & Processing (AP)

Sr. No.	Sect.; Pg; Article	Existing Clause	Modified Clause
1	Section-II 21.1, Line 2	"Section – VIII"	Should read as "Section – IX"
2	Section-II 21.1, Line 3	"Opening if the"	Should read as "Opening of the"
3	Section-II 27.0., Line 4	"Section – VII"	Should read as "Section – VIII"
4	Section-III Clause 2.2	The mobilization of all equipment and personnel for seismic data acquisition shall commence from the date of issue of the firm "Letter of Award" by Company to Contractor confirming award of Contract and continue till the entire equipment/ tools/personnel are properly positioned, camp is established/made ready for use and acquisition of 3-D Seismic Data is actually started in the field.	The mobilization of all equipment and personnel for seismic data acquisition shall commence from the date of issue of the firm "Letter of Award" by Company to Contractor confirming award of Contract and continue till the entire equipment/ tools/personnel are properly positioned, camp is established/made ready for use, pre-acquisition experimental work completed and acquisition of 3-D Seismic Data is actually started in the field.
5	Section-IV Clause 2.0 (i)	No foreign nationals will be deployed in the Contractor's workforce, else obtaining necessary security clearance from the Ministry of Defence, if required any, will be the sole responsibility of the Contractor.	Obtaining necessary security clearance from the Ministry of Defence or any other clearances as may be applicable for the Foreign Nationals deployed in their workforce will be the sole responsibility of the bidder. However, Company will help to the extent possible in providing any documents/ certificates required in this regard.

ADDENDUM TO THE TENDER DOCUMENT

TENDER No. CJG 1677 P12 for 3-D Vibroseis Seismic Data Acquisition & Processing (AP)

Sr. No.	Sect.; Pg; Article	Existing Clause	Modified Clause																																																																																																																																																																								
7		<u>PRICE BID FORMAT</u>	<u>PRICE BID FORMAT</u>																																																																																																																																																																								
		<table border="1"> <thead> <tr> <th>Srl. No.</th> <th>Item</th> <th>Unit</th> <th>Qty.</th> <th>Unit Rate (Currency)</th> <th>Total Price (Currency)</th> </tr> </thead> <tbody> <tr> <td align="center" colspan="6"><u>3D SEISMIC DATA ACQUISITION</u></td> </tr> <tr> <td>1</td> <td>Mobilization Charges</td> <td>Lumpsum</td> <td>1</td> <td>MOB***</td> <td>1 x MOB</td> </tr> <tr> <td>2</td> <td>Cost for Experimental Recording</td> <td>Per Day</td> <td>10*</td> <td>EXP</td> <td>10 x EXP</td> </tr> <tr> <td>3</td> <td>Standby Charges for Equipment and Crew</td> <td>Per Day</td> <td>10</td> <td>SBR</td> <td>10 x SBR</td> </tr> <tr> <td>4</td> <td>Force Majeure Charges</td> <td>Per Day</td> <td>10</td> <td>FM</td> <td>10 x FM</td> </tr> <tr> <td>5</td> <td>Seismic Data Acquisition Charges 3D Vibroseis, 56 fold (Full fold) (Bin Size : 20 m x 40 m)</td> <td>Per Sq. Km.</td> <td>1517</td> <td>OR** (Avg. of "A" as per Operating Rate Matrix given below)</td> <td>1517 x OR</td> </tr> <tr> <td>6</td> <td>LVL Survey Rate</td> <td>Per location</td> <td>1000</td> <td>LVL</td> <td>1000 x LVL</td> </tr> <tr> <td>7</td> <td>Up-hole Survey Rate</td> <td>Per location</td> <td>300</td> <td>UH</td> <td>300 x UH</td> </tr> <tr> <td>8</td> <td>Cost of Fixing Reference Pillar</td> <td>Per location</td> <td>50</td> <td>FRP</td> <td>50 x FRP</td> </tr> <tr> <td>9</td> <td>Demobilization Charges</td> <td>Lumpsum</td> <td>1</td> <td>DMOB</td> <td>1 x DMOB</td> </tr> <tr> <td align="center" colspan="6"><u>3D SEISMIC DATA PROCESSING</u></td> </tr> <tr> <td>10</td> <td>Charges for Basic Processing i.e. Processing of 56 fold (Full Fold) 3D Vibroseis Seismic Data up to Pre-Stack Time Migration (Pre-STM) (Bin Size : 20 m x 40 m)</td> <td>Per Sq. km.</td> <td>1517</td> <td>PR</td> <td>1517 x PR</td> </tr> <tr> <td colspan="6"> TOTAL EVALUATED CONTRACT VALUE (Sum Total of above) : (1 x MOB) + (10 x EXP) + (10 x SBR) + (10 x FM) + (1517 x OR) + (1000 x LVL) + (300 x UH) + (50 x FRP) + (1 x DMOB) + (1517 x PR). </td> </tr> </tbody> </table>	Srl. No.	Item	Unit	Qty.	Unit Rate (Currency)	Total Price (Currency)	<u>3D SEISMIC DATA ACQUISITION</u>						1	Mobilization Charges	Lumpsum	1	MOB***	1 x MOB	2	Cost for Experimental Recording	Per Day	10*	EXP	10 x EXP	3	Standby Charges for Equipment and Crew	Per Day	10	SBR	10 x SBR	4	Force Majeure Charges	Per Day	10	FM	10 x FM	5	Seismic Data Acquisition Charges 3D Vibroseis, 56 fold (Full fold) (Bin Size : 20 m x 40 m)	Per Sq. Km.	1517	OR** (Avg. of "A" as per Operating Rate Matrix given below)	1517 x OR	6	LVL Survey Rate	Per location	1000	LVL	1000 x LVL	7	Up-hole Survey Rate	Per location	300	UH	300 x UH	8	Cost of Fixing Reference Pillar	Per location	50	FRP	50 x FRP	9	Demobilization Charges	Lumpsum	1	DMOB	1 x DMOB	<u>3D SEISMIC DATA PROCESSING</u>						10	Charges for Basic Processing i.e. Processing of 56 fold (Full Fold) 3D Vibroseis Seismic Data up to Pre-Stack Time Migration (Pre-STM) (Bin Size : 20 m x 40 m)	Per Sq. km.	1517	PR	1517 x PR	TOTAL EVALUATED CONTRACT VALUE (Sum Total of above) : (1 x MOB) + (10 x EXP) + (10 x SBR) + (10 x FM) + (1517 x OR) + (1000 x LVL) + (300 x UH) + (50 x FRP) + (1 x DMOB) + (1517 x PR).						<table border="1"> <thead> <tr> <th>Srl. No.</th> <th>Item</th> <th>Unit</th> <th>Qty.</th> <th>Unit Rate (Currency)</th> <th>Total Price (Currency)</th> </tr> </thead> <tbody> <tr> <td align="center" colspan="6"><u>3D SEISMIC DATA ACQUISITION</u></td> </tr> <tr> <td>1</td> <td>Mobilization Charges</td> <td>Lumpsum</td> <td>1</td> <td>MOB***</td> <td>1 x MOB</td> </tr> <tr> <td>2</td> <td>Cost for Experimental Recording</td> <td>Per Day</td> <td>10*</td> <td>EXP</td> <td>10 x EXP</td> </tr> <tr> <td>3</td> <td>Standby Charges for Equipment and Crew</td> <td>Per Day</td> <td>10</td> <td>SBR</td> <td>10 x SBR</td> </tr> <tr> <td>4</td> <td>Force Majeure Charges</td> <td>Per Day</td> <td>10</td> <td>FM</td> <td>10 x FM</td> </tr> <tr> <td>5</td> <td>Seismic Data Acquisition Charges 3D Vibroseis, 56 fold (Full fold) (Bin Size : 20 m x 40 m)</td> <td>Per Sq. Km.</td> <td>1517</td> <td>OR** (Avg. of "A" as per Operating Rate Matrix given below)</td> <td>1517 x OR</td> </tr> <tr> <td>6</td> <td>LVL Survey Rate</td> <td>Per location</td> <td>1000</td> <td>LVL</td> <td>1000 x LVL</td> </tr> <tr> <td>7</td> <td>Up-hole Survey Rate</td> <td>Per location</td> <td>300</td> <td>UH</td> <td>300 x UH</td> </tr> <tr> <td>8</td> <td>Cost of Fixing Reference Pillar</td> <td>Per location</td> <td>50</td> <td>FRP</td> <td>50 x FRP</td> </tr> <tr> <td>9</td> <td>Demobilization Charges</td> <td>Lumpsum</td> <td>1</td> <td>DMOB</td> <td>1 x DMOB</td> </tr> <tr> <td align="center" colspan="6"><u>3D SEISMIC DATA PROCESSING</u></td> </tr> <tr> <td>10</td> <td>Charges for Basic Processing i.e. Processing of 56 fold (full-fold) 3D Vibroseis Seismic Data (Bin Size : 20 m x 40 m) per Sq. Km. basis (as per the Processing Sequence mentioned in Section-V, Clause B1.4):</td> <td>Per Sq. km.</td> <td>1517</td> <td>PR</td> <td>1517 x PR</td> </tr> <tr> <td colspan="6"> TOTAL EVALUATED CONTRACT VALUE (Sum Total of above) : (1 x MOB) + (10 x EXP) + (10 x SBR) + (10 x FM) + (1517 x OR) + (1000 x LVL) + (300 x UH) + (50 x FRP) + (1 x DMOB) + (1517 x PR). </td> </tr> </tbody> </table>	Srl. No.	Item	Unit	Qty.	Unit Rate (Currency)	Total Price (Currency)	<u>3D SEISMIC DATA ACQUISITION</u>						1	Mobilization Charges	Lumpsum	1	MOB***	1 x MOB	2	Cost for Experimental Recording	Per Day	10*	EXP	10 x EXP	3	Standby Charges for Equipment and Crew	Per Day	10	SBR	10 x SBR	4	Force Majeure Charges	Per Day	10	FM	10 x FM	5	Seismic Data Acquisition Charges 3D Vibroseis, 56 fold (Full fold) (Bin Size : 20 m x 40 m)	Per Sq. Km.	1517	OR** (Avg. of "A" as per Operating Rate Matrix given below)	1517 x OR	6	LVL Survey Rate	Per location	1000	LVL	1000 x LVL	7	Up-hole Survey Rate	Per location	300	UH	300 x UH	8	Cost of Fixing Reference Pillar	Per location	50	FRP	50 x FRP	9	Demobilization Charges	Lumpsum	1	DMOB	1 x DMOB	<u>3D SEISMIC DATA PROCESSING</u>						10	Charges for Basic Processing i.e. Processing of 56 fold (full-fold) 3D Vibroseis Seismic Data (Bin Size : 20 m x 40 m) per Sq. Km. basis (as per the Processing Sequence mentioned in Section-V, Clause B1.4):	Per Sq. km.	1517	PR	1517 x PR	TOTAL EVALUATED CONTRACT VALUE (Sum Total of above) : (1 x MOB) + (10 x EXP) + (10 x SBR) + (10 x FM) + (1517 x OR) + (1000 x LVL) + (300 x UH) + (50 x FRP) + (1 x DMOB) + (1517 x PR).					
Srl. No.	Item	Unit	Qty.	Unit Rate (Currency)	Total Price (Currency)																																																																																																																																																																						
<u>3D SEISMIC DATA ACQUISITION</u>																																																																																																																																																																											
1	Mobilization Charges	Lumpsum	1	MOB***	1 x MOB																																																																																																																																																																						
2	Cost for Experimental Recording	Per Day	10*	EXP	10 x EXP																																																																																																																																																																						
3	Standby Charges for Equipment and Crew	Per Day	10	SBR	10 x SBR																																																																																																																																																																						
4	Force Majeure Charges	Per Day	10	FM	10 x FM																																																																																																																																																																						
5	Seismic Data Acquisition Charges 3D Vibroseis, 56 fold (Full fold) (Bin Size : 20 m x 40 m)	Per Sq. Km.	1517	OR** (Avg. of "A" as per Operating Rate Matrix given below)	1517 x OR																																																																																																																																																																						
6	LVL Survey Rate	Per location	1000	LVL	1000 x LVL																																																																																																																																																																						
7	Up-hole Survey Rate	Per location	300	UH	300 x UH																																																																																																																																																																						
8	Cost of Fixing Reference Pillar	Per location	50	FRP	50 x FRP																																																																																																																																																																						
9	Demobilization Charges	Lumpsum	1	DMOB	1 x DMOB																																																																																																																																																																						
<u>3D SEISMIC DATA PROCESSING</u>																																																																																																																																																																											
10	Charges for Basic Processing i.e. Processing of 56 fold (Full Fold) 3D Vibroseis Seismic Data up to Pre-Stack Time Migration (Pre-STM) (Bin Size : 20 m x 40 m)	Per Sq. km.	1517	PR	1517 x PR																																																																																																																																																																						
TOTAL EVALUATED CONTRACT VALUE (Sum Total of above) : (1 x MOB) + (10 x EXP) + (10 x SBR) + (10 x FM) + (1517 x OR) + (1000 x LVL) + (300 x UH) + (50 x FRP) + (1 x DMOB) + (1517 x PR).																																																																																																																																																																											
Srl. No.	Item	Unit	Qty.	Unit Rate (Currency)	Total Price (Currency)																																																																																																																																																																						
<u>3D SEISMIC DATA ACQUISITION</u>																																																																																																																																																																											
1	Mobilization Charges	Lumpsum	1	MOB***	1 x MOB																																																																																																																																																																						
2	Cost for Experimental Recording	Per Day	10*	EXP	10 x EXP																																																																																																																																																																						
3	Standby Charges for Equipment and Crew	Per Day	10	SBR	10 x SBR																																																																																																																																																																						
4	Force Majeure Charges	Per Day	10	FM	10 x FM																																																																																																																																																																						
5	Seismic Data Acquisition Charges 3D Vibroseis, 56 fold (Full fold) (Bin Size : 20 m x 40 m)	Per Sq. Km.	1517	OR** (Avg. of "A" as per Operating Rate Matrix given below)	1517 x OR																																																																																																																																																																						
6	LVL Survey Rate	Per location	1000	LVL	1000 x LVL																																																																																																																																																																						
7	Up-hole Survey Rate	Per location	300	UH	300 x UH																																																																																																																																																																						
8	Cost of Fixing Reference Pillar	Per location	50	FRP	50 x FRP																																																																																																																																																																						
9	Demobilization Charges	Lumpsum	1	DMOB	1 x DMOB																																																																																																																																																																						
<u>3D SEISMIC DATA PROCESSING</u>																																																																																																																																																																											
10	Charges for Basic Processing i.e. Processing of 56 fold (full-fold) 3D Vibroseis Seismic Data (Bin Size : 20 m x 40 m) per Sq. Km. basis (as per the Processing Sequence mentioned in Section-V, Clause B1.4):	Per Sq. km.	1517	PR	1517 x PR																																																																																																																																																																						
TOTAL EVALUATED CONTRACT VALUE (Sum Total of above) : (1 x MOB) + (10 x EXP) + (10 x SBR) + (10 x FM) + (1517 x OR) + (1000 x LVL) + (300 x UH) + (50 x FRP) + (1 x DMOB) + (1517 x PR).																																																																																																																																																																											

ADDENDUM TO THE TENDER DOCUMENT

TENDER No. CJG 1677 P12 for 3-D Vibroseis Seismic Data Acquisition & Processing (AP)

Sr. No.	Sect.; Pg; Article	Existing Clause	Modified Clause																																																																																																																																	
8	Section – V, Clause A4.3	<p>Contractor shall use the following field acquisition parameters for the 3D seismic survey.</p> <table border="1"> <tr><td>1</td><td>Fold</td><td>56 (8 x 7)</td></tr> <tr><td>2</td><td>Group Interval</td><td>40 m</td></tr> <tr><td>3</td><td>VP Interval</td><td>80 m</td></tr> <tr><td>4</td><td>Bin Size (Inline x Cross line)</td><td>20 m x 40 m</td></tr> <tr><td>5</td><td>Source</td><td>2 x 2 Vibrators (flip flop)</td></tr> <tr><td>6</td><td>No. of sweeps</td><td>To be determined from experimental trials</td></tr> <tr><td>7</td><td>Sweep length</td><td>To be determined from experimental trials</td></tr> <tr><td>8</td><td>Move up between Sweeps</td><td>To be determined from experimental trials. One record on tape at each surface sweep location</td></tr> <tr><td>9</td><td>Number of Geophones per station</td><td>12</td></tr> <tr><td>10</td><td>Array of Geophones</td><td>To be determined from experimental trials</td></tr> <tr><td>11</td><td>Correlated record length</td><td>5 seconds</td></tr> <tr><td>12</td><td>Sample Interval</td><td>2 ms.</td></tr> <tr><td>13</td><td>Receiver line Interval</td><td>160 m</td></tr> <tr><td>14</td><td>Live receiver lines</td><td>14</td></tr> <tr><td>15</td><td>Live channels per receiver line</td><td>128</td></tr> <tr><td>16</td><td>Total No. of live channels per VP</td><td>1792</td></tr> <tr><td>17</td><td>Source line interval</td><td>320m</td></tr> <tr><td>18</td><td>Symmetrical Split Spread</td><td>Yes</td></tr> <tr><td>19</td><td>Orthogonal Spread Geometry</td><td>Yes</td></tr> <tr><td>20</td><td>Roll</td><td>One line</td></tr> <tr><td>21</td><td>Patch</td><td>Symmetrical patch Shooting (Total channels for each VP should be 1792 (14 lines x 128 channels))</td></tr> </table>	1	Fold	56 (8 x 7)	2	Group Interval	40 m	3	VP Interval	80 m	4	Bin Size (Inline x Cross line)	20 m x 40 m	5	Source	2 x 2 Vibrators (flip flop)	6	No. of sweeps	To be determined from experimental trials	7	Sweep length	To be determined from experimental trials	8	Move up between Sweeps	To be determined from experimental trials. One record on tape at each surface sweep location	9	Number of Geophones per station	12	10	Array of Geophones	To be determined from experimental trials	11	Correlated record length	5 seconds	12	Sample Interval	2 ms.	13	Receiver line Interval	160 m	14	Live receiver lines	14	15	Live channels per receiver line	128	16	Total No. of live channels per VP	1792	17	Source line interval	320m	18	Symmetrical Split Spread	Yes	19	Orthogonal Spread Geometry	Yes	20	Roll	One line	21	Patch	Symmetrical patch Shooting (Total channels for each VP should be 1792 (14 lines x 128 channels))	<p>Contractor shall use the following field acquisition parameters for the 3D seismic survey.</p> <table border="1"> <tr><td>1</td><td>Fold</td><td>56 (8 x 7)</td></tr> <tr><td>2</td><td>Group Interval</td><td>40 m</td></tr> <tr><td>3</td><td>VP Interval</td><td>80 m</td></tr> <tr><td>4</td><td>Bin Size (Inline x Cross line)</td><td>20 m x 40 m</td></tr> <tr><td>5</td><td>Source</td><td>2 x 2 Vibrators (flip flop)</td></tr> <tr><td>6</td><td>No. of sweeps</td><td>To be determined from experimental trials</td></tr> <tr><td>7</td><td>Sweep length</td><td>To be determined from experimental trials</td></tr> <tr><td>8</td><td>Move up between Sweeps</td><td>To be determined from experimental trials. One record on tape at each surface sweep location</td></tr> <tr><td>9</td><td>Number of Geophones per station</td><td>12</td></tr> <tr><td>10</td><td>Array of Geophones</td><td>To be determined from experimental trials</td></tr> <tr><td>11</td><td>Correlated record length</td><td>5 seconds</td></tr> <tr><td>12</td><td>Sample Interval</td><td>2 ms.</td></tr> <tr><td>13</td><td>Receiver line Interval</td><td>160 m</td></tr> <tr><td>14</td><td>Live receiver lines</td><td>14</td></tr> <tr><td>15</td><td>Live channels per receiver line</td><td>128</td></tr> <tr><td>16</td><td>Total No. of live channels per VP</td><td>1792</td></tr> <tr><td>17</td><td>Source line interval</td><td>320m</td></tr> <tr><td>18</td><td>Symmetrical Split Spread</td><td>Yes</td></tr> <tr><td>19</td><td>Orthogonal Spread Geometry</td><td>Yes</td></tr> <tr><td>20</td><td>Roll</td><td>One line</td></tr> <tr><td>21</td><td>Patch</td><td>Symmetrical patch Shooting (Total channels for each VP should be 1792 (14 lines x 128 channels))</td></tr> <tr><td>22</td><td>Block Orientation</td><td>The tentative Azimuth of the Trace Lines is 135° from North and Source Lines is 45° from North. Trace and Source Lines are orthogonal to each other. However, there may be a change of ±5° in the orientation of the above if required.</td></tr> </table>	1	Fold	56 (8 x 7)	2	Group Interval	40 m	3	VP Interval	80 m	4	Bin Size (Inline x Cross line)	20 m x 40 m	5	Source	2 x 2 Vibrators (flip flop)	6	No. of sweeps	To be determined from experimental trials	7	Sweep length	To be determined from experimental trials	8	Move up between Sweeps	To be determined from experimental trials. One record on tape at each surface sweep location	9	Number of Geophones per station	12	10	Array of Geophones	To be determined from experimental trials	11	Correlated record length	5 seconds	12	Sample Interval	2 ms.	13	Receiver line Interval	160 m	14	Live receiver lines	14	15	Live channels per receiver line	128	16	Total No. of live channels per VP	1792	17	Source line interval	320m	18	Symmetrical Split Spread	Yes	19	Orthogonal Spread Geometry	Yes	20	Roll	One line	21	Patch	Symmetrical patch Shooting (Total channels for each VP should be 1792 (14 lines x 128 channels))	22	Block Orientation	The tentative Azimuth of the Trace Lines is 135° from North and Source Lines is 45° from North. Trace and Source Lines are orthogonal to each other. However, there may be a change of ±5° in the orientation of the above if required.
1	Fold	56 (8 x 7)																																																																																																																																		
2	Group Interval	40 m																																																																																																																																		
3	VP Interval	80 m																																																																																																																																		
4	Bin Size (Inline x Cross line)	20 m x 40 m																																																																																																																																		
5	Source	2 x 2 Vibrators (flip flop)																																																																																																																																		
6	No. of sweeps	To be determined from experimental trials																																																																																																																																		
7	Sweep length	To be determined from experimental trials																																																																																																																																		
8	Move up between Sweeps	To be determined from experimental trials. One record on tape at each surface sweep location																																																																																																																																		
9	Number of Geophones per station	12																																																																																																																																		
10	Array of Geophones	To be determined from experimental trials																																																																																																																																		
11	Correlated record length	5 seconds																																																																																																																																		
12	Sample Interval	2 ms.																																																																																																																																		
13	Receiver line Interval	160 m																																																																																																																																		
14	Live receiver lines	14																																																																																																																																		
15	Live channels per receiver line	128																																																																																																																																		
16	Total No. of live channels per VP	1792																																																																																																																																		
17	Source line interval	320m																																																																																																																																		
18	Symmetrical Split Spread	Yes																																																																																																																																		
19	Orthogonal Spread Geometry	Yes																																																																																																																																		
20	Roll	One line																																																																																																																																		
21	Patch	Symmetrical patch Shooting (Total channels for each VP should be 1792 (14 lines x 128 channels))																																																																																																																																		
1	Fold	56 (8 x 7)																																																																																																																																		
2	Group Interval	40 m																																																																																																																																		
3	VP Interval	80 m																																																																																																																																		
4	Bin Size (Inline x Cross line)	20 m x 40 m																																																																																																																																		
5	Source	2 x 2 Vibrators (flip flop)																																																																																																																																		
6	No. of sweeps	To be determined from experimental trials																																																																																																																																		
7	Sweep length	To be determined from experimental trials																																																																																																																																		
8	Move up between Sweeps	To be determined from experimental trials. One record on tape at each surface sweep location																																																																																																																																		
9	Number of Geophones per station	12																																																																																																																																		
10	Array of Geophones	To be determined from experimental trials																																																																																																																																		
11	Correlated record length	5 seconds																																																																																																																																		
12	Sample Interval	2 ms.																																																																																																																																		
13	Receiver line Interval	160 m																																																																																																																																		
14	Live receiver lines	14																																																																																																																																		
15	Live channels per receiver line	128																																																																																																																																		
16	Total No. of live channels per VP	1792																																																																																																																																		
17	Source line interval	320m																																																																																																																																		
18	Symmetrical Split Spread	Yes																																																																																																																																		
19	Orthogonal Spread Geometry	Yes																																																																																																																																		
20	Roll	One line																																																																																																																																		
21	Patch	Symmetrical patch Shooting (Total channels for each VP should be 1792 (14 lines x 128 channels))																																																																																																																																		
22	Block Orientation	The tentative Azimuth of the Trace Lines is 135° from North and Source Lines is 45° from North. Trace and Source Lines are orthogonal to each other. However, there may be a change of ±5° in the orientation of the above if required.																																																																																																																																		

ADDENDUM TO THE TENDER DOCUMENT

TENDER No. CJG 1677 P12 for 3-D Vibroseis Seismic Data Acquisition & Processing (AP)