

PART-II**SCHEDULE OF RATES/ WORKS**

CONSTRUCTION OF PERIMETER WALL OF 310 METER LONG ALONG WITH REPLACEMENT OF EXISTING TWO NOS. OF ENTRANCE GATES IN OIL RESIDENTIAL COMPLEX, SECTOR-15A, NOIDA

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE	AMOUNT
1	Dismantling of concrete work including disposal of dismantled materials from site	60	M3		
2	Earth work in execution of foundations trenches, drains etc in all kinds of soil and disposal of excavated earth / surplus earth after back filling of foundation trenches from the premises.	120	M3		
3	RCC in proportion 1:2:4 in foundation/plinth level	50	M3		
5	Providing brick masonry work at all levels with bricks with class designation 75 in super structure in cement mortar 1 : 4 and curing etc	105	M3		
6	12 mm thick Cement sand plaster 1 : 4	950	M2		
7	Centering and shuttering including strutting, propping etc and removal of formwork etc complete for lintels and beams etc	140	M2		
8	Centering and shuttering including strutting, propping etc and removal of formwork etc complete for columns Pillars and posts etc etc	90	M2		
9	Reinforcement for RCC work including cutting, bending, binding, placing in position etc complete for ms steel and medium tensile steel bars	3000	KG		
10	Applying two or more coats APEX brand of exterior paint as directed manufacturer of required shade (readymade) to give an even shade including sand papering and preparation of surface complete.	1300	M2		

PART-II**SCHEDULE OF RATES/ WORKS**

CONSTRUCTION OF PERIMETER WALL OF 310 METER LONG ALONG WITH REPLACEMENT OF EXISTING TWO NOS. OF ENTRANCE GATES IN OIL RESIDENTIAL COMPLEX, SECTOR-15A, NOIDA

SL NO	DESCRIPTION OF ITEM	QTY	UNIT	RATE	AMOUNT
11	Supplying and fixing grill of MS flat and square bars of approved size in approved design with all welding spots.	7800	KG		
12	Electrical piping work with necessary consealed pipes in the brick work and restoring the surface to normal	700	M		
13	Electrical wiring works with all electrical fittings, switches etc complete	1200	M		
14	Supply and installation of wall lights of approved design ie VICTORIA or equivalent and make (BAJAJ/PHILLIP or equivalent etc)	70	NO		
15	Primer coating in the iron frame ie grill etc	460	M2		
16	Painting with synthetic enamel paints - two or more coats on new surface.	460	M2		
17	M. S iron gate with welded joints with approved design having 2 shutters fixed in position with the help of gate posts and properly stayed if necessary.	4	NO		
TOTAL CONTRACT VALUE					

Note:

- 1) The above prices are inclusive of all statutory levies, taxes, duties etc.
- 2) The eligible and acceptable bids shall be compared on the basis of the "Total Contract
- 3) The estimated quantities indicated above against each item are for evaluation purpose only. The actual work to be carried out may be more or less depending upon actual site requirement and payment will be made for the actual work done/materials supplied.