

OIL INDIA LIMITED
(A Government of India Enterprise)
CONTRACTS DEPARTMENT
P.O.: Duliajan- 786602, Assam

CORRIGENDUM-1 DATED: 16.04.2024 TO TENDER NO.: CDC6106P25

This Corrigendum is issued to all concerned bidders of the aforesaid tenders to notify the following:

PART-II SOQ has been revised and uploaded under "Amendments" folder in OIL's e-tender portal. All concerned bidders are advised to take the **Revised Part-II SOQ** into account and participate in the tender.

All others terms and conditions of the Bid Document remain unchanged. Details can be viewed at www.oil-india.com.


SR. OFFICER-CONTRACTS (C)

WORKS CONTRACT**SCHEDULE OF WORK, UNIT AND QUANTITY**

SL. NO.	DESCRIPTION OF SERVICE	UOM	QUANTITY	UNIT PRICE	TOTAL
	GROUP A				
	SECTION A				
1	Clearing jungle including uprooting of rank vegetation, grass, brushwood, trees and saplings of girth upto 30 cm measured at a height of 1 m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	M2	15200.00	9.83	149416.00
2	Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m. All kinds of soil	M2	9500.00	19.08	181260.00
3	Felling trees of the girth (measured at a height of 1 m above ground level) including cutting of trunks and branches removing the roots and stacking of serviceable material and disposal of unserviceable. Beyond 60 cm girth upto and including 120 cm girth.	EA	10.00	1331.53	13315.30
4	Felling trees of the girth (measured at a height of 1 m above ground level) including cutting of trunks and branches removing the roots and stacking of serviceable material and disposal of unserviceable. Beyond 120 cm girth upto and including 240 cm girth.	EA	5.00	6167.91	30839.55
5	Laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement- All work upto plinth level : 1:1.5:3 (1 cement: 1.5 coarse sand : 3graded stone aggregate 20 mm nominal size)	M3	486.498	2058.05	1001237.21
6	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	M3	3538.464	173.71	614666.58
7	Laying Brick Flat Soling (75mm thick) including grading the base and spreading 25mm thick sand bed at bottom and grouting soling with cement mortar (prop. 1:3) and carrying all materials from a distance of upto 30.00m.	M2	2548.80	173.85	443108.88
8	Laying in position cement concrete of specified grade excluding the cost of centring and shuttering - All work upto plinth level: 1:3:6 (1Cement: 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	M3	218.88	1649.80	361108.22
9	Reinforced cement concrete work in walls (any thickness), including attached pilasters, buttresses, plinth and string courses, fillets, columns, pillars, piers, abutments, posts and struts etc. upto floor five level excluding cost of centring, shuttering, finishing and reinforcement: 1:1.5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 20 mm nominal size)	M3	469.317	3327.37	1561591.31
10	Centring and shuttering including strutting, propping etc. and removal of form for: Foundations, footings, bases of columns, etc. for mass concrete.	M2	1575.36	181.97	286668.26
11	Brick work with F.P.S. bricks of class designation 75 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:4 (1 cement : 4 coarse sand)	M3	1353.449	2775.16	3756037.53
12	Centring and shuttering including strutting, propping etc. and removal of form for: Columns, Pillars, Piers, Abutments, Posts and Struts.	M2	4980.80	527.91	2629414.13

SL. NO.	DESCRIPTION OF SERVICE	UOM	QUANTITY	UNIT PRICE	TOTAL
13	Centring and shuttering including strutting, propping etc. and removal of form for: Lintels, beams, plinth beams, girders, bressumers and cantilevers.	M2	1830.00	388.67	711266.10
14	Brick work with F.P.S. bricks of class designation 75 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	M3	389.629	1637.15	637881.12
15	15mm cement plaster on rough side of single or half brick wall finished with a floating coat of neat cement of mix :1:3 (1 cement : 3 fine sand)	M2	13680.00	231.37	3165141.60
16	Demolishing R.C.C. work manually / by mechanical means including stacking of steel bars and disposal of unserviceable material within 50metres lead as per direction of Engineer-in-Charge.	M3	100.00	1991.29	199129.00
17	Providing and fixing concertina coil fencing with punched tape concertina coil 600 mm dia 10 metre openable length (total length 90m), having 50 nos. rounds per 6 metre length, upto 3 m height of wall with existing angle iron 'Y' shaped placed 2.4m or 3.00 m apart and with 9 horizontal R.B.T. reinforced barbed wire, stud tied with G.I. staples and G.I. clips to retain horizontal, including necessary bolts or G.I. barbed wire tied to angle iron, all complete as per direction of Engineer-in-charge, with reinforced barbed tape(R.B.T.) / Spring core(2.5mm thick) wire of high tensile strength of 165 kg/ sq.mm with tape(0.52 mm thick) and weight 43.478 gm/ metre (cost of M.S. angle, C.C. blocks shall be paid separately)	M	1900.00	289.80	550620.00
18	BAMBOO PILING including stiffness etc. using #Bhaluka bamboo# or big size #Jati# bamboo at river bank and water logging areas, including supply of bamboo and necessary ropes etc. complete.	M	3000.00	198.68	596040.00
19	Collecting / excavating sand, soil, silt, ordinary earth from any source, load into lorries, transport it to distant place of work including procuring earth and laying in layer of 150mm thickness and compacting, profile properly made for taking measurement, including all measurable lead upto 30m and lift as required. (The contractor shall be responsible for all formalities of supply of earth such as purchase of land including royalties, monopoly / other statutory taxes as required from any distance.)	M3	1140.00	460.20	524628.00
20	Dismantling woven wire/jingle wire/XPM/IRC fencing with post & rolling, collecting and stacking dismantled material as directed in a place ready for transport.	M2	5700.00	21.16	120612.00
21	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade: Two or more coats on new work	M2	465.92	98.50	45893.12
22	Services with welding and cutting set in carrying out miscellaneous repairs / new construction involving steel work (services of one welder and one jugali per set) to be supplied by the contractor. (New welding set inclusive fuel etc. to be supplied by the contractor).	PD8	5.00	2281.96	11409.80
23	Earth work in excavation of foundation of structures as per drawing and technical specification, including setting out, construction of shoring and bracing, removal of stumps and other deleterious matter, dressing of sides and bottom, backfilling the excavation earth to the extent required and utilising the remaining earth locally for roadwork.) for Ordinary Soil by Manual Means (Depth upto 3 m)	M3	3538.464	490.21	1734590.44
24	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars of grade Fe-500D or more.	KG	82960.846	83.17	6899853.56
25	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting,	KG	14788.742	98.83	1461571.37

SL. NO.	DESCRIPTION OF SERVICE	UOM	QUANTITY	UNIT PRICE	TOTAL
	hoisting, fixing in position and applying a priming coat of approved steel primer all complete				
26	Finishing walls with water proofing cement paint of required shade: New work (Two or more coats applied @ 3.84 kg/10 sqm)	M2	13680.00	74.48	1018886.40
SECTION B					
1	Supply of Local Bricks - First Class	NO	955132.00	12.68	12111073.76
2	Supply of Timber for shuttering.	DM3	69884.667	24.73	1728247.81
3	Supply of Sand for general use	M3	1583.377	801.26	1268696.66
4	Broken stone (Boulder broken 40-20mm)	M3	1027.748	2933.08	3014467.10
SECTION C					
1	Carriage of material by mechanical transport including loading unloading and stacking: Cement, stone blocks, G.I., C.I., A.C. & C.C. pipes below 100 mm dia and other heavy materials : Beyond 4KM and Upto5KM	TON	1129.00	158.88	179375.52
2	Extra on Carriage of material by mechanical transport including loading unloading and stacking: Cement, stone blocks, G.I., C.I., A.C. & C.C. pipes below 100 mm dia and other heavy materials on every additional KM: Beyond 20KM	TPM	107255.00	8.64	926683.20
3	Extra on Carriage of material by mechanical transport including loading unloading and stacking: Cement, stone blocks, G.I., C.I., A.C. & C.C. pipes below 100 mm dia and other heavy materials on every additional KM: Beyond 5KM and Upto 10KM	TPM	5645.00	12.32	69546.40
4	Extra on Carriage of material by mechanical transport including loading unloading and stacking: Cement, stone blocks, G.I., C.I., A.C. & C.C. pipes below 100 mm dia and other heavy materials on every additional KM: Beyond 10KM and Upto 20KM	TPM	11290.00	10.27	115948.30
TOTAL			₹4,81,20,224.23		

Note:

- a) Bidder must quote overall price within the range of “At Par” to “+10%” of Company’s Internal Estimate.
- b) Bidder must include all impale plant, labour, supervision, materials, erection of display board, sign/caution board, insurance, profit, taxes and duties including forest royalty, together with all general risks, liabilities in their quoted rates excluding PF and GST.