

OIL INDIA LIMITED
(A Government of India Enterprise)
CONTRACTS DEPARTMENT
P.O.: Duliajan- 786602, Assam

CORRIGENDUM-1 DATED: 20.04.2026 TO TENDER NO. : CDC1653P27

This Corrigendum is issued to all concerned bidders of the aforesaid tenders to notify the following:

- i) The SOQ (SCHEDULE OF WORK, UNIT AND QUANTITY) of the Tender has been revised and attached herewith.

All others terms and conditions of the Bid Document remain unchanged. Details can be viewed at www.oil-india.com.

PRITOM
PROTIM
BHUYAN

Digitally signed
by PRITOM
PROTIM BHUYAN
Date: 2026.04.20
10:11:22 +05'30'

OFFICER-CONTRACTS (C)

**WORKS CONTRACT
SCHEDULE OF WORK, UNIT AND QUANTITY**

SL NO.	DESCRIPTION OF SERVICE	UOM	QUANTITY	INTERNAL RATES EXCLUDING GST	TOTAL
	GROUP A				
	SECTION A				
1	:Clearing, removing, mud, silt etc. from steel / R.C.C. tanks, bowzers etc. including disposing off to a distance of 30m.	M3	216.000	534.12	115369.92
2	:Dismantling roofing including ridges, hips valleys and gutters etc., and stacking the material within 50 metres lead of: G.S. Sheet	M2	448.340	101.32	45425.81
3	:Dismantling steel work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking within 50metres lead.	KG	2000.000	3.52	7040.00
4	:"Dismantling wood work in frames, trusses, purlins and rafters up to 10metres span and 5 metres height including stacking the material within50 metres lead: Of sectional area 40 square centimetres and above. "	M3	1.000	2760.18	2760.18
5	:Demolishing R.C.C. work manually / by mechanical means including stacking of steel bars and disposal of unserviceable material within 50metres lead as per direction of Engineer-in-Charge.	M3	299.110	2136.13	638937.84
6	:Demolishing brick work manually / by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-Charge. In cement mortar	M3	77.970	1238.12	96536.22
7	:Surface dressing of the ground including removing vegetation and in-equalities not exceeding 15 cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5 m. All kinds of soil	M2	15750.000	20.49	322717.50
8	:Collecting / excavating sand, soil, silt, ordinary earth from anysource, load into lorries, transport it to distant place of work including procuring earth and laying in layer of 150mm thickness and compacting, profile properly made for taking measurement, including all measurable lead upto 30m and lift as required. (The contractor shall be responsible for all formalities of supply of earth such as purchase of land including royalties, monopoly / other statutory taxes as required from any distance.)	M3	4566.000	488.33	2229714.78
9	Planting trees as compensatory afforestation at the rate of 290 trees per hectare at a spacing of 6 m by grubbing and leveling the ground up to a depth of 150 mm, digging holes 0.9 m dia, 1 m deep, mixing farmyard/sludge manure with soil, planting of sapling 2 m high with 25 cm dia stem, backfilling the hole and watering.	HA	1.520	101764.00	154681.28
	Contract Execution Cost, A			₹ 36,13,183.53	
	Forest Royalty of 9% on the contract execution cost. Additional 10% Cess on forest royalties for each of MMDRRF and DMFT, B	AU	1.000	390223.82	390223.82
	Total A+B			₹ 40,03,407.35	

Notes:

1. The internal estimated rates against each line item are displayed for reference purposes only. The rates shall be quoted per unit as specified in the "PRICE BIDDING FORMAT" attached under "Notes and Attachments" tab.

2. Tenure of Agreement: The duration of the contract shall be for a period of **Sixteen (16) weeks** considered from the date of issue of Work Order.
3. Mobilisation Period: **Seven (7) days** from issuance of Work Order.
4. The quantity mentioned is purely for evaluation purpose only. However, payment shall be made on actuals.
5. The price/rate(s) quoted by the Bidders will be inclusive of all taxes except GST (i.e. IGST or CGST and SGST/UTGST as applicable in case of interstate supply or intra state supply respectively and Cess on GST, if applicable) on the final services. GST applicable for the work will be **18%**.
6. Bidder must include all impale plant, labour, supervision, materials, erection of display board, sign/caution board, insurance, profit, taxes and duties, together with all general risks, liabilities in their quoted rates excluding Forest Royalty, P.F & GST.