OIL INDIA LIMITED

KG BASIN PROJECT

KAKINADA

CORRIGENDUM

ADDENDUM No. 6 dated 25.11.2026

to

TENDER NO. CEG2403P27

1.0 This Addendum is hereby issued to Tender No. CEG2403P27 to effect thefollowing:

i) Amendments to certain provisions/clauses of the Tender, the details of which are set out in **Annexure-I** hereto.

ii) Extension of bid closing date and technical bid opening date as under –

Description	Existing Date & Time	**Extended upto**
Bid Closing Date & Time	**01.12.2026 (at 13.00 Hrs. IST)**	**11.12.2026 (at 13.00 Hrs. IST)**
Technical Bid Opening Date & Time	**01.12.2026 (at 14.30 Hrs. IST)**	**11.12.2026 (at 14.30 Hrs. IST)**

2.0 It is hereby clarified that Tender Number "CEG1335P26" mentioned in ADDENDUM No. 5 or elsewhere (if any), the same shall be read as "CEG2403P27."

3.0 All other terms and conditions of the Tender shall remain unaltered. Bidders are hereby advised to take due cognizance of the above amendments/clarifications and submit their bids accordingly.

Oil India Limited
KG Basin Project

Amendments to Tender No. CEG2403P27

SL NO	Clause No	Original Clause/ Included in Amendment	Amended Clause/To be included
1.	**Technical Deliverables and other details New Clause No. 2.1, (a) & (b) of Appendix-1, Exhibit-1 of PART-3 SECTION-II TERMS OF REFERENCE / TECHNICAL SPECIFICATIONS /** **SCOPE OF WORK** **(included in ADDENDUM No. 5 dated 20.11.2026)**	2.1 The prescribed time limits for BOPs and Riser packages will be as follows: a) Subsea BOP Testing Time – The prescribed time limit for testing of Contractor's subsea BOPs will be 15hrs. Any time taken beyond the prescribed time limit of 15 hours will be paid at Zero-Day Rate. b) Running and Pulling Times for Subsea BOPs and LMRP – The prescribed time limits for BOPs and Riser packages will be as follows: • Water depth :450m • Running Time (hrs): 16-18hrs • Pulling Time (hrs): 14–18 hrs • Total Round Trip (hrs): 28–36 hrs For any time taken beyond above prescribed times, zero-day rate will apply.	2.1 The prescribed time limits for BOPs and Riser packages will be as follows: a) Subsea BOP Testing Time – The prescribed time limit for testing of Contractor's subsea BOPs will be 15hrs. Any time taken beyond the prescribed time limit of 15 hours will be paid at Zero-Day Rate. b) Running and Pulling Times for Subsea BOPs and LMRP – The prescribed time limits for BOPs and Riser packages will be as follows: • Water depth :450m • Running Time (hrs): 16-18hrs • Pulling Time (hrs): 14–18 hrs • Total Round Trip (hrs): 28–36 hrs For any time taken beyond above prescribed times, zero-day rate will apply. Note: The Running and Pulling limits for Subsea BOPs and LMRP will be applicable for water depth up to 450 meters.