

OIL INDIA LIMITED  
(A Govt.of India Enterprise)  
NEF Project, Duliajan

**WORKS CONTRACT**

Tender No. D209871L16

SOQ - Schedule of Work, Unit, Quantities, Rates and Prices.

Service Line No.	Description of Work	Unit in Words	Quantity	Rate per Unit (Figures & Words)	Amount
10	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50 metres outside the periphery of the area cleared.	Square meter	1,800.000		
20	Cutting of trees including cutting of trunks, branches and removal of stumps including stacking of service able materials within a lead of 100 metres	Number	20.000		
30	Excavation of foundation trenches not exceeding 2 meters depth including dressing of bottom and sides of trenches and subsequent filling and compaction in 15cm layers as in column foundations,fence posts, etc. and disposal of all surplussoil as directed within a lead of 30 metres.	Cubic meter	70.000		
40	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 m and lift upto 1.5 m.	Cubic meter	9.000		
50	Surface dressing of ground including removing	Square meter	150.000		

	vegetation and inequalities not exceeding 15cm deep and disposal of rubbish, lead upto 50 m and lift upto 1.5m .		
60	Steel reinforcement for RCC work including straightening, cutting, bending, placing in position and binding all complete.Thermo-Mechanically Treated bars.	Kilogram	750.000
70	Brick flooring with first class bricks in cement mortar 1:4 including cement slurry etc. complete.	Square meter	86.000
80	Providing and laying cement concrete in retaining wall, return walls, walls (any thickness) including pilasters, piers, columns,abutments, pillars, posts, plain window sills, sunken floors, etc. up to floor five level excluding the cost of centering, shuttering and finishing.	Cubic meter	16.100
90	Providing and laying in position reinforced cement concrete excluding cost of centering and shuttering, finishing and reinforcement in -	Cubic meter	5.000
100	All work upto level V: Providing and fixing ,Centering and shuttering including strutting ,propping etc.And removal of formwork:	Square meter	53.000
110	Providing First class brickwork in foundation and plinth in : (a) in cement mortar 1: 3 ( 1 cement : 3 coarse sand )	Cubic meter	10.000
120	Providing ,laying cement plaster 1 : 3 (1 cement : 3 fine sand).including finishing all	Square meter	187.000
130	White washing with lime on new work (three or more coats)to give an even shade.	Square meter	187.000
140	Painting with synthetic enamel paint of approved brand and manufacture in all	Square meter	7.200

150	shades on new work Structural steel work in single section fixed with or without connecting plate including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kilogram	210.000
160	Providing 2nd class local wood in trusses, etc. including hoisting, fixing in position, supplying necessary fittings such as spikes, nuts and bolts, nails, etc. and applying wood preservative for unexposed surfaces etc. complete.	Cubic meter	2.500
170	Providing G.I. barbed wire fencing with 2.4m jungle heart wood post 30cm minimum dia. placed 2.5m apart using 9 horizontal lines and 2 diagonals barbed wire fixed from post to post with wire nails and projecting the post 2cm above the top most wire including earthwork and coal tarring of post below ground complete	Square meter	180.000

---

Total Amount(Rs):

---

Note :- Bidder must include all liabilities including statutory liabilities in their quoted rates.