NOTICE INVITING TENDER

<u>SUBJECT</u>: IFB No. CDH5424L21 for Charter Hire of O2(Two) No. 550 HP(Min)-750 HP(Max) Capacity Workover Rigs for a Period of O3(Three) years in the States of Assam & Arunachal Pradesh.


The above tender has been issued to the following limited parties, however other interested parties who meet the qualifying criteria as stipulated in the tender can also participate:

- (i) M/s Subhash Agarwalla, Sibsagar
- (ii) M/s Udipta Energy & Equipment Ltd., Sibsagar
- (iii) M/s Deep Industries Ltd., Ahmedabad
- (iv) M/s Quippo Oil & Gas Infrastructure Ltd., Gurgaon
- (v) M/s GTC Oilfield Services Pvt. Ltd., Ahmedabad
- (vi) M/s SK Petro Services Pvt. Ltd., Sibsagar
- (vii) M/s JayBee Energy Pvt. Ltd., Guwahati

Thanking you,

Yours faithfully, OIL INDIA LIMITED

Sd/(B. Brahma)
Sr. Manager – Contracts (G)
For Chief General Manager – Contracts
FOR RESIDENT CHIEF EXECUTIVE



CONTRACTS DEPARTMENT
TEL: (91) 374-2800548

E-mail: <u>contracts@oilindia.in</u>
Website: www.oil-india.com

FORWARDING LETTER

M/s	

Sub: IFB No. CDH5424L21 for Charter Hire of 02(Two) No. 550 HP(Min)-750 HP(Max) Capacity Workover Rigs for a Period of 03(Three) years in the States of Assam & Arunachal Pradesh.

Dear Sirs,

- 1.0 OIL INDIA LIMITED (OIL), a "Navaratna" Category, Government of India Enterprise, is a premier oil Company engaged in exploration, production and transportation of crude oil & natural gas with its Headquarters at Duliajan, Assam. Duliajan is well connected by Air with nearest Airport being at Dibrugarh, 45 km away.
- 2.0 In connection with its operations, OIL invites **National Competitive Bids (NCB)** from competent and experienced Contractors through OIL's e-procurement site for 'Charter Hire of O2(Two) No. 550 HP(Min)-750 HP(Max) Capacity Workover Rigs for a Period of O3(Three) years in the States of Assam & Arunachal Pradesh'. One complete set of Bid Document covering OIL's IFB for hiring of above services is uploaded in OIL's e-procurement portal. You are invited to submit your most competitive bid on or before the scheduled bid closing date and time through OIL's e-procurement portal. For your ready reference, few salient points of the IFB (covered in detail in the Bid Document) are highlighted below:

(i)	IFB No. /E-Tender No.	:	CDH5424L21
(ii)	Type of Bidding	:	Open Indigenous Tender; Online - Single Stage-Two Bid System
(iii)	Tender Fee	:	Not Applicable
(iv)	Bid Closing Date & Time	:	As mentioned in Online E-tender portal
(v)	Technical Bid Opening Date & Time	:	As mentioned in Online E-tender portal
(vi)	Price Bid Opening Date & Time	:	As mentioned in Online E-tender portal
(vii)	Bid Submission Mode	:	Bids must be uploaded online in OIL's E-procurement portal

(viii)	Bid Opening Place	:	Office of CGM-Contracts Contracts Department, Oil India Limited, Duliajan -786602, Assam, India.
(ix)	Bid Validity	:	120 days from date of Bid Closing
(x)	Mobilization Time	:	As defined in the tender
(xi)	Bid Security Amount	:	Not Applicable
(xii)	Bid Security Validity	:	Not Applicable
(xiii)	Original Bid Security to be submitted	:	Office of CGM-CONTRACTS, CONTRACTS DEPARTMENT, OIL INDIA LIMITED, DULIAJAN, ASSAM-786 602, INDIA
(xiv)	Amount of Performance Security	:	10% of annualized contract value
(xv)	Validity of Performance Security	:	Up to 3(three) months from date of completion of contract
(xvi)	Duration of the Contract	:	3(Three) years from the date of commencement of operation with provision for extension by 1(one) year at OIL's option.
(xvii)	Quantum of Liquidated Damage for Default in Timely Mobilization	:	Refer clause No. 30.0 of General Conditions of Contract, Part-3, Section-I.
(xviii)	Integrity Pact	:	Must be digitally signed & uploaded along with the Techno-commercial Bid.
(xix)	Bids to be addressed to	:	CGM-Contracts, Contracts Department, Oil India Limited, Duliajan-786602, Assam, India.

3.0 **Integrity Pact:** The Integrity Pact must be uploaded in OIL's E-procurement portal along with the Technical Bid digitally signed by the same signatory who signed the Bid i.e. who is duly authorized to sign the Bid. If any bidder refuses to sign Integrity Pact or declines to submit the Integrity Pact, their bid shall be rejected straightway. Uploading the Integrity Pact with digital signature will be construed that all pages of the Integrity Pact has been signed by the bidder's authorized signatory who signs the Bid.

4.0 **GUIDELINES FOR PARTICIPATING IN OIL'S E-PROCUREMENT:**

4.1 To participate in OIL's E-procurement tender, bidders should have a legally valid digital certificate of Class 3 with Organization's Name and Encryption certificate as per Indian IT Act from the licensed Certifying Authorities operating under the Root Certifying Authority of India (RCAI), Controller of Certifying Authorities (CCA) of India (http://www.cca.gov.in). Digital Signature Certificates having "Organization Name"


field as "Personal" are not acceptable. However, aforesaid Digital Signature Certificates having Bidder's Name in the "Organization Name" field are acceptable.

- 4.2 Digital Signature Certificate comes in a pair of Signing/verification and Encryption/decryption certificate. Bidder should have both the Signing/verification and Encryption/Decryption certificate for Signing and encryption, decryption purpose respectively. The driver needs to be installed once, without which the DSC will not be recognized. While participating on e-Tendering the DSC token should be connected to your system.
- 4.3 Encryption certificate is mandatorily required for submission of bid. In case bidder created response with one certificate (using encryption key) and bidder change his Digital Signature Certificate then old certificate [Used for encryption] is required in order to decrypt his encrypted response for getting the EDIT mode of the response. Once decryption is done, bidder may use new DSC certificate for uploading and submission of their offer. It is the sole responsibility of the bidder to keep their DSC certificate properly. In case of loss of the certificate, OIL INDIA LTD. will not be responsible.
- 4.4 For participation, applicants already having User ID & Password for OIL's E-Procurement Portal need to register against the IFB. New vendors/existing vendors not having User ID & Password for OIL's E-Procurement Portal shall obtain User ID & password through online vendor registration system in E-Portal.
- 4.4.1 Bidders without having E-Tender Login ID and password should complete their online registration at least 07 (Seven) days prior to the scheduled Bid Closing Date and time of the tender. For online registration, bidder may visit OIL's E-Tender site https://etender.srm.oilindia.in/irj/portal.
- 4.4.2 Necessary Login ID & Password will be issued by OIL only after submitting the complete online registration by the Bidder. In the event of late registration/incomplete registration by Bidder, OIL INDIA LIMITED shall not be responsible for late allotment of User ID & Password and request for bid closing date extension on that plea shall not be entertained by Company.
- 4.5 Parties, who do not have a User ID, can click on Guest login button in the e-Tender portal to view and download the tender. The detailed guidelines are given in User Manual available in OIL's E-Procurement site. For any clarification in this regard, bidders may contact E-Tender Support Cell at Duliajan at erp_mm@oilindia.in, Ph.: 0374-2807171/7192.
- 4.6 Details of process for submission of Bid Security (EMD) through the online payment gateway are available in Vendor User Manual under E-Procurement Portal. (**Note:** Important Points for on-line Payment can be viewed at Oil India's website at url:http://oil-india.com/pdf/ETenderNotification.pdf).
- 4.7 The link for OIL's E-Procurement Portal is available on OIL's web site (<u>www.oil-india.com</u>).

5.0 **IMPORTANT NOTES:**

Bidders shall take note of the following important points while participating in OIL's e-procurement tender:


- i) **BACKING OUT BY BIDDER:** In case any bidder withdraws their bid within the bid validity period, Bid Security will be forfeited and the party will be put on Holiday as per the Banning Policy (available in OIL's website) of Company.
- ii) **BACKING OUT BY L-1 BIDDER AFTER ISSUE OF LOA:** In case LOA issued is not accepted by the L1 bidder or the Performance Security is not submitted as per the terms of the contract within the time specified in the Bid Document, the Bid Security shall be forfeited and the bidder shall be dealt as per the Banning Policy (available in OIL's website) of Company.
- iii) **FURNISHING FRAUDULENT INFORMATION/DOCUMENT**: The information and documents furnished by the bidder/ contractor in respect of the subject tender/contract are accepted to be true and genuine. However, if it is detected during technical scrutiny or after award of the contract or after expiry of the contract, that the bidder had submitted any fake/fraudulent document or furnished false statement, the offer/contract shall be rejected/ cancelled, as the case may be and the bidder (if fake document/false statement pertains to such bidder) shall be dealt as per the Banning Policy (available in OIL's website) of Company. Undertaking of authenticity of information/documents submitted as per **Proforma-M** should be submitted along with the technical bids.
- iv) **ERRING / DEFAULTING AGENCIES:** Erring and defaulting agencies like bidder, contractor, supplier, vendor, service provider will be dealt as per OIL's Banning Policy dated 6th January, 2017 available in OIL's website: www.oil-india.com.
- v) Bid should be submitted online in OIL's E-procurement site up to 11.00 AM (IST)(Server Time) on the date as mentioned and will be opened on the same day at 2.00 PM(IST) at the office of the CGM-Contracts in presence of the authorized representatives of the bidders.
- vi) If the digital signature used for signing is not of "Class-3" with Organizations name, the bid will be rejected.
- vii) The tender is invited under **COMPOSITE BID SYSTEM**. The bidders shall submit both the "**TECHNICAL**" and "**PRICED**" bids through electronic form in the OIL's e-Procurement portal within the Bid Closing Date and Time stipulated in the e-Tender. The Technical Bid should be submitted as per Scope of Work & Technical Specifications along with all technical documents related to the tender and uploaded in "**Technical Attachments**" **Tab only**. **Details of prices as per Price Bid format/Priced bid can be uploaded under "Notes & Attachments" tab. A screen shot in this regard is shown below. Offer not complying with above submission procedure will be rejected as per Bid Evaluation Criteria.**



On "EDIT" Mode, Bidders are advised to upload "Technical Bid" and "Priced Bid" in the places as indicated above.

Notes:

- * The "Technical Bid" shall contain all techno-commercial details **except the prices**.
- ** The "Priced bid" must contain the price schedule and the bidder's commercial terms and conditions, if any. For uploading Priced Bid, click on Add Atachment, a browser window will open, select the file from the PC and name the file under Description, Assigned to General Data and click on OK to digitally sign and upload the File. Please click on Save Button of the Response to Save the uploaded files.
- wiii) Maintenance of Total bid value in the Response: For convenience of the Bidders and to improve transparency, the rates/costs quoted by bidders against the E-tender shall be available for online viewing to all the Techno-commercially qualified Bidders against the tender after price bids are opened in the system. For tenders where **Detailed Price Information under RFx Information Tab is "No price"**, the Price Bid is invited against the tender through attachment form under "Notes & Attachment". In such tenders, Bidders must upload their pricing as per the "**Price Bid Format Proforma-B"** under "**Notes & Attachment"** and additionally fill up the **on-line field "Total Bid Value"** under "**RFx Information"** Tab Page with the Total Cost (Including the GST component) as per the amount of the Price Bid in attachment form.



The "Total Bid Value" as entered by the Bidder in the on-line response shall be displayed in the E-tender portal amongst the techno-commercially qualified bidders and Company will not take any responsibility whatsoever towards incorrect information furnished by the bidders on the "Total Bid Value" field.

It is to be noted that Amount mentioned in the "Total Bid Value" field will not be considered for bid evaluation and evaluation will be purely based on the Price bid submitted as per the "Price Bid Format: Proforma-B" under "Notes & Attachments" tab page.

6.0 OIL now looks forward to your active participation in the IFB.

Thanking you,

Yours faithfully, **OIL INDIA LIMITED**

Sd/-(B. Brahma) Sr. Manager – Contracts (G) For Chief General Manager – Contracts FOR RESIDENT CHIEF EXECUTIVE

PART-1 INSTRUCTIONS TO BIDDERS (ITB)

1.0 Eligibility of the bidder:

- 1.1 The eligibility of the bidder are listed under BID EVALUATION CRITERIA (BEC), PART-2 of the Bid document.
- 1.2 Bidder shall bear all costs associated with the preparation and submission of bid. Oil India Limited, hereinafter referred to as Company, will in no case be responsible or liable for those costs, regardless of the conduct or outcome of the bidding process.

2.0 Bid Documents:

- 2.1 The services required, bidding procedures and contract terms are prescribed in the Bid Document. This Bid Document includes the following:
 - a) A Tender Forwarding Letter
 - b) Instructions to Bidders, (Part-1)
 - c) Bid Evaluation Criteria, (Part-2)
 - d) General Conditions of Contract, (Part-3, Section-I)
 - e) Terms of Reference/Technical Specification, (Part-3, Section-II)
 - f) Special Conditions of Contract, (Part-3, Section-III)
 - g) Schedule of Rates, (Part-3, Section-IV)
 - h) Estimated CIF value of items at the time of import, (Proforma-A)
 - i) Price Schedule Format, (Proforma-B)
 - j) Bid Form, (Proforma-C)
 - k) Statement of Non-Compliance, (Proforma-D)
 - 1) Bid Security Form (Proforma-E)
 - m) Performance Security Form, (Proforma-F)
 - n) Sample Agreement Form (Proforma-G)
 - o) Proforma of Letter of Authority (Proforma-H)
 - p) Authorisation for Attending Bid Opening (Proforma-I)
 - q) Integrity Pact (Proforma-J)
 - r) Safety Measures (Proforma-K)
 - s) Certificate of Compliance of Financial Criteria (Proforma-L)
 - t) Format of undertaking by Bidders towards submission of authentic information/documents (Proforma–M)
 - u) Commercial check List (Proforma-N)
- 2.2 The bidder is expected to examine all instructions, forms, terms and specifications in the Bid Documents. Failure to furnish all information required in the Bid Documents or submission of a bid not substantially responsive to the Bid Documents in every respect will be at the Bidder's risk & responsibility and may result in the rejection of its bid.
- 2.3 Bidders shall be deemed, prior to submitting their bids, to have satisfied themselves about the weather conditions, working culture in the area, sociopolitical environment, safety & security aspects, law & order situation and law

of the land, and obtain for themselves all necessary information as to the risks, contingencies and all other circumstances, which may influence or affect the various obligations under the Contract.

3.0 Transferability of bid documents:

- 3.1 Bid Documents are non-transferable. Bid can be submitted only by the bidder in whose name the Bid Document has been issued/registered.
- 3.2 In case of e-Tender, Bidder must submit the bid using Organizational Class-3 Digital Signature issued by the Competent Authority in favour of the bidder. Bid submitted using Digital Signature other than the Digital Signature of the bidder shall be summarily rejected.
- 3.3 Unsolicited bids will not be considered and will be rejected straightway.

4.0 Amendment of bid documents:

- 4.1 At any time prior to the deadline for submission of bids, the Company may, for any reason, whether at its own initiative or in response to a clarification requested by a prospective Bidder, modify the Bid Documents through issuance of an Addendum(s)/Corrigendum(s)/Amendment(s).
- 4.2 The Addendum will be uploaded in OIL's E-Tender Portal in the Tab "Technical Rfx" and under External Area "Amendments" folder. The Company may, at its discretion, extend the deadline for bid submission. Bidders are expected to take the Addendum into account in preparation and submission of their bid. Bidders are to check from time to time the E-Tender portal ["Technical RFx" Tab and under the folder "Amendments"] for any amendments to the bid documents before submission of their bids. No separate intimation shall be sent to the Bidders.

5.0 Preparation of Bids:

- 5.1 Language of Bids:
- 5.1.1 The bid prepared by the bidder and all correspondence and documents relating to the bid exchanged by the Bidder and the OIL shall be written in English language. Supporting documents and printed literature furnished by the Bidder may be in another language provided they are accompanied by an accurate translation of the relevant passages in English, duly authenticated by local chamber of Commerce of bidder's country, in which case, for purposes of interpretation of the bid, the translation shall prevail.
- 5.2 Bidder's/Agent's Name & address:
- 5.2.1 Bidders should indicate in their bids their detailed postal address including the Fax/Telephone / Cell Phone Nos. and E-mail address. Similar information should also be provided in respect of their authorised Agents in India, if any.

- 5.3 Documents comprising the bid:
- 5.3.1 Bids are invited under Single Stage Two Bid System. The bid to be uploaded by the Bidder in OIL's E-Tender portal shall comprise of the following components:

(A) Technical Bid (to be uploaded in "Technical Attachments" tab)

- a) Complete technical details of the services offered.
- b) Documentary evidence established in accordance with Clause 9.0.
- c) Bid Security (scanned) in accordance with Clause 10.0 hereunder. Original Bid Security should be sent as per Clause No. 10.10 below.
- d) Copy of Bid-Form without indicating prices in Proforma C.
- e) Statement of Non-compliance as per Proforma-D.
- f) Proforma A: List of items to be imported without the CIF values.
- g) Copy of Priced Bid without indicating prices (Proforma-B).
- h) Integrity Pact digitally signed by OIL's competent personnel as Proforma-J attached with the bid document to be digitally signed by the bidder's Authorised representative.
- i) All Other relevant Undertakings and Proformas & Annexures as applicable as part of Bid.

(B) Price Bid (to be uploaded in "Notes and Attachments" tab)

Bidder shall quote their prices in the following Proforma available in OIL's E-procurement portal in the "Notes & Attachments" Tab:

- a) Price-Bid Format as per Proforma-B
- b) Bid Form as per Proforma-C
- c) Proforma-A showing the items to be imported with the CIF values.

The Priced Bid shall contain the prices along with the currency quoted and any other commercial information pertaining to the service offered.

6.0 Bid Form:

6.1 The bidder shall complete the Bid Form and the appropriate Price Schedule furnished in their Bid.

7.0 Bid Price:

- 7.1 Prices must be quoted by the Bidders online as per the price bid format available in OIL's E-Tender Portal under "Notes & Attachment" Tab. Prices must be quoted by the bidders as per the Price/Bidding format.
- 7.2 Prices quoted by the successful bidder must remain firm during its performance of the Contract and is not subject to variation on any account.
- 7.3 All duties (except customs duty which will be borne by the Company) and taxes (excluding GST) including Corporate Income Tax, Personal Tax, Assam Entry

Tax etc. and other Cess/levies payable by the successful bidder under the Contract for which this Bid Document is being issued, shall be included in the rates, prices and total Bid Price submitted by the bidder, and the evaluation and comparison of bids shall be made considering the quoted GST in the proforma. For example, personal taxes and/or any corporate taxes arising out of the profits on the contract as per rules of the country shall be borne by the bidder.

8.0 Currencies of bid and payment:

Bidders shall submit their bid only in Indian Rupees and they will be paid in Indian Rupees only.

- 8.1 DELETED
- 8.2 DELETED

9.0 Documents establishing bidder's eligibility and qualifications:

9.1 These are listed in BID EVALUATION CRITERIA (BEC), PART-2 of the Bid document.

10.0 Bid Security:

- 10.1 The Bid Security is required to protect the Company against the risk of Bidder's conduct, which would warrant forfeiture of the Bid Security, pursuant to subclause 10.8.
- All the bids must be accompanied by Bid Security in Original for the amount as mentioned in the "Forwarding Letter" or an equivalent amount in other freely convertible currency and shall be in DD/FDR (account OIL INDIA LIMITED)/NEFT/RTGS/Electronic fund transfer to designated account of OIL/online payment through OIL's e-portal/Bank Guarantee (BG) in OIL's prescribed format as enclosed with the NIT vide Proforma E or an irrevocable Letter of Credit (L/C) from any of the following Banks
 - a) Any schedule Indian Bank or Any Branch of an International bank situated in India and registered with Reserve Bank of India as scheduled foreign bank in case of domestic bidder, or
 - b) In case of foreign bidder, the bank guarantee can be accepted from any scheduled bank in India or from International bank who has its branch in India registered with Reserve Bank of India, or
 - e)—Any foreign Bank which is not a Scheduled Bank in India provided the Bank Guarantee issued by such Bank is counter guaranteed by any Branch situated in India of any Scheduled Bank incorporated in India.

- d) Bank Guarantee issued by a Scheduled Bank on India at the request of some other Non-Schedule Bank of India shall not be acceptable.
- e) The Bank Guarantee / LC shall be valid for the time as asked for in the Bid Document. Bank Guarantees issued by Banks in India should be on non-judicial stamp paper of requisite value, as per Indian Stamp Act, purchased in the name of the Banker.
- 10.3 Any bid not secured in accordance with sub-clause 10.2 above shall be rejected by the Company as non-responsive.
- 10.4 The bidders shall extend the validity of the Bid Security suitably, if and when specifically advised by OIL, at the bidder's cost.
- 10.5 Unsuccessful Bidder's Bid Security will be discharged and/or returned within 30 days after finalization of the Tender.
- 10.6 Successful Bidder's Bid Security will be discharged and/or returned upon Bidder's furnishing the Performance Security and signing of the contract. Successful bidder will however ensure validity of the Bid Security till such time the Performance Security in conformity with Clause 27.0 below is furnished.
- 10.7 Bid Security shall not accrue any interest during its period of validity or extended validity.
- 10.8 The Bid Security may be forfeited:
 - a. If the bidder withdraws the bid within its original/extended validity.
 - b. If the bidder modifies/revises their bid suo-moto.
 - c. If the bidder does not accept the order/contract.
 - d. If the bidder does not furnish Performance Security Deposit within the stipulated time as per tender/order/contract.
 - e. If it is established that the bidder has submitted fraudulent documents or has indulged into corrupt and fraudulent practice, the bid security shall be forfeited after due process in addition to other action against the bidder.
- 10.9 In case any bidder withdraws their bid during the period of bid validity, Bid Security will be forfeited and the party shall be debarred for a period of 2(two) years or as deemed fit as per the prevailing Banning Policy of the Company (OIL).
- 10.10 The scanned copy of the original Bid Security submitted in the form of either Bank Guarantee or LC must be uploaded by bidder along with the Technical bid in the "Technical Attachment" tab of OIL's E portal. The original Bid Security shall be submitted by bidder to the office of CGM Contracts, Oil India Ltd.,

- Duliajan 786602(Assam), India in a sealed envelope which must reach GM-Contract's office on or before 12.45 Hrs (IST) on the Bid Closing date.
- 10.11 A bid shall be rejected straightway if Original Bid Security is not received within the stipulated date & time mentioned in the Tender and/or if the Bid Security validity is shorter than the validity indicated in Tender and/or if the Bid Security amount is lesser than the amount indicated in the Tender.
- 10.12 The Bank Guarantee issuing bank branch must ensure the following:
- 10.13 The Bank Guarantee issued by the bank must be routed through SFMS platform as per the following details:
 - (i) "MT 760 / MT 760 COV for issuance of bank guarantee.
 - (ii) "MT 760 / MT 767 COV for amendment of bank guarantee.

[Tender Number should reflect in the SFMS text under "MT 760 / MT 760 COV]

The above message/intimation shall be sent through SFMS by the BG issuing bank branch to HDFC Bank, Duliajan Branch, IFS Code – UTIB0001129, Branch address – Duliajan Branch, Utopia Complex, BOC Gate, Jayanagar, Duliajan, District Dibrugarh, PIN – 786602. The Bank details are as under:

	Bank Details o	f Beneficiary
A	Bank Name	HDFC BANK LTD
B	Branch Name	DULIAJAN
E	Branch Address	Utopia Complex, BOC Gate, Jayanagar, Duliajan, Dibrugarh, PIN - 786602
Đ	Banker Account No.	21182320000016
£	Type of Account	Current Account
F	IFSC Code	HDFC0002118
G	MICR Code	786240302
H	SWIFT Code	HDFCINBBCAL

10.14 Bid Security amount through NEFT or RTGS mode may be deposited on or before bid closing date and time to either of the following designated OIL's bank accounts:

	Bank Details of Beneficiary: OIL INDIA LIMITED	
a	Bank Name	STATE BANK OF INDIA
b	Branch Name	Duliajan
E	Branch Address	Duliajan, Dist-Dibrugarh
d	Bank Account No.	10494832599
e	Type of Account	Current Account
£	IFSC Code	SBIN0002053
g	MICR Code	786002302
h	SWIFT Code	SBININBB479

Note: If the bid security is submitted through NEFT or RTGS mode, details such as UTR No., Tender No., Bidder's name & Deposited Amount etc. must be uploaded with the Unpriced Techno Commercial Bid documents.

11.0 Exemption from submission of bid security:

- 11.1 Central Govt. offices and Central Public Sector undertakings are exempted from submitting Bid Security.
- 11.2 Micro or Small Enterprises (MSE) bidders are exempted from submitting Bid Security. Categorization and various Criteria applicable to MSE bidders shall be guided by the Gazette Notification No. CG DL E 26062020 220191 dated 26.06.2020 issued by MINISTRY OF MICRO, SMALL AND MEDIUM ENTERPRISES. The existing enterprises registered under EM Part II or UAM till 30th June'2020 shall continue to be valid only for a period up to the 31st day of March, 2021.
- 11.3 The bidder claiming as MSE status (MSE General, MSE SC/ST, MSE Woman) against this tender has to submit the following documents for availing the benefits applicable to MSEs:
 - i. Udyam Registration Number (URN) with Udyam Registration Certificate(URC)

OR

ii. Proof of registration with District Industry Centers or Khadi and Village Industries Commission or Khadi and Village Industries Board or Coir Board or National Small Industries Corporation or Directorate of Handicrafts and Handloom or Udyog Adhaar registration or registration with any other body specified by Ministry of MSME

11.3.1 In case bidding MSE is owned by Schedule Caste or Schedule Tribe entrepreneur or Woman Entrepreneur, valid documentary evidence issued by the agency who has registered the bidder as MSE owned by SC/ST entrepreneur/ Woman Entrepreneurs should also be enclosed.

12.0 PERIOD OF VALIDITY OF BIDS:

- 12.1 Bids shall remain valid as per the requirement mentioned in forwarding letter from the date of closing of bid prescribed by the Company. Bids of shorter validity will be rejected as being non-responsive. If nothing is mentioned by the bidder in their bid about the bid validity, it will be presumed that the bid is valid for 120 days from Bid Closing Date.
- In exceptional circumstances, the Company may solicit the Bidder's consent to an extension of the period of validity. The request and the response thereto shall be made in writing through Fax or e-mail. The Bid Security provided under Para 10.0 above shall also be suitably extended. A Bidder may refuse the request without forfeiting its Bid Security. A Bidder granting the request will neither be required nor permitted to modify their Bid.

13.0 Signing & submission of bids:

- 13.1 Signing of bids:
- Bids are to be submitted online through OIL's E-procurement portal with digital signature. The bid and all attached documents should be digitally signed by the bidder using "Class 3" digital certificates with Organization's Name [e-commerce application (Certificate with personal verification and Organisation Name)] as per Indian IT Act 2000 obtained from the licensed Certifying Authorities operating under the Root Certifying Authority of India (RCAI), Controller of Certifying Authorities (CCA) of India before bid is uploaded. Digital Signature Certificates having Bidder's Name in the "Organization Name" field are only acceptable. Digital Signature Certificate having "Organization Name" field other than Bidder's Name shall be rejected summarily.

The bid including all uploaded documents shall be digitally signed by duly authorized representative of the bidder holding a Power of Attorney to bind the Bidder to the contract.

If any modifications are made to a document after attaching digital signature, the digital signature shall again be attached to such documents before uploading the same. The Power of Attorney in original shall be submitted by bidder as mentioned in Para 13.2 below.

In case the digital signature is not of "Class-3" with organization name, the bid will be rejected. Bidder is responsible for ensuring the validity of digital signature and its proper usage by their employees.

13.1.2 The original and all copies of the bid shall be typed or written in indelible inks. Since bids are to be submitted ONLINE with digital signature, manual signature is NOT relevant. The letter of authorisation (as per Proforma-H) shall be indicated by written Power of Attorney accompanying the Bid.

- 13.1.3 Any physical documents submitted by bidders shall contain no interlineations, white fluid erasures or overwriting except as necessary to correct errors made by the Bidder, in which case such correction shall be initialed by the person or persons who has/have digitally signed the Bid.
- 13.1.4 Any Bid, which is incomplete, ambiguous, or not in compliance with the Bidding process shall be rejected.

13.2 Submission of bids:

The tender is processed under Composite Bid System. Bidder shall submit the Technical bid and Priced bid along with all the Annexures and Proforma (wherever applicable) and copies of documents in electronic form through OIL's e-procurement portal within the Bid Closing Date & Time stipulated in the etender. For submission of Bids online at OIL's E-Tender Portal, detailed instructions is available in "User Manual" available in OIL's E-Tender Portal. Guidelines for bid submission are also provided in the "Forwarding Letter". The Technical Bid is to be submitted as per Terms of Reference/Technical Specifications of the bid document and Priced Bid as per the Price Schedule. The Technical Bid should be uploaded in the "Technical Attachment" Tab Page only. Prices to be quoted as per Proforma-B should be uploaded as Attachment just in the attachment link under "Notes & Attachments" Tab under General Data in the e-portal. The priced bid should not be submitted in physical form and which shall not be considered. However, the following documents in one set should necessarily be submitted in physical form in sealed envelope superscribing the "IFB No., Brief Description of services and Bid Closing/Opening date & Time along with the bidder's name and should be submitted to CGM-Contracts, Oil India Ltd., Duliajan-786602 (Assam) on or before 12.45 Hrs (IST) on the bid closing date indicated in the IFB:

- a) The Original Bid Security along with 1(one) copy
- b) Printed catalogue and literature if called for in the bid document.
- c) Power of Attorney for signing of the bid digitally.
- d) Any other document required to be submitted in original as per bid document requirement.

Documents sent through E-mail/Fax/Telephonic method will not be considered.

- 13.2.1 All the conditions of the contract to be made with the successful bidder are given in various Sections of the Bid Document. Bidders are requested to state their non-compliance to each clause as per Proforma-D of the bid document and the same should be uploaded along with the Technical Bid.
- 13.2.2 Timely delivery of the documents in physical form as stated in Para 13.2 above is the responsibility of the bidder. Bidders should send the same through Registered Post or by Courier Services or by hand delivery to the Officer in Charge of the particular tender before the Bid Closing Date and Time. Company shall not be responsible for any postal delay/transit loss.

13.2.3 Bids received through the e-procurement portal shall only be accepted. Bids received in any other form shall not be accepted.

14.0 DELETED

15.0 Deadline for submission of bids:

- 15.1 Bids should be submitted online as per the online tender submission deadline. Bidders will not be permitted by System to make any changes in their bid/quote after the bid submission deadline is reached. Bidders are requested to take note of this and arrange to submit their bids within the submission deadline to avoid last minute rush/network problems.
- 15.2 No bid can be submitted after the submission dead line is reached. The system time displayed on the e-procurement web page shall decide the submission dead line.
- The documents in physical form as stated in Para 13.2 must be received by Company at the address specified in the "Forwarding Letter" on or before 12.45 Hrs(IST) on the Bid Closing Date mentioned in the "Forwarding Letter". Timely delivery of the same at the address mentioned in the Forwarding Letter is the responsibility of the Bidders.

16.0 Late Bids:

16.1 Bidders are advised in their own interest to ensure that their bids are uploaded in system much before the closing date and time of the bid. The documents in physical form if received by the Company after the deadline for submission prescribed by the Company shall be rejected and shall be returned to the Bidders in unopened condition immediately.

17.0 Modification and withdrawal of bids:

- 17.1 The Bidder after submission of Bid may modify or withdraw its Bid prior to Bid Closing Date & Time in the e-portal using Digital Signature by the person or persons who has/have digitally signed the Bid. Withdrawal or modification of bid through physical correspondence shall not be considered and accepted.
- 17.2 No Bid can be modified or withdrawn subsequent to the deadline for submission of Bids.
- 17.3 No Bid can be withdrawn in the interval between the deadline for submission of Bids and the expiry of the period of Bid Validity specified by the Bidder on the Bid Form. Withdrawal of a Bid during this interval shall result in the Bidder's forfeiture of its Bid Security and bidder shall also be debarred from participation in future tenders of OIL.

18.0 Extension of bid submission date:

18.1 Normally no request for extension of Bid Closing Date & Time will be entertained. However, OIL at its discretion, may extend the Bid Closing Date and/or Time due to any reasons.

19.0 Bid opening and evaluation:

- 19.1 Company will open the Technical Bids, including submission made pursuant to clause 17.0, in presence of Bidder's representatives who choose to attend at the date, time and place mentioned in the Forwarding Letter. However, an authorisation letter (as per Proforma-I) from the Bidder must be produced by the Bidder's representative at the time of Bid Opening. Unless this Letter is presented, the representative will not be allowed to attend the Bid Opening. The Bidder's representatives who are allowed to attend the Bid Opening shall sign a register evidencing their attendance. Only one representative against each Bid will be allowed to attend. In technical bid opening, only "Technical Attachment" will be opened. Bidders therefore should ensure that technical bid is uploaded in the "Technical Attachment" Tab Page only in the E-portal.
- 19.2 In case of any unscheduled holiday or Bandh on the Bid Opening Date, the Bids will be opened on the next full working day. Accordingly, Bid Closing Date / time will get extended up to the next working day and time.
- 19.3 Bids which have been withdrawn pursuant to clause 17.0 shall not be opened. Company will examine bids to determine whether they are complete, whether requisite Bid Securities have been furnished, whether documents have been digitally signed and whether the bids are generally in order.
- 19.4 At bid opening, Company will announce the Bidder's names, written notifications of bid modifications or withdrawal, if any, the presence of requisite Bid Security, and such other details as the Company may consider appropriate.
- Normally no clarifications shall be sought from the Bidders. However, for assisting in the evaluation of the bids especially on the issues where the Bidder confirms compliance in the evaluation and contradiction exists on the same issues due to lack of required supporting documents in the Bid (i.e. document is deficient or missing), or due to some statement at other place of the Bid (i.e. reconfirmation of confirmation) or vice versa, clarifications may be sought by OIL. In all the above situations, the Bidder will not be allowed to change the basic structure of the Bid already submitted by them and no change in the price or substance of the Bid shall be sought, offered or permitted.
- 19.6 Prior to the detailed evaluation, Company will determine the substantial responsiveness of each bid to the requirement of the Bid Documents. For purpose of these paragraphs, a substantially responsive bid is one, which conforms to all the terms and conditions of the Bid Document without material

deviations or reservation. A material deviation or reservation is one which affects in any substantial way the scope, quality, or performance of work, or which limits in any substantial way, in-consistent way with the Bid Documents, the Company's right or the bidder's obligations under the contract, and the rectification of which deviation or reservation would affect unfairly the competitive position of other bidders presenting substantial responsive bids. The Company's determination of Bid's responsiveness is to be based on the contents of the Bid itself without recourse to extrinsic evidence.

- 19.7 A Bid determined as not substantially responsive will be rejected by the Company and may not subsequently be made responsive by the Bidder by correction of the non-conformity.
- 19.8 The Company may waive minor informality or nonconformity or irregularity in a Bid, which does not constitute a material deviation, provided such waiver, does not prejudice or affect the relative ranking of any Bidder.

20.0 Opening of priced bids:

- 20.1 Company will open the Priced Bids Company will open the Priced Bids on the same date as technical bids. In case of any unscheduled holiday or Bandh on the Priced Bid Opening Date, the Bids will be opened on the next working day.
- 20.2 The Company will examine the Price quoted by Bidders to determine whether they are complete, any computational errors have been made, the documents have been properly signed, and the bids are generally in order.
- Arithmetical errors will be rectified on the following basis. If there is a discrepancy between the unit price and the total price (that is obtained by multiplying the unit price and quantity) the unit price shall prevail and the total price shall be corrected accordingly. If there is a discrepancy between words, and figures, the amount in words will prevail. If any Bidder does not accept the correction of the errors, their Bid will be rejected.

21.0 DELETED

22.0 Evaluation and comparison of bids:

The Company will evaluate and compare the bids as per BID EVALUATION CRITERIA (BEC), PART-2 of the Bid Documents.

22.1 Discounts / rebates

- 22.1.1 Unconditional discounts/rebates, if any, given in the bid will be considered for evaluation.
- 22.1.2 Post bid or conditional discounts/rebates offered by any bidder shall not be considered for evaluation of bids. However, if the lowest bidder happens to be

the final acceptable bidder for award of contract, and if they have offered any discounts/rebates, the contract shall be awarded after taking into account such discounts/rebates.

- 22.2 DELETED
- 22.3 DELETED
- 22.4 DELETED

23.0 Contacting the company:

- 23.1 Except as otherwise provided in Clause 19.0 above, no Bidder shall contact Company on any matter relating to its bid, from the time of the bid opening to the time the Contract is awarded except as required by Company vide subclause 19.5.
- 23.2 An effort by a Bidder to influence the Company in the Company's bid evaluation, bid comparison or Contract award decisions may result in the rejection of their bid.

24.0 Award of contract:

24.1 Award criteria

24.1.1 The Company will award the Contract to the successful Bidder whose bid has been determined to be substantially responsive and has been determined as the lowest evaluated bid, provided further that the Bidder is determined to be qualified to perform the Contract satisfactorily.

25.0 Company's right to accept or reject any bid:

Company reserves the right to accept or reject any or all bids and to annul the bidding process and reject all bids, at any time prior to award of contract, without thereby incurring any liability to the affected bidder, or bidders or any obligation to inform the affected bidder of the grounds for Company's action.

26.0 Notification of award:

- 26.1 Prior to the expiry of the period of bid validity or extended validity, Company will notify the successful Bidder in writing by registered letter or by fax or E-mail (to be confirmed in writing by registered / couriered letter) that its Bid has been accepted.
- 26.2 The notification of award will constitute the formation of the Contract.

Upon the successful Bidder's furnishing of Performance Security pursuant to Clause 27.0 below, the Company will promptly notify each un-successful Bidder and will discharge their Bid Security, pursuant to Clause 10.0 hereinabove.

27.0 Performance security:

Successful bidder has to submit Performance Security amount as mentioned in GCC clause no. 10.0.

28.0 Signing of contract:

- At the same time as the Company notifies the successful Bidder that its Bid has been accepted, the Company will either call the successful Bidder for signing of the agreement or send the Contract Form provided in the Bid Documents, along with the General & Special Conditions of Contract, Technical Specifications, Schedule of Rates incorporating all agreements agreed between the two parties.
- 28.2 The successful Bidder shall sign and date the contract and return it to the Company after receipt of LOA. Till the contract is signed, the LOA issued to the successful bidder shall remain binding amongst the two parties.
- In the event of failure on the part of the successful Bidder to sign the contract, OIL reserves the right to terminate the LOA issued to the successful Bidder and invoke the Bid Security or the Performance Security if submitted by the successful Bidder. The party shall also be debarred for a period of 2(two) years from the date of default.

(Signing of the Contract may be done at the place of award in presence of both parties)

29.0 Credit facility:

Bidders should indicate clearly in the Bid about availability of any credit facility inclusive of Government to Government credits indicating the applicable terms and conditions of such credit.

30.0 Mobilisation and advance payment:

- 30.1 Request for advance payment shall not be normally considered. However, depending on the merit and at the discretion of the Company, advance against mobilisation charge may be given at an interest rate of 1% above the prevailing Bank rate (CC rate) of SBI from the date of payment of the advance till recovery/refund.
- Advance payment agreed to by the Company shall be paid only against submission of an acceptable bank guarantee whose value should be equivalent to the amount of advance plus the amount of interest covering the period of advance. Bank guarantee shall be valid for 2 months beyond completion of

mobilisation and the same may be invoked in the event of Contractor's failure to mobilise as per agreement.

30.3 In the event of any extension to the mobilisation period, Contractor shall have to enhance the value of the bank guarantee to cover the interest for the extended period and also to extend the validity of bank guarantee accordingly.

31.0 Integrity pact:

- OIL shall be entering into an Integrity Pact with the Bidders as per format enclosed vide Proforma-M of the Bid Document. The Integrity Pact has been duly signed digitally by OIL's competent signatory and uploaded in the OIL's e-portal. The Integrity Pact shall be returned by the bidder (along with the technical Bid) duly signed by the same signatory who signed the Bid i.e. who is duly authorized to sign the Bid. Uploading the Integrity Pact in the OIL's E-portal with digital signature will be construed that all pages of the Integrity Pact has been signed by the bidder's authorized signatory who has signed the bid. If any bidder refuses to sign Integrity Pact or declines to submit the Integrity Pact, their bid shall be rejected straightway.
- 31.2 Bidders may contact the Independent External Monitors for any matter relating to the IFB at the following addresses:
 - a. Shri Sutanu Behuria, IAS (Retd.); Ex-Secretary, Dept. of Heavy Industry, Ministry of Heavy Industries & Public Enterprises, E-mail: sutanu2911@gmail.com
 - b. Shri Rudhra Gangadharan, IAS(Retd.), Ex-Secretary, Ministry of Agriculture; E-Mail: rudhra.gangadharan@gmail.com
 - c. Shri Om Prakash Singh, IPS (Retd.), Former DGP, Uttar Pradesh, E-mail: Ops2020@rediffmail.com

32.0 Local conditions:

It is imperative for each Bidder to be fully informed themselves of all Indian as well as local conditions, factors and legislation which may have any effect on the execution of the work covered under the Bidding Document. The bidders shall be deemed, prior to submitting their bids to have satisfied themselves of all the aspects covering the nature of the work as stipulated in the Bidding Document and obtain for themselves all necessary information as to the risks, contingencies and all other circumstances, which may influence or affect the various obligations under the Contract.

No request will be considered for clarifications from the Company (OIL) regarding such conditions, factors and legislation. It is understood and agreed that such conditions, factors and legislation have been properly investigated

and considered by the Bidders while submitting the Bids. Failure to do so shall not relieve the Bidders from responsibility to estimate properly the cost of performing the work within the provided timeframe. Company (OIL) will assume no responsibility for any understandings or representations concerning conditions made by any of their officers prior to award of the Contract. Company (OIL) shall not permit any Changes to the time schedule of the Contract or any financial adjustments arising from the Bidder's lack of knowledge and its effect on the cost of execution of the Contract.

33.0 Specifications:

Before submission of Bids, Bidders are requested to make themselves fully conversant with all Conditions of the Bid Document and other relevant information related to the works/services to be executed under the contract.

<u>END OF PART - 1</u> &&&&

PART-2 BID EVALUATION CRITERIA (BEC)

A) GENERAL CONFORMITY:

The bid shall conform generally to the specifications and terms and conditions given in this bid document. Bids shall be rejected in case the services offered do not conform to required parameters stipulated in the technical specifications. Notwithstanding the general conformity of the bids to the stipulated specifications, the following requirements will have to be particularly met by the Bidders without which the same will be considered as non-responsive and rejected.

B) TECHNICAL:

Bidder must meet the following minimum criteria failing which offer shall be rejected:

This tender is being floated on limited tendering basis to the shortlisted vendors as mentioned herein with a provision for other potential bidders meeting the following BEC Criteria to submit their bids along with all supporting documents.

The Bidders to whom this tender has been issued as mentioned in the NIT should only give an **undertaking** (as per **ANNEXURE-VI**) towards fulfilment of the Clause Nos. 1.0 to 7.0 below. However, bidders other than the ones listed in the NIT are required to submit all the requisite supporting documents towards fulfilment of the following clauses, along with their bids. Notwithstanding above, OIL reserves the right to seek clarifications including submission of any or all documents even from the already shortlisted bidders to evaluate and ascertain suitability of their bids.

1.0 The bidder shall have at least 2(two) years experience of providing Drilling / Work-over services to oil (E&P) Company with charter hired rig in the last 7 years as on the Bid Closing Date (Technical).

2.0 **FINANCIAL CRITERIA**:

2.1 The bidder must have minimum **annual financial turnover** as mentioned below in any of preceding three financial/accounting years reckoned from the original bid closing date as per the Audited Annual Reports:

No. of Rigs offered	Annual Financial Turnover
1 No.	INR 3,96,50,000.00
2 Nos.	INR 7,93,00,000.00

2.2 **Net worth** of bidder for the accounting year preceding the original bid closing date should be minimum:

No. of Rigs offered	Net Worth
1 No.	INR 1,19,00,000.00
2 Nos.	INR 2,38,00,000.00

[Net worth shall mean: "Share capital + Reserves created out of profits and securities Premium – Aggregate value of accumulated losses - account (excluding revaluation reserves) – deferred expenditure – Miscellaneous Expenditure to the extent not written off and carried forward Loss - Reserves created out of write back of depreciation and amalgamation".]

2.3 **Working Capital**: The Bidder should at least have working capital as mentioned below for the accounting year preceding the original bid closing date:

No. of Rigs offered	Working Capital
1 No.	INR 1,19,00,000.00
2 Nos.	INR 2,38,00,000.00

Note: Working Capital shall mean "Current Assets minus Current liabilities" as per latest year's audited consolidated annual Financial Statements.

2.4 <u>Bid Capacity</u>: The bidding capacity of the contractor should be equal to or more than the following:

No. of Rigs offered	Bid Capacity
1 No.	INR 7,93,50,000.00
2 Nos.	INR 15,87,00,000.00

The bidding capacity shall be worked out by the following formula:

Bidding Capacity = $[A \times 1.5] - B$

Where,

- A = Maximum annual turnover in any one of the preceding three financial years.
- B = Commitments in next twelve months from the date of expiry of the bid validity as per **Annexure-VIII**.
- 2.5 <u>Debt equity ratio</u>: Debt equity ratio of the bidder should not be more than 2:1.Debt equity ratio shall mean long term borrowings/ Net-worth.
- 2.6 Considering the time required for preparation of Financial Statements, if the last date of preceding financial / accounting year falls within the preceding six months reckoned from the original bid closing date and the Financial Statements of the preceding financial / accounting year are not available with the BIDDER, then the financial turnover of the previous three financial/accounting years excluding the preceding financial / accounting year will be considered. In such cases, the Net worth of the previous financial/ accounting year excluding the preceding financial / accounting year will be considered. However, the BIDDER has to submit an affidavit/undertaking certifying that the balance sheet/Financial Statements for the financial year _______ (as the case may be) has actually not been audited as on the Original bid closing date as per format.

Notes:

- (a) For proof of Annual Turnover & Net worth any one of the following documents must be submitted along with the bid:
 - (i) A certificate issued by a practicing Chartered/Cost Accountant (with Membership Number and Firm Registration Number), certifying the Annual turnover & Net worth as per format prescribed in **ANNEXURE-VII**.

OR

- (ii) Audited Balance Sheet along with Profit & Loss account. In case of foreign bidders, self-attested/digitally signed printed published accounts are also acceptable.
- (b) In case the bidder is a Central Govt. Organization/PSU /State Govt. Organization / Semi-State Govt. Organization or any other Central/State Govt. Undertaking, where the auditor is appointed only after the approval of Comptroller and Auditor General of India and the Central Government, their certificates may be accepted even though FRN is not available. However, bidder has to provide documentary evidence for the same.

3.0 **WORKOVER RIG:**

3.1 The bidder shall be in possession of the rigs offered.

3.2 Identification of rig:

- i) All the bidders are required to identify the rigs at the time of submission of bid with documentary proof thereof, confirming availability of the rigs for this contract.
- ii) In case owner of the rigs himself is the bidder, the certificate confirming availability of the rigs for this contract, shall be furnished by owner himself along with the bid.
- 3.3 The horsepower rating of the rigs offered should be between **550 HP** (Minimum)-**750 HP** (Maximum). Further, the rigs offered should be self elevating mast and sub-structure (as per API standard). The details of the rigs are given in Section-II, Terms of Reference and Technical Specification.
- 3.4 **Vintage**: The Work-over Rig units including the accessories and equipment offered should not be older than 15(Fifteen) years from the date of original bid closing date.
- 3.5 Bidder must confirm to provide 1(one) or 2 (two) complete rig packages as specified under Section-II of the bidding document.
- 4.0 Bidder while submitting the documents in support of their experience vide Clause 1.0 above shall also submit details of experience and past performance or the collaborator (in case of collaboration) or of joint venture partner (in case of a joint venture), or Leader of the consortium (in case of Consortium bid) on works/jobs

done of similar nature in the past along with the technical bid. Also, details of current work in hand and other contractual commitments of the bidder (indicating areas and clients) are to be submitted along with documentary experience in the technical bid in support of the experience laid down in Para 1.0 above.

- 5.0 The bidder must confirm to provide the key personnel with requisite experience and qualification as specified in Clause 7.18 L (personnel to be deployed) under Section-II, Terms of Reference/Technical Specification.
- 6.0 Offers indicating **mobilization time** of more than **60 days** from the date of issuance of LOA (Letter of Award) will be summarily rejected.

7.0 **DOCUMENTS:**

- 7.1 Bidders must furnish documentary evidences in support of fulfilling all the above requirement as under:
 - (a) Rigs offered documents relating to rigs already in possession along with technical specifications / details.
 - (b) Vintage of the offered rig as per Para 3.4 above.
 - (c) Drilling/Workover experience of bidder- Statement to be furnished by bidder in a tabular form along with copies of contracts / work orders (with detailed scope of work and contract duration), completion certificates / payment certificates issued by the clients.
 - (d) Financial turnover of bidder- Audited balance sheets / profit and loss accounts etc.
 - All documents submitted with bid must be self-certified by the bidder's authorized person signing the bid.

8.0 <u>VERIFICATION AND CERTIFICATION OF DOCUMENTS BY INDEPENDENT</u> THIRD PARTY INSPECTION AGENCIES:

- 8.1 Oil India Limited (OIL) has engaged the following 09 (Nine) Independent Inspection Agencies for a period of 04 (four) years with effect from 06.05.2020 to verify and certify various documents required against BEC/BRC of the tender:
 - i. M/s. RINA India Pvt. Ltd.
 - ii. M/s. Dr. Amin Controller Pvt. Ltd.
 - iii. M/s. Germanischer Llyod Industrial Services GmbH (DNV GL Oil & Gas)
 - iv. M/s. TÜV SÜD South Asia Pvt. Ltd.
 - v. M/s. IRCLASS Systems and Solutions Private Limited
 - vi. M/s. Gulf Llyods Industrial Services (India) Pvt. Ltd.
 - vii. M/s. TUV India Private Limited
 - viii. M/s. TÜV Rheinland (India) Pvt. Ltd.
 - ix. M/s. Bureau Veritas (India) Private Limited

- 8.2 The Bidders have to get verified and certified the various documents required against BEC/BRC of the tender by anyone of the above Independent Inspection Agencies and submit the duly certified Inspection Certificate by the Inspection Agencies along with the Technical Bid of the Tender. All Charges of the Third-party Independent Inspection Agencies towards verification of bidder's documents and certification thereof shall be borne by the respective bidders and Payments on account of above inspection, verification and certification shall be made directly by the Bidder to the Inspection Agency(s). OIL will not be responsible for any payment dispute between Bidders and Third Party Inspection Agencies.
- 8.3 As mentioned above, Bidder(s) have to submit the verified documents along with the Technical Bids. Bid submitted with un-verified supporting documents shall not be normally considered. However, in case a bidder submits its bid alongwith all relevant supporting documents as per BEC/BRC without getting all/some of them verified by the designated Independent Inspection agency, such bid can be provisionally considered provided it is accompanied by an Undertaking by the Bidder on their official letterhead to submit the duly verified copies/verification certificate within seven (7) days of actual bid opening. Company will neither send any reminder nor seek any clarification in this regard from such bidders, and the bid will be rejected outright if the bidder fails to submit the verified copies/verification certificate within seven (7) days of actual bid opening at its own risk and responsibility. If a bidder does not submit the undertaking towards submission of third party certification within 7 days from date of Bid Closing date, but certified document reaches us within the cut-off date of above seven (7) days, then such bids shall be considered.
- 8.4 The methodology of inspection/ verification of documents followed by the agencies is broadly as under but not limited to:
- (a) Oil India Limited will incorporate a relevant clause in the tender along with the list of empanelled inspection agencies where document verification pertaining to BEC/BRC of the tender is required. The prospective bidder will contact any of the empanelled inspection agencies against such tender. When prospective bidders approach any of the OIL's empanelled Inspection Agency, the agency will ask for the tender document and should go through the Tender Document, especially the requirements of BEC/BRC and list the documents to be verified. The inspection Agency shall depute their qualified/competent inspector to the Bidder's premises to check the original documents and certify the copies which the bidder shall submit along with their bids. OIL will reserve the right to ask the inspection agencies to verify the documents with source, if required at no extra cost to OIL. A copy of the Inspection Certificate shall be directly sent to the Concerned Tendering officer of OIL INDIA LIMITED, mentioned in the respective tender.

(b) Verification of documents are normally categorised as under:

> General Requirement:

- · Check Bidder's PAN Card
- Check Bidder's GST Certificate
- Check ITR of company last three years (minimum)
- Check Bidder's Certificate of Incorporation Domestic Bidder.

> Additional Documents : (If applicable against the tender)

- Joint Ventures Agreements To Double-check with JV Partners
- Consortium Agreements To Double-check with Consortium Partners
- Holding/ Parent/Subsidiary Company To check the notarized Share Holding pattern

> Technical Criteria

- Experience Proof To check Original Work Order as per BEC /criteria
- To check Company Name
- To check Similar Work Definition against Work Order, Scope of work (JV or Consortium too)
- To check the Execution period
- To Check the Completion Certificates Letter of Appreciations of proper Execution
- Reference contact verification and true copy verification
- Match Original Work Order/Contract Copy with Soft Copies or notarized scan copies

> Financial Criteria

• Check Audited Balance Sheet – Turnover as per BEC along with the bidder's compliance with respect to the following clause:

Considering the time required for preparation of Financial Statements, if the last date of the preceding financial / accounting year falls within the preceding six months reckoned from the original bid closing date and the Financial Statements of the preceding financial / accounting year are not available with the bidder, then the financial turnover of the previous three financial/accounting years excluding the preceding financial / accounting year will be considered. In such cases, the Net worth of the previous financial / accounting year will be considered. However, the bidder

has to submit an affidavit/undertaking certifying that 'the balance sheet/Financial Statements for the financial year ______ (as the case may be) has actually not been audited as on the Original bid closing date as per format'.

- Check Net-Worth, Working Capital etc. as per BEC
- Check Notarization validity
- Check original audited Balance Sheet with scan copies.
- To check the Line of Credit, if incorporated in the tender.

C) COMMERCIAL BID EVALUATION:

- 1.0 Bids shall be submitted under Composite Bid system i.e. Technical Bid and Priced Bid together in the OIL's e-Tender portal. The Technical Bid is to be uploaded as per Scope of Work & Technical Specification of the tender in "Technical RFx Response" Tab and Priced Bid as per Proforma-B uploaded in the "Notes & Attachments" Tab.
- 2.0 Bidder shall offer firm prices. Price quoted by the successful bidder must remain firm during the execution of the contract and not subject to variation on any account.
- 3.0 Bids should be valid for 120 days. Bids with shorter validity will be rejected as being non-responsive.
- 4.0 The Integrity Pact must be uploaded in OIL's E-Procurement portal along with the Technical Bid digitally signed by the same signatory who digitally signed the Bid i.e. who is duly authorized to sign the Bid. If any bidder refuses to sign Integrity Pact or declines to submit the Integrity Pact, their bid will be rejected.
- 5.0 Bids submitted after the Bid Closing Date and Time will be rejected.
- 6.0 Bids received through the e-procurement portal shall only be accepted. Bids received in any other form shall not be accepted.
- 7.0 The bid documents are non-transferable. Bid can only be submitted in the name of the bidder in whose name the User ID and Password have been issued. Unsolicited bids will not be considered and will be straightway rejected.
- 8.0 Bid documents shall be typed or written in indelible ink and shall be digitally signed by the bidder or his authorised representative.
- 9.0 Any physical documents wherever called for, submitted by bidders shall contain no interlineations, white fluid erasures or overwriting except as necessary to correct errors made by the Bidder, in which case such correction shall be initialled by the person or persons who has/have digitally signed the Bid.
- 10.0 Any Bid containing false statement will be rejected.

- 11.0 Bidders must quote clearly and strictly in accordance with the price schedule outlined in "Price Bid Format" of Bid Document, otherwise the Bid will be summarily rejected.
- 12.0 Bidder must accept and comply with the following clauses as given in the Bid Document in toto failing which bid will be rejected:
 - i) Performance Guarantee Clause
 - ii) Force Majeure Clause
 - iii) Tax Liabilities Clause
 - iv) Arbitration Clause
 - v) Acceptance of Jurisdiction and Applicable Law
 - vi) Liquidated damage and penalty clause
 - vii) Safety, Environment & Labour Law
 - viii) Termination Clause
 - ix) Integrity Pact
- 13.0 The Bids and all uploaded documents must be digitally signed using "Class 3" digital certificate [e-commerce application (Certificate with personal verification and Organization name)] as per Indian IT Act obtained from the licensed Certifying Authorities operating under the Root Certifying Authority of India (RCAI), Controller of Certifying Authorities (CCA) of India.

D) <u>BID EVALUATION CRITERIA:</u>

The bids conforming to the technical specifications, terms and conditions stipulated in the bidding document and considered to be responsive after subjecting to Bid Rejection Criteria will be considered for further evaluation as per the Bid Evaluation Criteria given below:

- 1.0 If there is any discrepancy between the unit price and the total price, the unit price will prevail and the total price shall be corrected. Similarly, if there is any discrepancy between words and figure, the amounts in words shall prevail and will be adopted for evaluation.
- 2.0 Bidder shall quote same rates for all the Rigs quoted by them. Bidders quoting different rates (either total or individual item rate) would be rejected.
- 3.0 Bids will be evaluated considering 01 No. of Rig for 03(Three) years of operation. L-1 bidder will be offered the contract for maximum of 02 Nos. of Rigs, if L-1 bidder quotes for 02 Nos. of Rigs, else 01 No. Rig (Min. quote). If L-1 Bidder quote for 01 No. of Rig, the balance 01 No. of Rig will be offered to L-2 bidder subject to matching their price to L-1 value. If the L-2 bidder refuses to match their price to L-1 value, then the offer will be made to L3 bidder and so on. For matching of price, if Operating Day Rate is higher, it will be reduced to L1 rate and balance items will be proportionately reduced to match the total L-1 quoted value. However, if ODR rate is lower, reduction in rates will be done for only balance items by proportionately reducing their rates to match the L-1 quoted value. For matching the rate a timeframe of 15 days will be provided to the bidders and in the event of non-acceptance or non-response within the allotted 15 days, the same will be offered to the next eligible bidder.

- 4.0 The contracts will be signed with successful bidders for 03(Three) years of operation.
- 5.0 The rates towards Standby, Repair, Force Majeure and Fishing will be restricted to the limit indicated against each as under:
 - 1. Payment towards mobilisation of each rig package shall not exceed 7.5% of the total contract price for 3 years for one rig. However, mobilization charges if quoted in excess of 7.5% of the estimated contract cost, the excess amount shall be paid at the end of the contract.
 - 2. Payment towards Standby time rate shall be 70% of the operating day rate.
 - 3. Payment towards rig Repair day rate shall be 60% of operating day rate.
 - 4. Payment towards Force Majeure day rate shall be 50% of operating day rate.
 - 5. Payment towards Fishing day rate shall be as per Section-IV: Schedule of Rates.
- 6.0 The quantities shown against each item in the "Price Bid Format (i.e. in Proforma-B)" shall be considered for the purpose of Bid Evaluation. It is, however, to be clearly understood that the assumptions made in respect of the number of days/parameters for various operations are only for the purpose of evaluation of the bid and the Contractor will be paid on the basis of the actual number of days/parameter, as the case may be.
- 7.0 The bidders must quote their charges / rates in the manner as called for vide "Schedule of Rates" under Section-IV and the summarized price schedule format vide enclosed Proforma-B.
- 8.0 To ascertain the inter-se-ranking, the comparison of the responsive bids will be made subject to loading for any deviation. Commercial Bids shall be evaluated taking into account the rates quoted in the PRICE BID FORMAT (Proforma-B) by taking into account the summation of the following:

TOTAL ESTIMATED CONTRACT COST FOR 1 RIG FOR 3 YEARS CONTRACT including all Taxes & Duties including GST:

TCROG = TCRO+GST = TM + TD + TOC + TLA + TLB + TLC + TCS + GST

Where,

- a. Total Mobilization Charge for 1 rig, $TM = M \times 1$
- b. Total Demobilization Charge for 1 rig, TD = D x 1
- c. Total Operating Day rate for 1 rig, TOC = OC x 960 days
- d. Total Inter-Location movement Charges for 1 rig, TLA = LA \times 21 (No. of ILM within a distance of 50 KMs)
- e. Total Inter-Location Movement Charges for 1 rig on kilometerage basis for movement in excess of 50 KM, TLB = LB x 600
- f. Total Inter-Location Movement Charge for 1 rig, TLC = LC x 03 (No. of ILM for Cluster Location)

g. Total Catering Charge, TCS = CS x 3000 (no. of catering charge per person per day)

Where,

M = Lumpsum amount for each rig mobilization along with equipment and services as per Section-II

D = Lumpsum amount for each rig demobilization along with equipment and services as per Section-II

OC = Operating Charges per day per Rig

LA = Charges per ILM (within 50 KM)

LB = Charges in excess of 50 KM

LC = Charges per ILM for Cluster Location

CS = Catering Charge per person per day

E) GENERAL

- 1.0 In case bidder takes exception to any clause of bid document not covered under BEC, then the Company has the discretion to load or reject the offer on account of such exception if the bidder does not withdraw/modify the deviation when/as advised by company. The loading so done by the Company will be final and binding on the bidders.
- 2.0 To ascertain the substantial responsiveness of the Bid the Company reserves the right to ask the bidder for clarification in respect of clauses covered under BEC also and such clarifications fulfilling the BEC clauses in toto must be received on or before the deadline given by the Company, failing which the offer will be summarily rejected.
- 3.0 If any of the clauses in the BEC contradict with other clauses of the Bid Document elsewhere, then the clauses in the BEC shall prevail.
- 4.0 **CUSTOMS DUTY**: In terms of Sl. No. 404 of the Customs Notification No.50/2017-Customs dated 30.06.2017, imports of the items specified in List 33 of the Notification are subject to levy of concessional rate of customs duty @5% (BCD Nil & IGST @5%) subject to conditions specified therein (Condition No. 48). However, this is subject to change as per Government guidelines and the provisions ruling at the time of tender closing will be applicable.

Similarly, the domestic supply of such goods would attract 5% GST (i.e. IGST or CGST & SGST/UTSGT) on submission of EC in terms of GST Notification No. 03/2017.

<u>Note</u>: The Bidder has to re-export the rigs after completion of the contract in case of imported rigs. The bidder will be fully responsible to pay the customs duty in case the rigs are taken by the Contractor to area where customs duty benefit is not applicable. This is applicable in case OIL issues recommendatory letter for availing concessional customs duty for import of goods.

5.0 **PURCHASE PREFERENCE CLAUSE FOR MSE**:

Purchase Preference to Micro and Small Enterprises registered with District Industry Centres or Khadi and Village Industries Commission or Khadi and Village Industries Board or Coir Board or National Small Industries Corporation or

Directorate of Handicrafts and Handloom or any other body specified by Ministry of MSME.

- 5.1 In case participating MSEs quote price within price band of L1+15%, such MSE shall be considered for award of contract by bringing down their price to L1 price in a situation where L1 price is from someone other than a MSE.
- 5.2 In case of more than one such MSE qualifying for 15% purchase preference, the contract shall be awarded to lowest eligible MSE amongst the MSEs qualifying for 15% purchase preference.
- 5.3 In case any part of the work is sub-contracted to a Micro or Small Enterprise as per contract conditions then the contractor shall provide complete details (i.e. name of the subcontractor, value of sub-contacted work, copy of valid registration certificate etc.) of the sub-contractor to OIL.
- 5.4 DOCUMENTATION REQUIRED TO BE SUBMITTED BY MSEs:

Categorisation and various criteria applicable to MSE bidders shall be guided by the Gazette Notification No. CG-DL-E-26062020-220191 dated 26.06.2020 issued by MINISTRY OF MICRO, SMALL AND MEDIUM ENTERPRISES. The existing enterprises registered under EM-Part-II or UAM till 30th June 2020 shall continue to be valid only for period up to the 31st day of March, 2021.

The bidder claiming as MSE status (MSE-General, MSE-SC/ST, MSE-Woman) against this tender has to submit the following documents for availing the benefits applicable to MSEs:

i. Udyam Registration Number with Udyam Registration Certificate.

Or

ii. Proof of registration with District Industry Centres or Khadi and Village Industries Commission or Khadi and Village Industries Board or Coir Board or National Small Industries Corporation or Directorate of Handicrafts and Handloom or Udyog Adhaar registration or registration with any other body specified by Ministry of MSME.

<u>Note</u>: In case bidding MSE is owned by Schedule Caste or Schedule Tribe entrepreneur or Woman Entrepreneur, valid documentary evidence issued by the agency who has registered the bidder as MSE owned by SC/ST entrepreneur/Woman Entrepreneurs should also be enclosed.

COMPLIANCE OF THE COMPETITION ACT, 2002: The bidder shall strictly comply with the provisions of the Competition Act, 2002, more particularly, Section-3 of the Act. Any violation of the provisions of the Act shall attract penal action under the Act.

END OF PART-2 &&&&

<u>Part-3</u> <u>SECTION-I</u> GENERAL CONDITIONS OF CONTRACT (GCC)

1.0 APPLICABILITY, DEFINITION & INTERPRETATION

1.1 Applicability

All clauses in the General Conditions of Contract [GCC] shall apply to all transactions except as otherwise stated in the Special Conditions of Contract [SCC] and/or BEC/BRC. Furthermore, in the event if there is any conflict between the Principal text of the Agreement and the Appendixes, the Principal text will prevail.

1.2 Definition & Interpretation

In the contract (as hereinafter defined) the following words and expressions shall have the meaning hereby assigned to them except where the context otherwise requires:

1.2.1 COMPANY/OIL/Operator:

Shall mean Oil India Limited [OIL] a public sector undertaking, incorporated under COMPANY's Act 1956 having its registered office at Duliajan-786602, Assam, India and includes its successor and permitted assigns.

1.2.2 CONTRACTOR:

Shall mean the person or persons, firm or COMPANY or corporation incorporated in India or abroad, who has been awarded with the contract and includes contractor's legal representatives, his successors and permitted assigns.

1.2.3 Contract:

Shall mean a written agreement between the COMPANY and the CONTRACTOR for execution of the services/works including all contract documents and subsequent amendments, if any.

1.2.4 Site:

Shall mean the place in which the operations/services are to be carried out or places approved by OIL for the purposes of the CONTRACT together with any other places designated in the CONTRACT as forming part of the site.

1.2.5 COMPANY's Site Representative/Engineer:

Shall mean the person or the persons appointed by the COMPANY from time to time to act on its behalf at the site for overall co-ordination, supervision and project management at site.

1.2.6 Sub-Contract:

Shall mean order/contract placed by the CONTRACTOR for any portion of the CONTRACT or work sublet with necessary written consent of COMPANY on third

party. Such sub-letting shall not relieve the CONTRACTOR from any obligation, duty or responsibility under the CONTRACT.

1.2.7 Sub-Contractor:

Shall mean any person or firm or COMPANY (other than CONTRACTOR) to whom any part of the work has been entrusted by CONTRACTOR, with written consent of OIL or the persons appointed by OIL, successors and permitted assigns of such persons, firm or COMPANY).

1.2.8 Contractor's Representative:

Shall mean such person/or persons duly appointed representative at the site and base as the CONTRACTOR may designate in writing to the COMPANY as having authority to act for the CONTRACTOR in matters affecting the work and to provide the requisite services.

1.2.9 Contract Price/Value:

Shall mean the sum accepted or the sum calculated in accordance with the rates accepted in tender and/or the contract rates as payable to the CONTRACTOR for the entire execution and completion of the services/works, including amendments/modification/change order issued by the COMPANY.

1.2.10 Firm price:

The prices will remain unchanged, except for statutory changes, during currency of the CONTRACT unless specifically agreed to in writing by COMPANY.

1.2.11 Service/Works/Operations:

Shall mean and include all items and things to be supplied/done and all work/Service to be performed by the CONTRACTOR as specified in the Scope of Work under this CONTRACT and shall also include all extra, additional, altered or substituted works/services as required for the purpose of successful execution of the Contract.

1.2.12 Equipment/Materials/Goods:

Shall mean and include any equipment, machinery, instruments, stores, goods which CONTRACTOR is required to provide to the COMPANY for/under the CONTRACT and amendments thereto.

1.2.13 Drawings:

Shall mean and include all Engineering sketches, general arrangements/layout drawings, sectional plans, all elevations, photographs, etc. related to the CONTRACT together with modification and revision thereto.

1.2.14 Specifications:

Means and includes all technical specifications, provision attached and referred to in the tender/contract document regarding method and manner of performing the services and qualities of the service/materials to be provided under the contract and also as modified by the COMPANY/its site representative during the execution of contract in the best interest of service.

1.2.15 Engineer In-charge (EIC):

Shall mean the person designated from time to time by the COMPANY and shall include those who are expressly authorized by the COMPANY to act for and on its behalf for operation of the contract.

1.2.16 Inspectors:

Shall mean any person or outside Agency nominated by COMPANY to inspect equipment, materials and services, if any, in the CONTRACT (stage wise as well as final) as per the terms of the CONTRACT.

1.2.17 Tests:

Shall mean such process or processes to be carried out by the CONTRACTOR as are prescribed in the CONTRACT, considered necessary by the COMPANY or their representative to ascertain quality, workmanship, performance and efficiency of equipment or services thereof.

1.2.18 Approval:

Shall mean and include the written consent duly signed by COMPANY or their authorized official in respect of all documents, drawings or other particulars in relation to the CONTRACT.

1.2.19 Day:

Shall mean a calendar day of twenty–four (24) consecutive hours beginning at 00:00 hours with reference to local time at the site.

1.2.20 Month:

Shall mean a calendar month as per Gregorian calendar.

1.2.21 Year:

Shall mean calendar year as per Gregorian calendar.

1.2.22 Working day:

Means any day which is not declared to be holiday by the COMPANY.

1.2.23 Bid/offer:

Shall mean the proposal/Offer along with supporting documents submitted by the bidder in response to the tender or enquiry in accordance with the terms of Tender or Enquiry, for consideration by COMPANY, prior to award of contract.

1.2.24 Guarantee:

Shall mean the period and other conditions governing the warranty/guarantee of the services as provided in the CONTRACT.

1.2.25 Mobilization:

Shall mean rendering the equipment fully manned and equipped as per CONTRACT and ready to begin work at site designated by the COMPANY and accepted by the COMPANY after inspection.

1.2.26 De-mobilization:

Shall mean the removal of all items forming part of the mobilization from the site of the COMPANY and inspection and acceptance thereafter by the COMPANY including compliance of requirement in relation to re-export of imported equipment/materials under concessional duty scheme in accordance with relevant notification from Customs Authorities.

1.2.27 Wilful Misconduct:

Shall mean intentional disregard of good and prudent standards of performance or proper conduct under the Contract with knowledge that it is likely to result in any injury to any person or persons or loss or damage of property of the Company or Third Party.

1.2.28 Gross Negligence:

Shall mean any act or failure to act (whether sole, joint or concurrent) by a person or entity which was intended to cause, or which was in reckless disregard of or unjustifiable indifference to, avoidable and harmful consequences such person or entity knew, or should have known, would result from such act or failure to act. Notwithstanding the foregoing, Gross negligence shall not include any action taken in good faith for the safeguard of life or property.

1.2.29 Criminal Negligence:

Shall mean that the crime happened negligently, there was duty of care upon the Person but inadvertently due to his negligence, the duty was breached, which causes harm to the people in the form of death or serious injury.

1.2.30 GST Legislations:

'GST legislations' means 'any or all of the following legislations as may be applicable to the CONTRACTOR and OIL:

- (A) The Central Goods & Services Tax Act, 2017;
- (B) The Integrated Goods & Services Act, 2017;
- (C) The Union Territory Goods & Services Tax Act, 2017;
- (D) The respective State Goods & Service Tax Acts'
- (E) The Goods and Services (Compensation to States) Act, 2017
- (F) The Customs Act and the Customs Tariff Act.
- (G) Any other applicable Act related to GST

2.0 CONTRACT DOCUMENT:

- **2.1 Governing language:** The governing language for the CONTRACT shall be English. All CONTRACT documents and all correspondence and communication to be given and all other documentation to be prepared and supplied under the CONTRACT shall be written in English and the CONTRACT shall be construed and interpreted in accordance with English language.
- **2.2 Entire Agreement:** The CONTRACT constitutes the entire agreement between OIL and the CONTRACTOR with respect to the subject matter of the CONTRACT and supersedes all communication, negotiations and agreement (whether written or oral) of the parties with respect thereto made prior to the date of this agreement, unless such communication(s) expressly forms part of the contract or included by reference.
- **2.3 Amendment in CONTRACT:** No Amendment of the Contract shall be valid unless it is in writing, is dated, expressly refers to the Contract, and is signed by a duly authorized representative of each party thereto. OIL shall not be bound by any printed conditions, provisions in the CONTRACTOR's BID, forms of acknowledgement of CONTRACT, invoice and other documents which purport to impose any condition at variance with or supplement to CONTRACT.

3.0 WAIVERS AND AMENDMENTS:

- **3.1 Waivers:** It is fully understood and agreed that none of the terms and conditions of this contract shall be deemed waived by either party unless such waiver is executed in writing only by the duly authorized representatives of both the parties. The failure of either party to execute any right shall not act as a waiver of such right by such party.
- **3.2 Change Program:** It is agreed that CONTRACTOR shall carry out work in accordance with the completion program (e.g. Drilling Programme) to be furnished by the COMPANY, which may be changed from time to time by reasonable modifications in the program as COMPANY sees fit. COMPANY's instruction in this regard shall be final and binding.

4.0 CONTRACT TIMELINE:

4.1 Effective Date of Contract:

The contract shall become effective as of the date COMPANY notifies the CONTRACTOR in writing that it has been awarded the contract. This date of issuance of Letter of Award (LOA) by the COMPANY will be the effective date of contract. All terms and conditions of the contract shall come into force with the date of issuance of LOA.

4.2 Date of Commencement of Operation:

The date on which the mobilization is completed in all respects and CONTRACTOR is ready to commence operation as per the contract provision [Certified by the COMPANY's representative] will be treated as the date of Commencement of Operation.

4.3 Duration of the contract:

The contract shall be valid for a period as defined in the LOA and Special Conditions of Contract [SCC].

5.0 SCOPE OF WORK/CONTRACT:

Scope of the CONTRACT shall be as defined in the CONTRACT, specifications, drawings and Appendices.

6.0 GENERAL OBLIGATION OF CONTRACTOR:

CONTRACTOR shall, in accordance with and subject to the terms and conditions of this Contract:

- **6.1** Perform the work described in the Terms of Reference/Scope of Work. The CONTRACTOR shall execute the work with professional competence and in an efficient and workman like manner.
- **6.2** Except as otherwise provided in the Terms of Reference and the special Conditions of the contract, employ all labours/personnel as required to perform the work.
- 6.3 Perform all other obligations, work and services which are required by the terms of this contract or which reasonably can be implied from such terms as being necessary for the successful and timely completion of the work.
- **6.4** Comply with all applicable statutory obligations specified in the contract.
- 6.5 CONTRACTOR shall be deemed to have satisfied himself before submitting their bid as to the correctness and sufficiency of its bid for the services required and of the rates and prices quoted, which rates and prices shall, except insofar as otherwise provided, cover all its obligations under the contract.
- 6.6 CONTRACTOR shall be deemed, prior to submitting their bids, to have satisfied themselves about the weather conditions, working culture in the area, sociopolitical environment, safety & security aspects, law & order situation and law of the land, and obtain for themselves all necessary information as to the risks, contingencies and all other circumstances, which may influence or affect the various obligations under the Contract.
- 6.7 CONTRACTOR shall give or provide all necessary supervision during the performance of the services and as long thereafter within the warranty period as

COMPANY may consider necessary for the proper fulfilling of CONTRACTOR's obligations under the contract.

7.0 GENERAL OBLIGATION OF COMPANY:

COMPANY shall, in accordance with and subject to the terms and conditions of this contract:

- **7.1** Pay CONTRACTOR in accordance with terms and conditions of the contract.
- 7.2 Allow CONTRACTOR access, subject to normal security and safety procedures, to all areas as required for orderly performance of the work as specified in the Scope of Works of the contract or work connected therewith.
- **7.3** Perform all other obligations required of COMPANY by the terms of this contract.

8.0 DUTIES AND POWER/AUTHORITY:

8.1 OIL's site representative/engineer:

The duties and authorities of OIL's site representative/engineer are to act on behalf of OIL for:

- (a) Overall supervision, co-ordination and Project Management at site.
- (b) Proper and optimum utilization of equipment and services.
- (c) Monitoring of performance and progress
- (d) Commenting/countersigning on reports made by the CONTRACTOR's representative at site in respect of works, receipts, consumption etc. after satisfying himself with the facts of the respective cases.
- (e) He shall have the authority, but not obligation at all times and any time to inspect/test/examine/verify any equipment machinery, instruments, tools, materials, personnel, procedures and reports etc. directly or indirectly pertaining to the execution of the work. However this shall not construe to imply an acceptance by the inspector. Hence, the overall responsibility of quality of work shall rest solely with the CONTRACTOR.
- (f) Each and every document emerging from site in support of any claim by the CONTRACTOR has to have the countersignature/comments of the OIL's representative/engineer without which no claim shall be entertained by the OIL.

8.2 CONTRACTOR's representative:

(a) The CONTRACTOR's representative shall have all the powers requisite for the performance of the Service/Works, subject to holding due authorization from the CONTRACTOR.

- (b) Representative(s) shall liaise with OIL's representative/engineer for the proper co-ordination and timely completion of the works and on any matter pertaining to the works.
- (c) Representative(s) shall extend full co-operation to OIL's representative/inspector/engineer in the manner required by them for supervision/inspection/observation of equipment, material, procedures, performance, reports and records pertaining to works.
- (d) To have complete charge of CONTRACTOR's personnel engaged in the performance of the work and to ensure compliance of rules and regulations and safety practice.

9.0 Personnel to be deployed by contractor:

CONTRACTOR warrants that it shall provide competent, qualified and sufficiently experienced personnel to perform the work correctly and efficiently.

- 9.1 The CONTRACTOR should ensure that their personnel observe all statutory safety requirement including those prescribed by the COMPANY. Upon COMPANY's written request, CONTRACTOR, entirely at its own expense, shall remove immediately any personnel of the CONTRACTOR determined by the COMPANY to be unsuitable and shall promptly replace such personnel with personnel acceptable to the COMPANY. Replacement personnel should be mobilized within 15 days from the date of issuance of notice without affecting the operation of the COMPANY.
- 9.2 The CONTRACTOR shall be solely responsible throughout the period of the contract for providing all requirements of their personnel including but not limited to, their transportation to & fro from Duliajan/field site, enroute/ local boarding, lodging, personal protective gear & medical attention etc. COMPANY shall have no responsibility or liability in this regard.
- **9.3** However, COMPANY shall provide available medical assistance/facilities to CONTRACTOR's Personnel in case of emergency at its own establishment on chargeable basis.
- **9.4** CONTRACTOR's key personnel shall be fluent in English language (both writing and speaking).

10.0 PERFORMANCE SECURITY:

10.1 On receipt of notification of award from the COMPANY, the CONTRACTOR shall furnish the Performance Security to COMPANY within 15 (fifteen) days from the date of issue of LOA for an amount specified in the Forwarding Letter and Letter of Award (LOA) as per Proforma-Form and must be in the form of a Bank Draft/Cashier's cheque/Banker's cheque*/ NEFT/RTGS/Electronic fund transfer to designated account of OIL# or Fixed Deposit Receipt (account OIL

INDIA LIMITED) or irrevocable Bank Guarantee or irrevocable Letter of Credit (LC) from:

- 10.2 Any schedule Indian Bank or Any Branch of an International bank situated in India and registered with Reserve Bank of India as scheduled foreign bank in case of domestic CONTRACTOR/service provider, or
- 10.3 DELETED
- **10.4** Bank Guarantee issued by a Bank, amongst others, must contain the following particulars of such bank:

Full address.

Branch Code.

Code Nos. of the authorized signatory with full name and designation.

Phone Nos., Fax Nos., E-mail address.

- 10.5 The domestic CONTRACTOR/service provider(s) will have to submit the Bank Guarantee from any of the scheduled banks and on non-judicial stamp paper of requisite value as per the Indian Stamp Act, purchased in the name of the issuing banker.
- **10.6** DELETED.
- **10.7** The Performance Security shall be denominated in the currency of the contract.
- 10.8 The Performance Security specified above must be valid for the entire duration of the Contract and claim period should be valid for a minimum of 03 (three) months beyond the contract period. The Performance Security will be discharged by COMPANY not later than 30 days following its expiry of claim period. In the event of any extension of the Contract period, Bank Guarantee should be extended by CONTRACTOR by the period equivalent to the extended period.
- 10.9 The Performance Security shall be encashed by COMPANY on account of CONTRACTOR's failure to fulfil its obligations under the Contract and/or non-performance/un-satisfactory of the Contractor. Company shall not be required to proof any loss or damage on account of Contractor's non-performance/un-satisfactory performance.
- **10.10** The Performance Security will not accrue any interest during its period of validity or extended validity.
- **10.11** Failure of the successful Bidder to comply with the requirements of clause 10.0 shall constitute sufficient grounds for annulment of the award and forfeiture of the Bid Security. In such an eventuality, action will be initiated as per the Banning Policy of OIL in vogue.

#Subject to credit in OIL's account within prescribed time

*The validity of Bank Draft/Cashier's/Banker's cheque (as applicable) should not be less than 3 months.

In the event CONTRACTOR fails to honour any of the commitments entered into under this agreement, and/or in the event of termination of the contract under provisions of Integrity Pact and/or in respect of any amount due from the CONTRACTOR to OIL, OIL shall have unconditional option under the guarantee to invoke the above bank guarantee and claim the amount from the bank. The bank shall be obliged to pay the amount to OIL on demand.

11.0 SIGNING OF CONTRACT:

11.1 The successful bidder is required to sign a formal detailed contract with OIL within a maximum period of 60 days of date of LOA. Until the contract is signed, the LOA as well as GCC & SCC as prescribed in the Tender, shall remain binding amongst the two parties. In the event of failure on the part of the successful Bidder to sign the contract, OIL reserves the right to terminate the LOA issued to the successful Bidder and invoke the Bid Security or the Performance Security if submitted by the successful Bidder. Such CONTRACTOR shall be put on holiday as per the Banning Policy of OIL [available at www.oil-india.in].

12.0 CLAIMS, TAXES & DUTIES:

12.1 Claims:

CONTRACTOR agrees to pay all claims, taxes and fees for equipment, labour, materials, services and supplies to be furnished by it hereunder and agrees to allow no lien or charge resulting from such claims to be fixed upon any property of COMPANY. COMPANY may, at its option, pay and discharge any liens or overdue charges for CONTRACTOR's equipment, labour, materials, services and supplies under this CONTRACT and may thereupon deduct the amount or amounts so paid from any sum due, or thereafter become due, to CONTRACTOR hereunder.

12.2 Notice of claims:

CONTRACTOR or COMPANY, as the case may be, shall promptly give the other, notice in writing of any claim made or proceeding commenced for which that party is entitled to indemnification under the CONTRACT. Each party shall confer with the other concerning the defense of any such claims or proceeding, shall permit the other to be represented by counsel in defense thereof, and shall not affect settlement of or compromise any such claim or proceeding without the other's written consent.

12.3 Taxes:

- 12.3.1 CONTRACTOR, unless specified otherwise in the CONTRACT, shall bear all tax liabilities, duties, Govt. levies etc. including GST and customs duty, Corporate and personnel taxes levied or imposed on the CONTRACTOR on account of payments received by it from the COMPNAY for the work done under this CONTRACT. It shall be the responsibility of CONTRACTOR to submit to the concerned Indian authorities, the returns and all other concerned documents required for this purpose and to comply in all respects with the requirements of the laws in this regard, in time.
- **12.3.2** Tax levied on CONTRACTOR as per the provisions of Indian Income Tax Act and any other enactment/rules on income derived/payments received under the contract will be on CONTRACTOR's account.
- **12.3.3** CONTRACTOR shall be responsible for payment of personal taxes, if any, for all the personnel deployed in India by CONTRACTOR.
- 12.3.4 The CONTRACTOR shall furnish to the COMPANY, if and when called upon to do so, relevant statement of accounts or any other information pertaining to work done under the contract for submitting the same to the Tax authorities, on specific request from them in accordance with provisions under the law. CONTRACTOR shall be responsible for preparing and filing the return of income etc. within the prescribed time limit to the appropriate authority.
- 12.3.5 Prior to start of operations under the contract, the CONTRACTOR shall furnish the COMPANY with the necessary documents, as asked for by the COMPANY and/or any other information pertaining to the contract, which may be required to be submitted to the Income Tax authorities at the time of obtaining "No Objection Certificate" for releasing payments to the CONTRACTOR.
- **12.3.6** Corporate income tax will be deducted at source from the invoice at the specified rate of income tax as per the provisions of Indian Income Tax Act as may be in force from time to time and COMPANY will issue TDS Certificate to the CONTRACTOR as per the provisions of Income Tax Act.
- **12.3.7** Corporate and personnel taxes on CONTRACTOR shall be the liability of the CONTRACTOR and the COMPANY shall not assume any responsibility on this account.
- **12.3.8** All local taxes, levies and duties, sales tax, octroi, etc. on purchases and sales made by CONTRACTOR shall be borne by the CONTRACTOR.
- 12.3.9 CONTRACTOR shall provide all the necessary compliances/invoice/ documents for enabling OIL to avail Input tax credit benefits in respect of the payments of GST which are payable against the CONTRACT. The CONTRACTOR should provide tax invoice issued under GST legislations for the goods and Services (indicating GST). Payment towards the components of GST shall be released by

OIL only against appropriate documents i.e.: Tax Invoice/Bill of entry for availing input tax credit (as applicable).

- **12.3.10** The tax invoices as per above provisions should contain all the particulars as required under the invoicing rules under the GST legislations, including, but not limited to the following:
 - (i) Name, Address and the GST Registration Number (under the relevant Tax Rules) of the Service Provider (CONTRACTOR).
 - (ii) Name and Address and GST Registration Number of the Service Receiver (Address of OIL).
 - (iii) Description, Classification and Value of taxable service/goods and the amount of applicable tax (CGST, SGST, IGST, UTGST and cess).
- **12.3.11** In case of imported goods, CONTRACTOR/supplier is required to provide original Bill of Entry or copy of Bill of Entry duly attested by Custom authority.
- **12.3.12** The CONTRACTOR should mention the Place of supply in the invoice raised under GST Law.
- **12.3.13** OIL would not accept any invoice without its GSTIN mentioned on the invoice

Note: CONTRACTOR who is under composition levy of the GST legislation would raise Bill of supply instead of Tax invoice, which will have GSTIN of supplier as well as OIL.

12.4 Goods and Services Tax:

- 12.4.1 "GST" shall mean Goods and Services Tax charged on the supply of material(s) and services. The term "GST" shall be construed to include the Integrated Goods and Services Tax (hereinafter referred to as "IGST") or Central Goods and Services Tax (hereinafter referred to as "CGST") or State Goods and Services Tax (hereinafter referred to as "SGST") or Union Territory Goods and Services Tax (hereinafter referred to as "UTGST") depending upon the import/ interstate or intrastate supplies, as the case may be. It shall also mean GST compensation Cess, if applicable.
- 12.4.2 Where the OIL is entitled to avail the input tax credit of GST:

OIL will reimburse the GST to the Supplier of Goods/Services (Service Provider) at actual against submission of Invoices as per format specified in rules/regulation of GST to enable OIL to claim input tax credit of GST paid. In case of any variation in the executed quantities, the amount on which the GST is applicable shall be modified in same proportion. Returns and details required to be filled under GST laws &rules should be timely filed by supplier with requisite details.

12.4.3 Where the OIL is not entitled to avail/take the full input tax credit of GST:

OIL will reimburse GST to the Supplier of Goods/Services (Service Provider) at actual against submission of Invoices as per format specified in rules/regulation of GST subject to the ceiling amount of GST as quoted by the bidder. In case of any variation in the executed quantities (If directed and/or certified by the In-Charge) the ceiling amount on which GST is applicable will be modified on pro-rata basis.

- 12.4.4 The CONTRACTOR will be under obligation for charging correct rate of tax as prescribed under the respective tax laws. Further the CONTRACTOR shall avail and pass on benefits of all exemptions/concessions available under tax laws. Any error of interpretation of applicability of taxes/duties by the CONTRACTOR shall be to CONTRACTOR's account.
- 12.4.5 In case of statutory variation in GST, other than due to change in turnover, payable on the contract value during contract period, the Supplier of Goods/Services (Service Provider) shall submit a copy of the 'Government Notification' to evidence the rate as applicable on the Bid due date and on the date of revision.
- 12.4.6 Beyond the contract period, in case OIL is not entitled for input tax credit of GST, then any increase in the rate of GST beyond the contractual delivery period shall be to Service provider's account whereas any decrease in the rate GST shall be passed on to the OIL.
- 12.4.7 Beyond the contract period, in case OIL is entitled for input tax credit of GST, then statutory variation in applicable GST on supply and on incidental services, shall be to OIL's account.
- 12.4.8 Claim for payment of GST/Statutory variation, should be raised within two [02] months from the date of issue of 'Government Notification' for payment of differential (in %) GST, otherwise claim in respect of above shall not be entertained for payment of arrears.
- 12.4.9 The base date for the purpose of applying statutory variation shall be the Bid Opening Date.
- 12.4.10 The CONTRACTOR will be liable to ensure to have registered with the respective tax authorities, wherever applicable and to submit self-attested copy of such registration certificate(s) and the CONTRACTOR will be responsible for procurement of material in its own registration (GSTIN) and also to issue its own Road Permit/E-way Bill, if applicable etc.

12.5 Anti-profiteering clause

12.5.1 As per Clause 171 of GST Act it is mandatory to pass on the benefit due to reduction in rate of tax or from input tax credit to the consumer by way of commensurate reduction in prices.

12.5.2 In case rating of Contractor is negative/black listed after award of work for supply of goods/services, then OIL shall not be obligated or liable to pay or reimburse GST to such vendor/Contractor and shall also be entitled to deduct/recover such GST along with all penalties/interest, if any, incurred by OIL.

13.0 CUSTOMS DUTY, IF APPLICABLE:

- 13.1.1 CONTRACTOR shall be responsible to import the equipment/tools/spares/consumables etc. required for execution of the contract. The CONTRACTOR shall undertake to complete all the formalities as required under the Customs Act/Foreign Trade Policy (FTP) and indemnify OIL from all the liabilities of Customs in this regard.
- 13.1.2 CONTRACTOR will be solely responsible for payment of all applicable Customs Duty and to comply all Rules and Regulations. Total Contract Price/Value is inclusive of all Customs Duty, if not mentioned otherwise elsewhere in the Contract.
- 13.1.3 Above clause is to be read with Customs Duty Clause in SCC, if any.

14.0 INSURANCE:

14.1 CONTRACTOR shall at his own expense arrange secure and maintain insurance with reputed insurance companies to the satisfaction of the Company as follows:

Contractor at his cost shall arrange, secure and maintain insurance as may be necessary and to its full value for all such amounts to protect the works in progress from time to time and the interest of Company against all risks as detailed herein. The form and the limit of such insurance, as defined here in together with the under works thereof in each case should be as acceptable to the Company. However, irrespective of work acceptance the responsibility to maintain adequate insurance coverage at all times during the period of Contract shall be that of Contractor alone. Contractor's failure in this regard shall not relieve him of any of his responsibilities & obligations under Contract. All costs on account of insurance liabilities covered under Contract will be to Contractor's account and will be included in Value of Contract. However, the Company may from time to time, during the currency of the Contract, ask the Contractor in writing to limit the insurance coverage risk and in such a case, the parties to the Contract will agree for a mutual settlement, for reduction in value of Contract to the extent of reduced premium amounts. Contractor shall cover insurance with Indian Insurance Companies.

- **14.2** Any deductible set forth in any of the above insurance shall be borne by Contractor.
- **14.3** CONTRACTOR shall require all of his sub-Contractor to provide such of the foregoing insurance coverage as Contractor is obliged to provide under this

Contract and inform the Company about the coverage prior to the commencement of agreements with its sub-Contractors.

14.4 All insurance taken out by Contractor or their sub-contractor shall be endorsed to provide that the underwriters waive their rights of recourse on the Company and to the extent of the liabilities assumed by Contractor under this Contract.

14.5 Certificate of Insurance:

Before commencing performance of the CONTRACT, CONTRACTOR shall furnish OIL with certificates of insurance indicating:

- i) Kinds and amounts of insurance as required herein
- ii) Details of coverage
- iii) Insurance corporation or companies carrying the aforesaid coverage
- iv) Effective and expiry dates of policies
- v) That OIL shall be given thirty (30) days written advance notice of any material change in the policy
- vi) Waiver of subrogation endorsement has been attached to all policies and
- vii) The territorial limits of all policies.
- 14.6 Contractor shall also inform the Company at least 60 days in advance regarding the expiry cancellation and/or changes in any of such documents & ensure revalidation/renewal, etc., as may be necessary well in time.
- 14.7 If any of the above policy expire or/are cancelled during the term of this CONTRACT and CONTRACTOR fails for any reason to renew such policies, OIL in no case shall be liable for any loss/damage occurred during the term when the policy is not effective. Furthermore, a penal interest @1% of the Total contract value shall be charged towards not fulfilling of the contractual obligations. Notwithstanding above, should there be a lapse in any insurance required to be taken by the Contractor for any reason whatsoever, loss/damage claims resulting therefrom shall be to the sole account of Contractor.
- 14.8 Contractor on demand from Company shall furnish the Insurance Policy having detail terms and conditions, with respect to any Certificate of Insurance submitted to the Company.

CONTRACTOR shall, at his own expense, arrange appropriate comprehensive insurance to cover all risks assumed by the CONTRACTOR under this CONTRACT in respect of CONTRACTOR's equipment, tools and any other belongings of the CONTRACTOR and its personnel as well deputed under this CONTRACT during the entire period of their engagement in connection with this CONTRACT including extensions if any. The CONTRACTOR shall also carry

adequate insurance cover against damage/loss to third party person/property. OIL will have no liability on this account.

14.9 Principal Assured

The following are to be included as Principal Assured(s) in the Insurance Policies (except in case of Workmen's Compensation/Employer's Liability insurance): "Oil India Limited, and CONTRACTOR's name (as appearing in the Contract /LOA)".

14.10 Waiver of subrogation:

All insurance policies of the CONTRACTOR with respect to the operations conducted hereunder as set forth in clauses hereof, shall be endorsed by the underwriter in accordance with the following policy wording:

"The insurers hereby waive their rights of subrogation against Oil India Limited or any of their employees or their affiliates and assignees".

14.11 Deductible:

The CONTRACTOR shall take policy with minimum deductible as per IRDA prescribed for the policy(ies). That portion of any loss not covered by insurance provided for in this article solely by reason of deductible provision in such insurance policies shall be to the account of the CONTRACTOR.

14.12 Compliance with Sec 25(1), of "The General Insurance Business (Nationalization) Act 1972"

Section 25(1) of "The General Insurance Business (Nationalization) Act 1972" is reproduced below:

"No person shall take out or renew any policy of insurance in respect of any property in India or any ship or other vessel or aircraft registered in India with an insurer whose principal place of business is outside India save with the prior permission of the Central Government".

The above requirement of aforesaid Act needs to be complied with by the CONTRACTOR wherever the aforesaid provisions of Act apply, and compliance confirmations submitted.

14.13 Loss Payee Clause:

The Insurance Policies should mention the following in Loss Payee Clause: "In respect of Insurance claims in which OIL's interest is involved, written consent of OIL will be required".

14.14 On account payment to OIL in case of claim

In case any loss or damage happen and where OIL's interest is involved, OIL reserves the right to recover the loss amount from the CONTRACTOR prior to final settlement of the claim.

- **14.15** CONTRACTOR shall require all of its SUB-CONTRACTORs to provide such of the foregoing insurance cover as the CONTRACTOR is obligated to provide under this CONTRACT.
- **14.16** CONTRACTOR shall at all time during the currency of the contract provide, pay for and maintain the following insurance amongst others:
- i) **Workman Compensation and/Employers' Liability Insurance**: Workmen's compensation and employer's liability insurance as required by the laws of the country of origin of the employee.
- ii) <u>Commercial General Liability Insurance</u>: Commercial General Public Liability Insurance covering liabilities including contractual liability for bodily injury, including death of persons, and liabilities for damage of property. This insurance must cover all operations of CONTRACTOR required to fulfil the provisions under this Contract.
- iii) <u>Comprehensive General Automotive Liability</u>: Automobile Public Liability Insurance covering owned, non-owned and hired automobiles used in the performance of the work hereunder, with bodily injury limits and property damage limits shall be governed by Indian Insurance Regulations.
- iv) <u>Carrier's Legal Liability Insurance</u>: Carrier's Legal Liability Insurance in respect of all CONTRACTOR's items to be transported by the CONTRACTOR to the site of work, for physical loss or destruction of or damage to goods or merchandise, while in transit.
- v) **Public Liability Act Policy:** Public Liability Act Policy covering the statutory liability arising out of accidents occurring during the currency of the contract due to handling hazardous substances as provided in the Public Liability Insurance Act 1991 and the Rules framed there under.
- Pradhan Mantri Suraksha Bima Yojana (PMSBY) and Pradhan Mantri Jeevan Jyoti Bima Yojana (PMJJBY): CONTRACTOR shall, ensure that all his/its personnel deployed under this contract have obtained additional insurance coverage under the Pradhan Mantri Suraksha Bima Yojana (PMSBY) and Pradhan Mantri Jeevan Jyoti Bima Yojana (PMJJBY) through the participating banks and submit the proof of such insurance coverage to the satisfaction of OIL.
- vii) CONTRACTOR's equipment used for execution of the work hereunder shall have an insurance cover with a suitable limit (as per international standards).
- viii) Any other insurance policy set forth in the SCC

Note: An undertaking by the service provider has to be mandatorily provided during the Mobilization time that they have taken all the

Insurance provisions as per the contract and as the Law and Insurance Regulation.

15.0 LIABILITY:

- 15.1 Except as otherwise expressly provided herein, neither COMPANY nor its servants, agents, nominees, CONTRACTORs, or sub-CONTRACTORs shall have any liability or responsibility whatsoever to whomsoever for loss of or damage to the equipment and/or loss of or damage to the property of the CONTRACTOR and/or their CONTRACTORs or sub-CONTRACTORs, irrespective of how such loss or damage is caused and even if caused by the negligence of COMPANY and/or its servants, agent, nominees, assignees, CONTRACTORs and sub-CONTRACTORs.
- The CONTRACTOR shall protect, defend, indemnify and hold harmless COMPANY from and against such loss or damage and any suit, claim or expense resulting there from. Neither COMPANY nor its servants, agents, nominees, assignees, CONTRACTORs, sub-CONTRACTORs shall have any liability or responsibility whatsoever for injury to, illness, or death of any employee of the CONTRACTOR and/or of its CONTRACTORs or sub-CONTRACTOR irrespective of how such injury, illness or death is caused and even if caused by the negligence of COMPANY and/or its servants, agents nominees, assignees, CONTRACTORs and sub-CONTRACTORs. CONTRACTOR shall protect, defend, indemnify and hold harmless COMPANY from and against such liabilities and any suit, claim or expense resulting there from.
- 15.3 The CONTRACTOR hereby agrees to waive its right of recourse and further agrees to cause its underwriters to waive their right of subrogation against COMPANY and/or its underwriters, servants, agents, nominees, assignees, CONTRACTORs and sub-CONTRACTORs for loss or damage to the equipment of the CONTRACTOR and/or its sub-CONTRACTORs and/or their employees when such loss or damage or liabilities arises out of or in connection with the performance of the contract limited to the CONTRACTOR's liabilities agreed to under this Contract.
- The CONTRACTOR hereby further agrees to waive its right of recourse and agrees to cause its underwriters to waive their right of subrogation against COMPANY and/or its underwriters, servants, agents, nominees, assignees, CONTRACTORs and sub-CONTRACTORs for injury to, illness or death of any employee of the CONTRACTOR and of its CONTRACTORs, sub-CONTRACTORs and/or their employees when such injury, illness or death arises out of or in connection with the performance of the contract limited to the CONTRACTOR's liabilities agreed to under this Contract.
- 15.5 Except as otherwise expressly provided herein, neither CONTRACTOR nor its servants, agents, nominees, CONTRACTORs or sub-CONTRACTORs shall have any liability or responsibility whatsoever to whomsoever for loss of or damage to the equipment and/or loss or damage to the property of the COMPANY and/or

their CONTRACTORs or sub-CONTRACTORs, irrespective of how such loss or damage is caused and even if caused by the negligence of CONTRACTOR and/or its servants, agents, nominees, assignees, CONTRACTORs and sub-CONTRACTORs. The COMPANY shall protect, defend, indemnify and hold harmless CONTRACTOR from and against such loss or damage and any suit, claim or expense resulting there from.

- 15.6 Except as otherwise expressly provided herein, neither CONTRACTOR nor its servants, agents, nominees, assignees, CONTRACTORs, sub-CONTRACTORs shall have any liability or responsibility whatsoever to whomsoever for injury or illness, or death of any employee of the COMPANY and/or of its CONTRACTORs or sub-CONTRACTORs irrespective of how such injury, illness or death is caused and even if caused by the negligence of CONTRACTOR and/or its servants, agents, nominees, assignees, CONTRACTORs and sub-CONTRACTORs. COMPANY shall protect, defend indemnify and hold harmless CONTRACTOR from and against such liabilities and any suit, claim or expense resulting there from.
- 15.7 The COMPANY agrees to waive its right of recourse and further agrees to cause its underwriters to waive their right of subrogation against CONTRACTOR and/or its underwriters, servants, agents, nominees, assignees, CONTRACTORs and sub-CONTRACTORs for loss or damage to the equipment of COMPANY and/or its CONTRACTORs or sub-CONTRACTORs when such loss or damage or liabilities arises out of or in connection with the performance of the contract.
- The COMPANY hereby further agrees to waive its right of recourse and agrees to cause it underwriters to waive their right of subrogation against CONTRACTOR and/or its underwriters, servants, agents, nominees, assignees, CONTRACTORs and sub-CONTRACTORs for injury to, illness or death of any employee of the COMPANY and of its CONTRACTORs, sub-CONTRACTORs and/or their employees when such injury, illness or death arises out of or in connection with the performance of the Contract.

16.0 <u>LIMITATION OF LIABILITY</u>:

- a) Notwithstanding any other provisions herein to the contrary, except only in cases of wilful misconduct and/or criminal acts and/or criminal negligence, neither the CONTRACTOR nor the COMPANY (OIL) shall be liable to the other, whether in Contract, tort, or otherwise, for any consequential loss or damage, loss of use, loss of production, or loss of profits or interest costs, provided however that this exclusion shall not apply to any obligation of the CONTRACTOR to pay Liquidated Damages to the COMPANY and/or COMPANY's right to forfeit the Performance Bank Guarantee(s) in terms of the contract.
- b) Notwithstanding any other provisions incorporated elsewhere in the contract, the aggregate liability of the CONTRACTOR in respect of this contract, whether under Contract, in tort or otherwise, shall not exceed 100% of the Contract Price

(if not specified otherwise in SCC), provided however that this limitation shall not apply to the cost of repairing or replacing defective equipment by the CONTRACTOR, or to any obligation of the CONTRACTOR to indemnify the COMPANY with respect to Intellectual Property Rights.

c) COMPANY shall indemnify and keep indemnified CONTRACTOR harmless from and against any and all claims, costs, losses and liabilities in excess of the aggregate liability amount in terms of clause (b) above.

17.0 LIABILITY OF UNION GOVERNMENT OF INDIA:

It is expressly understood and agreed upon by and between CONTRACTOR and OIL INDIA LIMITED, and that OIL INDIA LIMITED is entering into this agreement solely on its own behalf and not on behalf of any other person or entity. In particular, it is expressly understood and agreed that Union of India is not a party to this agreement and has no liabilities, obligations or rights, whatsoever hereunder. It is expressly understood and agreed that OIL INDIA LIMITED is an independent legal entity with power and authority to enter into contracts solely on its own behalf under the applicable laws of India and general principles of the Contract law. The bidder/CONTRACTOR expressly agrees, acknowledges and understands that OIL INDIA LIMITED is not an agent, representative or delegate of the Union of India. It is further understood and agreed that Union of India is not and shall not be liable for any acts, omissions, commissions, breaches or other wrongs arising out of the contract. Accordingly, bidder/ CONTRACTOR hereby expressly waives, releases and foregoes any and all actions or claims, including cross claims, impleader claims or counter claims against the Union of India arising out of this contract and covenants not to sue the Union of India as to any manner, claim, cause of action or thing whatsoever arising of or under this agreement.

18.0 CONSEQUENTIAL DAMAGE:

Except as otherwise expressly provided, neither party shall be liable to the other for special, indirect or consequential damages resulting from or arising out of the contract, including but without limitation, to loss or profit or business interruptions, howsoever caused and regardless of whether such loss or damage was caused by the negligence (either sole or concurrent) of either party, its employees, agents or sub-CONTRACTORs.

19.0 RISK PURCHASE:

In the event, CONTRACTOR's failure to provide the services as per the Contractual scope, terms and conditions, COMPANY (OIL) reserves the right to hire the services from any other source at the CONTRACTOR's risk & cost and the difference in cost shall be borne by the CONTRACTOR. Further, OIL shall retain the right of forfeiture of Performance Bank Guarantee and any other action as deemed fit. In certain operational situations OIL reserves the right to

take over the site including the service equipment at the risk and cost of the CONTRACTOR.

20.0 INDEMNITY AGREEMENT:

- 20.1 Except as provided hereof CONTRACTOR agrees to protect, defend, indemnify and hold COMPANY harmless from and against all claims, suits, demands and causes of action, liabilities, expenses, cost, liens and judgments of every kind and character, without limit, which may arise in favour of CONTRACTOR's employees, agents, CONTRACTORs and sub-CONTRACTORs or their employees or in favour of any third party(is) on account of bodily injury or death, or damage to personnel/property as a result of the operations contemplated hereby, regardless of whether or not said claims, demands or causes of action arise out of the negligence or otherwise, in whole or in part or other faults.
- 20.2 Except as provided hereof COMPANY agrees to protect, defend, indemnify and hold CONTRACTOR harmless from and against all claims, suits, demands and causes of action, liabilities, expenses, cost, liens and judgments of every kind and character, without limit, which may arise in favour of COMPANY's employees, agents, CONTRACTORs and sub-CONTRACTORs or their employees or in favour of any third party(is) on account of bodily injury or death, or damage to personnel/property as a result of the operations contemplated hereby, regardless of whether or not said claims, demands or causes of action arise out of the negligence or otherwise, in whole or in part or other faults.

21.0 INDEMNITY APPLICATION:

The indemnities given herein above, whether given by COMPANY or CONTRACTOR shall be without regard to fault or to the negligence of either party even though said loss, damage, liability, claim, demand, expense, cost or cause of action may be caused, occasioned by or contributed to by the negligence, either sole or concurrent of either party.

22.0 ROYALTY PATENTS:

Each party shall hold harmless and indemnify the other from and against all claim and proceedings for or on account of any patent rights, design, trade mark or other protected rights arising from any use of materials, equipment, processes, inventions and methods, which have not been imposed on the attending party by the terms of the contract or the specifications forming part thereof.

23.0 WARRANTY AND REMEDY OF DEFECTS:

23.1 CONTRACTOR warrants that they shall perform the work in a first class, workmanlike, and professional manner and in accordance with their highest degree of quality, efficiency and current state of the art technology/industry

practices and in conformity with all specifications, standards and drawings set forth or referred to in the Terms of Reference and with instructions and guidance, which COMPANY may, from time to time, furnish to the CONTRACTOR.

Should COMPANY discover at any time during the tenure of the Contract or till the Unit/equipment/tools are demobilized from site or base camp (if applicable) that the work does not conform to the foregoing warranty, CONTRACTOR shall after receipt of notice from COMPANY, promptly perform any and all corrective work required to make the services conform to the Warranty. Such corrective Work shall be performed entirely at CONTRACTOR's own expenses. If such corrective Work is not performed within a reasonable time, the COMPANY, at its option may have such remedial Work performed by others and charge the cost thereof to CONTRACTOR subject to a maximum of the contract value payable for the defective work which needs corrective action which the CONTRACTOR must pay promptly. In case CONTRACTOR fails to perform remedial work, or pay promptly in respect thereof, the performance security shall be forfeited.

24.0 SUBCONTRACTING/ASSIGNMENT:

- 24.1 CONTRACTOR shall not subcontract, transfer or assign the contract, or any part under this contract, to any third party(ies). Except for the main services under this contract, CONTRACTOR may sub-contract the petty support services subject to COMPANY's prior written approval. However, CONTRACTOR shall be fully responsible for complete execution and performance of the services under the Contract.
- 24.2 Consequent upon of placement of contract, if successful bidder(s)(other than Micro/Small Enterprise) is procuring materials/services from their sub-vendor, who is a Micro or Small Enterprise registered with District Industry Centers or Khadi and Village Industries Commission or Khadi and Village Industries Board or Coir Board or National Small Industries Corporation or Directorate of Handicrafts and Handloom or any other body specified by Ministry of MSME with prior consent in writing of the purchasing authority/Engineer in Charge the details like Name, Registration No., Address, Contact No., details of material and value of procurement made, etc. of such enterprises shall be furnished by the CONTRACTOR at the time of submission of invoice/bill.

25.0 RECORDS, REPORTS AND INSPECTION:

The CONTRACTOR shall, at all times during the currency of the contract, permit the COMPANY and its authorized employees and representatives to inspect all the Work performed and to witness and check all the measurements and tests made in connection with the said work. The CONTRACTOR shall keep an authentic, accurate history and logs including safety records of each service item with major items consumed, which shall be open at all reasonable times for inspection by the COMPANY's designated representatives and its authorized

employees. The CONTRACTOR shall provide the COMPANY's designated representatives with a daily written report, on form prescribed by the COMPANY showing details of operations during the preceding 24 hours and any other information related to the said services requested by the COMPANY whenever so requested. The CONTRACTOR shall not, without COMPANY's written consent allow any third person(s) access to the said information or give out to any third person information in connection therewith.

26.0 CONFIDENTIALITY, USE OF CONTRACT DOCUMENTS AND INFORMATION:

- 26.1 CONTRACTOR shall not, without COMPANY's prior written consent, disclose the contract, or any provision thereof, or any specification, plan, drawing pattern, sample or information furnished by or on behalf of COMPANY in connection therewith, to any person other than a person employed by CONTRACTOR in the performance of the contract. Disclosure to any such employed person shall be made in confidence and shall extend only, as may be necessary for purposes of such performance with prior permission from COMPANY. However, nothing hereinabove contained shall deprive the CONTRACTOR of the right to use or disclose any information which is:
- a) possessed by the CONTRACTOR, as evidenced by the CONTRACTOR's written records, before receipt thereof from the COMPANY which however the CONTRACTOR shall immediately inform to COMPANY; or
- b) required to be disclosed by the CONTRACTOR pursuant to an order of a court of competent jurisdiction or other governmental agency having the power to order such disclosure, provided the CONTRACTOR uses its best efforts to provide timely notice to COMPANY of such order to permit COMPANY an opportunity to contest such order subject to prior permission from COMPANY.
- 26.2 CONTRACTOR shall not, without COMPANY's prior written consent, make use of any document or information except for purposes of performing the contract.
- Any document supplied to the CONTRACTOR in relation to the contract other than the Contract itself remain the property of COMPANY and shall be returned (in all copies) to COMPANY on completion of CONTRACTOR's performance under the Contract if so required by COMPANY.
- During the currency of the Contract, COMPANY and its employees, agents, other CONTRACTORs, sub-CONTRACTORs (of any tier) and their employees etc. may be exposed to certain confidential information and data of the CONTRACTOR. Such information and data held by the COMPANY, its employees, agents, other CONTRACTORs, sub-CONTRACTORs (of any tier) and their employees in the strictest Confidence and shall not be disclosed to any other party except on a need to know basis.

However, the above obligation shall not extend to information which:

- i) is, at the time of disclosure, known to the public which CONTRACTOR shall immediately inform COMPANY;
- ii) is lawfully becomes at a later date known to the public through no fault of CONTRACTOR subject to CONTRACTOR's undertaking that no information has been divulged by them to the public;
- iii) is lawfully possessed by CONTRACTOR before receipt thereof from COMPANY which should be immediately informed to COMPANY;
- iv) is developed by CONTRACTOR independently of the information disclosed by COMPANY which should be shared with the COMPANY;
- v) CONTRACTOR is required to produce before competent authorities or by court order subject to prior permission from COMPANY;

27.0 REMUNERATION AND TERMS OF PAYMENT:

- 27.1 COMPANY shall pay to the CONTRACTOR during the term of the Contract the amount due from time to time calculated according to the rates of payment set and in accordance with other provisions hereof. No other payments shall be due from COMPANY unless specifically provided for in the Contract. All payments will be made in accordance with the terms hereinafter described.
- **27.2** Request for payment/part payment to third party i.e. other than the party on whom the contract has been awarded will not be entertained by OIL under any circumstances.
- 27.3 MANNER OF PAYMENT: All payments due by COMPANY to CONTRACTOR hereunder shall be made at CONTRACTOR's designated bank. Bank charges, if any will be on account of the CONTRACTOR.
- Payment of any invoices shall not prejudice the right of COMPANY to question the validity of any charges therein, provided COMPANY within one year after the date of payment shall make and deliver to CONTRACTOR written notice of objection to any item or items the validity of which COMPANY questions.
- 27.5 INVOICES: Mobilization charges will be invoiced only upon completion of mobilization as certified by COMPANY representative and CONTRACTOR is ready at site for starting the services/operation. Payment of mobilization charges shall be made within 45 days following the date of receipt of undisputed invoices by COMPANY.
- **27.6** CONTRACTOR shall send invoice to COMPANY on the day following the end of each month for all daily or monthly charges due to the CONTRACTOR.
- **27.7** CONTRACTOR will submit 02 (Two) sets of all invoices duly super scribed 'Original' and 'copy' as applicable to the COMPANY for processing payment.
- **27.8** Payment of monthly invoices, if undisputed, shall be made within 30 days following the date of receipt of invoice by COMPANY.

- 27.9 COMPANY shall within 30 days of receipt of the invoice notify the CONTRACTOR of any item under dispute, specifying the reasons thereof, in which event, payment of the disputed amount may be withheld until settlement of the dispute, but payment shall be made of any undisputed portion on or before the due date. This will not prejudice the COMPANY's right to question the validity of the payment at a later date as envisaged in clause no. 27.4 above.
- 27.10 The acceptance by CONTRACTOR of part payment on any billing not paid on or before the due date shall not be deemed a waiver of CONTRACTOR's rights in any other billing, the payment of which may then or thereafter be
- **27.11** Payment of Final demobilization charges shall be made if applicable within 45 days on receipt of invoice by COMPANY accompanied by the following documents from the CONTRACTOR:
 - a) Audited account up to completion of the Contract.
 - b) Tax audit report for the above period as required under the Indian Tax Laws
 - c) Documentary evidence regarding the submission of returns and payment to taxes for the expatriate personnel engaged by the CONTRACTOR or by its sub-CONTRACTOR.
 - d) Proof of re-export of all items including the unutilized spares and consumables (excepting consumables consumed during the contract period) and also cancellation of re-export bond if any.
 - e) Any other documents as required by applicable Indian Laws.

In case, no demobilization charges are payable, the documents mentioned above will have to be submitted by the CONTRACTOR before release of the final payment by the COMPANY. A certificate from Chartered Accountant on (a), (b) & (c) above will suffice.

27.12 CONTRACTOR shall maintain complete and correct records of all information on which CONTRACTOR's invoice are based upto 02 (two) years from the date of last invoice. Such records shall be required for making appropriate adjustments or payments by either party in case of subsequent audit query/objection.

28.0 DELETED

29.0 DETAILS OF STATUTORY PAYMENTS LIKE EPF AND ESI ETC.

Wherever applicable, the CONTRACTOR (including those engaging 'International Workers') shall have itself registered under Employees' Provident Fund and Miscellaneous Provisions Act, 1952 and Employees' State Insurance Act, 1948

and follow the relevant statutory provisions including Rules made there-under concerning contractual workers.

The CONTRACTOR shall be required to submit the following documents/details to the Corporation:

- (i) Copy of PF-ECR duly stamped by the designated Bank, alongwith a print of the digitally signed PDF data sheet of the ECR, as proof of payment, each month, details of this PDF data sheet shall be verified by the appropriate authority (i.e. Payment Making Authority) in the COMPANY from the official website of EPFO (http://www.epfindia.gov.in).
- (a) Copy of the online challan endorsed/stamped by the designated bank as proof of receipt of payment towards monthly contribution of ESI contribution.
- (b) Copy of Return of contribution in respect of ESI for each contribution period of the six months i.e. for the contribution period ended 30th Sept and the contribution period ended 31st March.
- (iii) As an Annexure to each EPF-ECR and ESI Challan(s), CONTRACTOR shall also furnish the following Certificates:
 - 1) The furnished information is correct to the best of his knowledge.
 - 2) In case any discrepancies or irregularities is/are noticed in this undertaking, then OIL is free to inform the PF/ESIC Authorities.
 - 3) Before the completion of contract, CONTRACTOR shall serve one-month notice to all his contractual workers, informing that their services will be terminated.
 - 4) Within one month on completion/expiry of the contract, CONTRACTOR shall pay all the dues/terminal dues such as leave with wages, bonus (if applicable), Gratuity (if applicable), to all his contractual workmen, failing which CONTRACTOR's Bank Guarantee/Security Deposit may be withheld by OIL.

COMPANY may verify the deposit of statutory contribution made by the CONTRACTORs with the EPFO/ESI authorities, where deemed necessary. However, before making payment of the last bill/invoice of the CONTRACTOR, the COMPANY may verify the details/status of the payment towards EPF/ESI made by the CONTRACTOR from the authorities/official website of EPF/ESI (i.e. http://www.epfindia.gov.in and http://www.esic.in). In case the information furnished by the CONTRACTOR is found to be incorrect the COMPANY shall take appropriate action against the CONTRACTOR in accordance with law.

The CONTRACTOR agrees and undertakes to indemnify OIL for any liabilities arising out of declarations made by him in future on violation or provisions of the EPF Act 1952 and ESI Act 1948.

30.0 TIMELY MOBILISATION AND LIQUIDATED DAMAGES:

- a) Time is the essence of this Contract. If the CONTRACTOR fails to mobilize and deploy the required manpower/equipment and/or fails to commence the operation within the period specified as specified under mobilization clause under SCC, OIL shall have, without prejudice to any other right or remedy in law or contract including sub clause (b) below, the right to terminate the contract.
- b) If the contractor is unable to mobilize/deploy and commence the operation within the period specified in sub clause (a) above, it may request OIL for extension of the time with unconditionally agreeing for levy and recovery of LD. Upon receipt of such a request, OIL may at its discretion, extend the period of mobilization and shall recover from the CONTRACTOR, as an ascertained and agreed Liquidated Damages, a sum equivalent to @ 0.5% of contract value including mobilization cost, per week or part thereof of delay subject to maximum of 7.5% of the Contract Price.
- c) The parties agree that the sum specified above is not a penalty but a genuine pre-estimate of the loss/damage which will be suffered by OIL on account of delay on the part of the CONTRACTOR and the said amount will be payable without proof of actual loss or damage caused by such delay.
- d) LD will be calculated on the basis of Total Contract value [(if not specified otherwise in SCC] excluding duties and taxes, where such duties/taxes have been shown separately in the contract. However, the applicable GST on the LD shall have to be borne by the CONTRACTOR. Accordingly, the liquidated damages shall be recovered from the CONTRACTOR along with applicable GST.

31.0 FORCE MAJEURE:

In the event of either party being rendered unable by `Force Majeure' to perform any obligation required to be performed by them under the contract, the relative obligation of the party affected by such `Force Majeure' will stand suspended as provided herein. The term force majeure as employed herein shall mean Acts of God such as earthquake, hurricane, typhoon, flood, volcanic activity etc.; war (declared/undeclared); riot, revolts, rebellion, terrorism, sabotage by persons other than the CONTRACTOR's Personnel; fires, explosions, ionising radiation or contamination by radio-activity or noxious gas, if not caused by CONTRACTOR's fault; declared epidemic or disaster; acts and regulations of respective Govt. of the two parties, namely the COMPANY and the CONTRACTOR and civil commotions, lockout not attributable to the CONTRACTOR.

Upon occurrence of such cause, the party claiming that it has been rendered unable as aforesaid thereby, shall notify the other party in writing within 72

(Seventy Two) hours of the alleged beginning and ending thereof, giving full particulars and satisfactory evidence in support of its claim.

Should 'force majeure' condition as stated above occurs and should the same be notified within 72 (Seventy two) hours after its occurrence the `force majeure' rate (if specified in the SCC of the Contract) shall apply for the first 15 (fifteen) days for each such occasion.

Either party shall have the right to terminate the Contract if such 'force majeure' conditions continue beyond successive 60 (Sixty) days [or exclusively mentioned in the SCC of the Contract] with prior written notice of 15 days, provided termination of the Contract does not result into safety hazard to the life and property on account of withdrawal of operations or the operation is at critical stage. COMPANY shall have the absolute right to decide whether any safety hazard exists or operation is at critical position and decision of the COMPANY shall binding upon the CONTRACTOR.

Should either party decide not to terminate the Contract even under such condition, no payment would apply after expiry of fifteen (15) days force majeure period. [or exclusively mentioned in the SCC of the Contract]

Time for performance of the relative obligation suspended by Force Majeure shall then stand extended by the period for which such cause lasts.

If however, relative obligation of the party affected by such 'Force Majeure' is limited to part of the obligation(s), the contract shall not be terminated and the parties shall continue to perform their respective obligations, which are not affected by the 'force majeure' condition, provided the obligations affected by the 'force majeure' do not preclude the parties in performing the obligations not affected by such conditions.

32.0 SET-OFF:

Any sum of money due and payable to the CONTRACTOR (including Performance Security refundable to them) under this or any other Contract, whether in progress or in future, may be appropriated by OIL and set-off against any claim of OIL (or such other person or persons contracting through OIL) for payment of a sum of money arising out of this contract or under any other contract made by the CONTRACTOR with OIL (or such other person or persons contracting through OIL).

33.0 WITHHOLDING:

COMPANY may withhold or nullify the whole or any part of the amount due to CONTRACTOR, after informing the CONTRACTOR of the reasons in writing, on

account of subsequently discovered evidence in order to protect COMPANY from loss on account of:

- **33.1** For non-completion of jobs assigned as per Scope of Work/Terms of Reference.
- **33.2** Defective work not remedied by CONTRACTOR.
- **33.3** Claims by COMPANY's recognized sub-CONTRACTOR of CONTRACTOR or others filed or on the basis of reasonable evidence indicating probable filing of such claims against CONTRACTOR.
- **33.4** Failure of CONTRACTOR to pay or provide for the payment of salaries/ wages, contributions, taxes or enforced savings with-held from wages etc. with respect to personnel engaged by the CONTRACTOR.
- **33.5** Failure of CONTRACTOR to pay the cost of removal of unnecessary debris, materials, tools, or machinery.
- Any failure by CONTRACTOR to fully reimburse COMPANY under any of the indemnification provisions of this Contract. If, during the progress of the work CONTRACTOR shall allow any indebtedness to accrue for which CONTRACTOR, under any circumstances in the opinion of COMPANY, may be primarily or contingently liable or ultimately responsible and CONTRACTOR shall, within five days after demand is made by COMPANY, fail to pay and discharge such indebtedness, then COMPANY may during the period for which such indebtedness shall remain unpaid, with-hold from the amounts due to CONTRACTOR, a sum equal to the amount of such unpaid indebtedness.
- **33.7** Withholding will also be effected on account of the following:
- i) Order issued by a Court of Law or statutory authority in India.
- ii) Income-tax deductible at source according to law prevalent from time to time in the country.
- iii) Any obligation of CONTRACTOR which by any law prevalent from time to time to be discharged by COMPANY in the event of CONTRACTOR's failure to adhere to such laws.
- iv) Any payment due from CONTRACTOR in respect of unauthorised imports.
 - When all the above grounds for withholding payments are removed, payment shall thereafter be made for amounts so with-held.
- **33.8** COMPANY reserves the right to disburse or deposit the amount so withheld to the concerned person(s) or agency or government authority, as the case may be, besides nullifying such amount on account of loss suffered by the COMPANY against 33.2, 33.3, 33.6 & 33.7 above.

34.0 APPLICABLE LAWS:

The Contract shall be deemed to be a Contract made under, governed by and construed in accordance with the laws of India for the time being in force and shall be subject to the sole and exclusive jurisdiction of Courts situated in Dibrugarh (or the Place where the contract is executed) and Principal Bench of Gauhati High Court (or the High Court under whose territorial jurisdiction, the place of execution of contract falls).

This Agreement including all matter connected with this Agreement, shall be governed by the laws of India (both substantive and procedural) for the time being in force and shall be subject to exclusive jurisdiction of Courts, mentioned hereinabove. Foreign companies, operating in India or entering into Joint ventures in India, shall also be governed by the laws of India and shall be subject to sole and exclusive jurisdiction of above Courts.

The CONTRACTOR shall ensure full compliance of various Indian Laws and Statutory Regulations, as stated below, to the extent applicable, as stated below, but not limited to, in force from time to time and obtain necessary permits/licenses etc. from appropriate authorities for conducting operations under the Contract:

- a) The Mines Act 1952
- b) The Oil Mines Regulations, 2017
- c) The Employees' Compensation Act, 1923
- d) The Code of Wages, 2019
- e) The Contract Labour (Regulation & Abolition) Act, 1970 and the rules framed there under
- f) The Employees Pension Scheme, 1995
- g) The Interstate Migrant Workmen Act., 1979 (Regulation of employment and conditions of service).
- h) The Employees Provident Fund and Miscellaneous Provisions Act, 1952
- i) Goods and Service Tax Act
- j) Customs & Excise Act & Rules
- k) Factories Act, 1948
- 1) Industrial Disputes Act, 1947
- m)Payment of Gratuity Act, 1972
- n) Environmental Protection Act, 1986 & other pollution control Acts.

Note: The above Acts are only indicative and not exhaustive. The Acts shall include the rules and regulations framed thereunder.

35.0 LABOUR LAWS:

i) CONTRACTOR shall comply with the provisions of various labour related laws, including but not limited to the Code of Wages, 2019, Employee Provident Fund and Miscellaneous Provisions Act 1952, COMPANY's Liability Act 1938,

Employees' Compensation Act 1923, Industrial Disputes Act 1947, the Maternity Benefit Act 1961 and Contract Labour (Regulation and Abolition) Act 1970, Employment of Children Act 1938, Employees' State Insurance Act, 1948 or any modifications/amendment thereof or any other law relating thereto and rules made there under from time to time.

- ii) No Labour below the age of eighteen [18] years shall be employed on the work.
- iii) CONTRACTOR shall not pay less than what is provided under law to labourers engaged by him on the work.
- iv) CONTRACTOR shall at his expense comply with all labour laws and keep the COMPANY indemnified in respect thereof.
- v) CONTRACTOR shall pay equal wages for men and women in accordance with applicable Labour laws.
- vi) If the CONTRACTOR is covered under the Contract Labour (Regulation and Abolition) Act, he shall obtain a license from licensing authority [i.e. office of the Labour Commissioner] by payment of necessary prescribed fee and the deposit, if any, before starting the work under the Contract. Such fee/deposit shall be borne by the CONTRACTOR.
- vii) CONTRACTOR must obtain the PF Code from the concerned PF Authority under Employees Provident Fund and Miscellaneous Provisions Act, 1952. Similarly, CONTRACTOR must obtain ESI Code under Employees State Insurance Act.
- viii) CONTRACTOR being the employer of the labours/personnel to be engaged under the contract shall be liable to pay gratuity to the labours/personnel as per the provision of the Payment of Gratuity Act, 1972 and accordingly, shall keep the COMPANY indemnified in respect thereof. If however, COMPANY requires to pay gratuity to such labour(s) as per the direction of the competent authority under the Act, COMPANY shall recover such amount from the outstanding dues payable to the CONTRACTOR under the contract or any other contract(s).
- ix) CONTRACTOR shall furnish to Engineer in Charge the distribution return of the number & description, by trades of the work people employed on the works. CONTRACTOR shall also submit on the 4th& 19th of every month to Engineer in Charge a true statement showing in respect of the 2nd half of the preceding month & the 1st half of the current month (1) the accidents that occurred during the said fortnight showing the circumstances under which they happened and the extent of damage and injury caused by them and (2) the number of female workers who have been allowed Maternity Benefit as provided in the Maternity Benefit Act 1961 on Rules made there under and the amount paid to them.
- x) Engineer in Charge shall on a report having been made by an inspecting officer as defined in Contract Labour (Regulation and Abolition) Act 1970 have the power to deduct from the money due to the CONTRACTOR any sum required or estimated to be required for making good the loss suffered by a worker or

workers by reason of non-fulfillment of the conditions of the Contract for the benefit of workers, non-payment of wages or of deductions made from his or their wages which are not justified by the terms of the Contract or non-observance of the said regulations.

xi) The CONTRACTOR shall indemnify the COMPANY against any payments to be made under and for the observance of the provisions of the aforesaid acts without prejudice to his right to obtain indemnity from his sub-CONTRACTOR.

36.0 STATUTORY REQUIREMENTS:

During the tenure of this CONTRACT nothing shall be done by the CONTRACTOR in contravention of any law, act and/or rules/regulations, thereunder or any amendment.

37.0 GENERAL HEALTH, SAFETY & ENVIRONMENT (HSE) GUIDELINES:

- 37.1 It will be solely the CONTRACTOR's responsibility to fulfil all the legal formalities with respect to the Health, Safety and Environmental aspects of the entire job (namely; the person employed by him, the equipment, the environment, etc.) under the jurisdiction of the district of that state where it is operating. Ensure that all sub-CONTRACTORs hired by CONTRACTOR comply with the same requirement as the CONTRACTOR himself and shall be liable for ensuring compliance all HSE laws.
- 37.2 will the It be entirely responsibility of the Contractor/his Supervisor/representative to ensure strict adherence to all HSE measures and statutory rules during operation in OIL's installations and safety of workers engaged by him. The crew members will not refuse to follow any instruction given bv company's Installation Manager/Safety Officer/ Engineer/Official/Supervisor/Junior Engineer for safe operation.
- Any compensation arising out of the job carried out by the Contractor whether related to pollution, Safety or Health will be paid by the contractor only.
- Any compensation arising due to accident of the Contractor's personnel while carrying out the job, will be payable by the contractor.
- When there is a significant risk to health, environment or safety of a person or place arising because of a non-compliance of HSE Measures Company shall have the right to direct the contractor to cease work until the non-compliance is corrected.

38.0 POLLUTION AND CONTAMINATION:

The CONTRACTOR shall be liable for all surface and sub-surface pollution to the extent caused by CONTRACTOR and resulting from CONTRACTOR's operation/service or spillage or dumping of solvents/additive substances or pollutants, which the CONTRACTOR brings to the Site for use in connection with Work to be performed under this Contract.

Notwithstanding anything to the contrary contained herein, it is agreed that except on the ground of willful misconduct or criminal misconduct, COMPANY shall release, indemnify and hold CONTRACTOR and its sub-CONTRACTORs harmless from any and all claims, judgments, losses, expenses and any costs related thereto (including but not limited to Court costs and "Attorney's fees") for:

- a) Damage to or loss of any reservoir or producing formation; and/or
- b) Damage to or loss of any well; and/or
- c) Any other subsurface damage or loss; and/or
- d) Any property damage or loss or personal injury or death arising out of or in connection with a blowout, fire explosion and loss of well control regardless of cause.

39.0 STATUTORY VARIATION/NEWLY ENACTED LAW:

- All duties, taxes except otherwise specified in the Contract as applicable on the closing date of bid submission as per relevant acts and rules shall be in CONTRACTOR's account. Variation in case of custom duty on CIF value declared by the bidder shall be to COMPANY account.
- 39.2 In the event of introduction of any new legislation or any amendment or enforcement of any Act or Law, rules or regulations of Government of India or State Government(s) or Public Body, which becomes effective after the date of submission of Price Bid or revised price bid, if any, for this CONTRACT and which results in increased/decreased cost of the works under the CONTRACT through increased/decreased liability of taxes and/or duties, required to be paid by the CONTRACTOR, (other than personnel and Corporate taxes), the Parties shall agree to a revision in pricing to reflect such change subject to the production of documentary the satisfaction proof to COMPANY/CONTRACTOR as applicable to the extent which directly is attributable to such introduction of new legislation or change or amendment as mentioned above and adjudication by the competent authority (applicable when disputed by COMPANY) & the courts wherever levy of such taxes/duties are disputed by COMPANY/CONTRACTOR.
- Any increase in net amount of the duties and taxes (i.e. the amount of taxes/duties payable minus eligible credit of taxes/duties paid on input services/inputs) after the contractual completion/mobilization date during the extended period will be to the CONTRACTOR's account, where delay in completion/mobilization period is attributable to the CONTRACTOR. However, any decrease in net amount of the duties and taxes (i.e. the amount of taxes/duties payable minus eligible credit of taxes/duties paid on input

- services/inputs) after the contractual completion/mobilization date will be to COMPANY's account.
- The Contract Price and other prices given in the Schedule of Prices are based on the applicable tariff as indicated by the CONTRACTOR in the Schedule of Prices. In case this information subsequently proves to be wrong, incorrect or misleading, COMPANY will have no liability to reimburse/pay to the CONTRACTOR the excess duties, taxes, fees, if any finally levied/imposed by the concerned authorities. However, in such an event, COMPANY will have the right to recover the difference in case the rate of duty/tax finally assessed is on the lower side.
- **39.5** Notwithstanding the provision contained in Clause-39.1 to 39.4 above, the COMPANY shall not bear any liability in respect of:
- i. Personal taxes on the personnel deployed by CONTRACTOR, his sub-CONTRACTOR/sub-sub-CONTRACTORs and Agents etc.
- ii. Corporate taxes and Fringe benefit tax in respect of CONTRACTOR and all of their sub-CONTRACTORs, agents etc.
- iii. Other taxes & duties including Customs Duty and GST in addition to new taxes etc. in respect of sub-CONTRACTORs, vendors, agents etc. of the CONTRACTOR.
- iv. Any liability on the CONTRACTOR, which was accrued under the old law or contract, which the CONTRACTOR is obligated to pay either to the COMPANY or to the Government Authority.
- 39.6 In order to ascertain the net impact of the amendment/ revisions/enactment of various provisions of taxes/duties, the CONTRACTOR is liable to provide following disclosure to COMPANY:
- i. Details of each of the input services used in relation to providing service to COMPANY including estimated monthly value of input service and GST tax amount.
- ii. Details of Inputs (material/consumable) used/required for providing service to COMPANY including estimated monthly value of input and GST paid/payable on purchase of inputs.
- 39.7 The above provisions would be applicable only in case of variation in rate of taxes and duties on supply of services to OIL and not applicable on taxes and duties on input (goods and services) towards such services.
- **39.8** Any claim or reduction on account of change in law shall be accompanied with undertaking that the provisions of anti-profiteering clause under GST Act have been complied with.

40.0 SEVERABILITY:

Should any provision of this agreement be found to be invalid, illegal or otherwise not enforceable by any court of law, such finding shall not affect the remaining provisions hereto and they shall remain binding on the parties hereto.

41.0 Commission of misconduct/submission of fraudulent document by the bidder/contractor and Banning thereof:

The information and documents furnished by the bidder/CONTRACTOR in respect of the tender/contract are accepted by COMPANY to be true and genuine. However, if it comes to the notice of the COMPANY anytime either during the pendency of the tender or after award of the contract or after completion the contract that a Bidder/CONTRACTOR furnished fraudulent document/false information in relation to the subject tender/contract or committed any misconduct, appropriate action shall be taken against the Bidder/CONTRACTOR for debarment/banning of the bidder/CONTRACTOR from participating in any future tender of the COMPANY in terms of the COMPANY's Banning Policy, 2017 besides making the CONTRACTOR liable for other penal action including termination of ongoing contract(s) at his/her risk and peril. In such event, the Bid Security/Performance Security in respect of ongoing contract(s) shall be forfeited by the COMPANY.

42.0 SETTLEMENT OF DISPUTES:

42.1 Arbitration (Applicable for Suppliers/CONTRACTORs other than PSU and MSME):

- 1. Except as otherwise provided elsewhere in the contract, if any dispute, difference, question or disagreement arises between the parties hereto or their respective representatives or assignees, in connection with construction, meaning, operation, effect, interpretation of the contract or breach thereof which parties are unable to settle mutually, the same shall be referred to Arbitration as provided hereunder:
- 2. A party wishing to commence arbitration proceeding shall invoke Arbitration Clause by giving 30 days' notice to the other party. The notice invoking arbitration shall specify all the points of dispute with details of the amount claimed to be referred to arbitration at the time of invocation of arbitration and not thereafter. If the claim is in foreign currency, the claimant shall indicate its value in Indian Rupee for the purpose of constitution of the arbitral tribunal.
- 3. It is agreed and undertaken by the Parties that irrespective of country of origin of the CONTRACTOR, the arbitration proceedings shall be governed by the Arbitration and Conciliation Act, 1996 and under no circumstances, the proceedings shall be construed as International Arbitration.

4. The number of arbitrators and the appointing authority will be as under:

Claim amount (excluding claim for interest and counter claim, if any)	Number of Arbitrator	Appointing Authority
Upto Rs.25.00 Lakh	Not applicable	Not applicable
Above Rs.25.00 Lakh Upto Rs.25 Crore	Sole Arbitrator	OIL
Above Rs. 25 Crore	3 Arbitrators	One Arbitrator by each party and the 3 rd Arbitrator, who shall be the presiding Arbitrator, by the two Arbitrators.

- 5. The parties agree that they shall appoint only those persons as arbitrators who accept the conditions of the arbitration clause. No person shall be appointed as Arbitrator or Presiding Arbitrator who does not accept the conditions of the arbitration clause.
- 6. If any of the Arbitrators so appointed dies, resigns, becomes incapacitated or withdraws for any reason from the proceedings, it shall be lawful for the concerned party/arbitrators to appoint another person in his place in the same manner as aforesaid. Such person shall proceed with the reference from the stage where his predecessor had left if both parties consent for the same; otherwise, he shall proceed de novo.
- 7. Parties agree and undertake that neither shall be entitled for any pre-reference or pendente-lite interest on its claims. Parties agree that any claim for such interest made by any party shall be void.
- 8. The arbitral tribunal shall complete the proceedings, make and publish the award within time stipulated in the Arbitration and Conciliation Act, 1996(as amended).
- 9. If after commencement of the arbitration proceedings, the parties agree to settle the dispute mutually or refer the dispute to conciliation, the arbitrators shall put the proceedings in abeyance until such period as requested by the parties. Where the proceedings are put in abeyance or terminated on account of mutual settlement of dispute by the parties, the fees payable to the arbitrators shall be determined as under:
 - (i) 20% of the fees if the claimant has not submitted statement of claim.
 - (ii) 40% of the fees if the pleadings are complete

- (iii) 60% of the fees if the hearing has commenced.
- (iv) 80% of the fees if the hearing is concluded but the award is yet to be passed.
- 10. Each party shall be responsible to make arrangements for the travel and stay etc. of the arbitrator appointed by it. Claimant shall also be responsible for making arrangements for travel/stay arrangements of the Presiding Arbitrator and the expenses incurred shall be shared equally by the parties.
 - In case of sole arbitrator, both parties shall equally share all expenditures that may be required to be incurred.
- 11. The fees and other administrative/secretarial expenses of the arbitrator(s) shall not exceed the model fee as stipulated in Schedule of the Act and such expenses shall be equally borne by the parties.
- 12. The Place/Seat of Arbitration shall be Guwahati or the place where the contract is executed. The venue of the arbitration shall be decided by the Arbitrator(s) in discussion with the parties. The cost of arbitration sittings shall be equally borne by the parties.
- 13. The Arbitrator(s) shall give reasoned and speaking award and it shall be final and binding on the parties.
- 14. Subject to aforesaid, provisions of the Arbitration and Conciliation Act, 1996 and any statutory modifications or re-enactment thereof shall apply to the arbitration proceedings under this clause.

42.2 Arbitration (applicable in case of Contract awarded on Public Sector Enterprise):

- a) In the event of any dispute or difference relating to the interpretation and application of the provisions of commercial contract (s) between Central Public Sector Enterprises (CPSEs) and also between CPSEs and Government Departments/Organizations (excluding disputes -concerning Railways, Income Tax, Customs & Excise Departments), such dispute or difference shall be taken up by either party for resolution through AMRCD as mentioned in OPE OM No. 4(1)/2013-DPE(GM)/FTS-1835 dated 22-05-2018.
- b) A party wishing to commence arbitration proceeding shall invoke Arbitration Clause and refer the dispute(s) to AMRCD with a copy to the other party. The notice invoking arbitration shall specify all the points of dispute with details of the amount claimed to be referred to arbitration at the time of invocation of arbitration and not thereafter.
- c) Upon such reference, the dispute shall be decided by the Competent Authority appointed under the AMRCD, whose decision shall bind the parties finally and

conclusively. The parties in the dispute will share equally the cost of the arbitration as intimated by the Arbitrator.

42.3 Arbitration (Applicable to Micro, Small and Medium Enterprise)

In the event of any dispute or difference relating to, arising from or connected with the Contract, efforts shall be made to resolve the dispute(s) amicably by mutual consultation and in case such dispute(s) cannot be resolved through mutual consultation, then same shall be resolved through the procedure as prescribed in Section-18 of the Micro, Small and Medium Enterprises Development Act, 2006.

42.4 Resolution of disputes through conciliation by OEC

(Not Applicable in cases where value of dispute is less than Rs. 25 Lakhs and more than 2 Crore)

If any dispute, difference, question or disagreement arises between the parties hereto or their respective representatives or assignees, in connection with construction, meaning, operation, effect, interpretation of the contract or breach thereof which parties are unable to settle mutually, Company at its discretion, on its own or on the request of the CONTRACTOR, may refer the dispute to Outside Expert Committee ("OEC") to be constituted by Corporate Business Committee (CBC), OIL as provided hereunder:

- a) The party desirous of resorting to conciliation shall send a notice of 30 (thirty) days to the other party of its intention of referring the dispute for resolution through OEC. The notice invoking conciliation shall specify all the points of disputes with details of the amount claimed to be referred to OEC and the party concerned shall not raise any new issue thereafter.
- b) OIL shall nominate three outside experts, one each from Financial/commercial, Technical and Legal fields from the Panel of Outside Experts maintained by OIL who shall together be referred to as OEC (Outside Experts Committee).
- c) Parties shall not claim any interest on claims/counterclaims from the date of notice invoking conciliation till execution of settlement agreement, if so arrived at. In case, parties are unable to reach a settlement, no interest shall be claimed by either party for the period from the date of notice invoking conciliation till the date of OEC recommendations in any further proceeding.
- d) The Proceedings of the OEC shall be broadly governed by Part III of the Arbitration and Conciliation Act, 1996 including any modifications thereof. Notwithstanding above, the proceedings shall be summary in nature and Parties agree to rely only upon documentary evidence in support of their claims and not to bring any oral evidence in the OEC proceedings.

- e) OEC shall hear both the parties and recommend possible terms of settlement between the parties. The recommendations of OEC shall be non-binding and the parties may decide to accept or not to accept the same. Parties shall be at liberty to accept the OEC recommendation with any modification they may deem fit.
- f) Where recommendations are acceptable to both the parties, a settlement agreement will be drawn up in terms of the OEC recommendations or with such modifications as may be agreed upon by the parties. The settlement agreement shall be signed by both the parties and authenticated by all the OEC members either in person or through circulation. This settlement agreement shall have the same legal status and effect as that of an arbitration award on agreed terms on the substance of the dispute rendered by an arbitral tribunal under Section 30 of the Arbitration and Conciliation Act, 1996.
- g) OIL will share all other guidelines regarding reconciliation through OEC with the CONTRACTOR when it resorts to settlement through OEC. Both parties agree to adhere to these guidelines.
- h) All the expenditure incurred in the OEC proceedings shall be shared by the parties in equal proportion. The parties shall maintain account of expenditure and present to the other for the purpose of sharing on conclusion of the OEC proceedings.
- i) The OEC proceedings must be completed within a period of 3(three) months from the date of constitution of the OEC with a provision of extension of one months, subject to mutual agreement. The Place of OEC shall be either at New Delhi or Guwahati.
- j) If the parties are not able to resolve the dispute through OEC or do not opt for conciliation through OEC, the party may invoke arbitration clause as provided in the contract.
- k) The parties shall be represented by their in-house employees/executives. No party shall bring any advocate or outside consultant/advisor/agent. Ex-officers of OIL who have handled the matter in any capacity directly or indirectly shall not be allowed to attend and present the case before OEC on behalf of Contractor. However, ex- employees of parties may represent their respective organizations.
- Solicitation or any attempt to bring influence of any kind on either OEC Members or OIL is completely prohibited in conciliation proceedings and OIL reserves the absolute right to close the conciliation proceedings at its sole discretion if it apprehends any kind of such attempt made by the Contractor or its representatives.

42.5 Exclusions

Parties agree that following matters shall not be referred to conciliation or arbitration:

- i) Any claim, difference or dispute relating to, connected with or arising out of OIL's decision to initiate any proceedings for suspension or debarment or banning, or decision to suspend or to ban or to debar business dealings with the bidder/CONTRACTOR and/or with any other person involved or connected or dealing with bid/contract/bidder/CONTRACTOR.
- ii) Any claim, difference or dispute relating to, connected with or arising out of OIL's decision under the provisions of Integrity Pact executed between OIL and the Bidder/CONTRACTOR.
- iii) Any claim, difference or dispute relating to, connected with or arising out of OIL's decision to comply with any order or directive of any statutory or government authority.
- iv) Any claim which is less than Rs. 25 Lakh.

43.0 COMPLETION OF CONTRACT:

Unless otherwise terminated under the provisions of any other relevant Clause or extended through written communication, this Contract shall be deemed to have been completed at the expiry of the Period specified in the contract or period of defect liability, as provided for under the Contract, whichever is later.

44.0 TERMINATION:

- **44.1 Termination on expiry of the contract**: This Agreement shall be deemed to have been automatically terminated on the expiry of the contract period unless OIL has exercised its option to extend this contract in accordance with the provisions, if any, of this contract.
- **44.2 Termination of contract for death**: If the CONTRACTOR is an individual or a proprietary concern and the individual or the proprietor dies or if the CONTRACTOR is a partnership concern and one of the partners dies then unless, the COMPANY is satisfied that the legal heir of the individual or the proprietary concern or the surviving partners are capable of carrying out and completing Contract, the COMPANY is entitled to cancel the Contract for the uncompleted part without being in any way liable for any compensation payment to the estate of the deceased CONTRACTOR and/or to the surviving partners of the CONTRACTOR's firm on account of the cancellation of Contract. The decision of the COMPANY in such assessment shall be final & binding on the parties. In the event of such cancellation, the COMPANY shall not hold the

estate of the deceased CONTRACTOR and/or the surviving partners of CONTRACTOR's firm liable for any damages for non-completion of the Contract.

- **44.3 Termination on account of Force Majeure**: Unless the contract provides otherwise, either party shall have the right to terminate this Contract on account of Force Majeure as set forth in Article-31.0 above.
- 44.4 Termination on account of insolvency: In the event that the CONTRACTOR or its collaborator or its guarantor at any time during the term of the Contract, becomes insolvent or makes a voluntary assignment of its assets for the benefit of creditors or is adjudged bankrupt or under the process of insolvency or liquidation, then the COMPANY shall, by a notice in writing have the right to terminate the Contract and all the CONTRACTOR's rights and privileges hereunder, shall stand terminated forthwith.

However, COMPANY shall be at liberty to give the Receiver or Liquidator or Insolvency Professional Manager, as appointed by the Competent Court/Tribunal, the option of carrying out the Contract subject to its technical & financial competence and his providing a guarantee for due and faithful performance of the Contract.

- 44.5 Termination for Unsatisfactory Performance: If the COMPANY considers that, the performance of the CONTRACTOR is unsatisfactory, or not as per the provision of the Contract, the COMPANY shall notify the CONTRACTOR in writing and specify in details the cause of dissatisfaction. The COMPANY shall have the option to terminate the Contract by giving 15 days notice in writing to the CONTRACTOR, if CONTRACTOR fails to comply with the requisitions contained in the said written notice issued by the COMPANY. In the event CONTRACTOR rectifies its non-performance to the satisfaction of the COMPANY, the option of termination may not be exercised by the COMPANY. If however CONTRACTOR repeats non-performance subsequently, COMPANY shall exercise the option to terminate contract by giving 07 days notice. Such CONTRACTOR shall be put on holiday as per the Banning Policy of OIL [available at www.oil-india.in].
- 44.6 Termination due to change of ownership and Assignment: In case the CONTRACTOR's rights and/or obligations under this Contract and/or the CONTRACTOR's rights, title and interest to the equipment/ material, are transferred or assigned without the COMPANY's written consent, the COMPANY may at its option, terminate this Contract. COMPANY shall not be however under any obligation to accord consent to the CONTRACTOR for change of ownership & assignment of the contract.
- 44.7 If at any time during the term of this Contract, breakdown of CONTRACTOR's equipment results in CONTRACTORs being unable to perform their obligations hereunder for a period of 15 successive days, COMPANY at its option, may terminate this Contract in its entirely or partially to the extent non-performance, without any further right or obligation on the part of the COMPANY, except for

the payment of money then due. No notice shall be served by the COMPANY under the condition stated above.

- 44.8 Termination for delay in mobilization: CONTRACTOR is required to mobilize complete equipment alongwith crew for commencement of services at the specified site within the maximum allowed number of days from the date of LOA/Notice for Mobilization as specified in the special conditions of contract. If the CONTRACTOR (successful bidder) fails to complete the mobilization as above, OIL shall have, without prejudice to any other clause of the CONTRACT, the right to terminate the contract.
- 44.9 Notwithstanding any provisions herein to the contrary, the Contract may be terminated at any time by the COMPANY on giving 30 (thirty) days written notice to the CONTRACTOR due to any other reason not covered under the above Article from 44.1 to 44.8 and in the event of such termination the COMPANY shall not be liable to pay any cost or damage to the CONTRACTOR except for payment of services as per the Contract upto the date of termination.
- **44.10 Consequence of Termination**: In all cases of termination herein set forth, the relative obligations of the parties to the Contract shall be limited to the period up to the date of termination. Notwithstanding the termination of this Contract, the parties shall continue to be bound by the provisions of this Contract that reasonably require some action or forbearance after such termination.

Upon termination of this Contract, CONTRACTOR shall return to COMPANY all of COMPANY's properties, which are at the time in CONTRACTOR's possession.

In the event of termination of contract, COMPANY will issue Notice of termination of the contract with date or event after which the contract will be terminated. The contract shall then stand terminated and the CONTRACTOR shall demobilize their personnel & materials.

Demobilization charges shall not be payable by COMPANY in case of Article from 44.4 to 44.7.

45.0 TO DETERMINE THE CONTRACT:

In such an event (i.e. termination under Article No. 44.4 to 44.9 above), the contract shall stand terminated and shall cease to be in force from the date of such notification by the COMPANY. Thereafter the CONTRACTOR shall stop forthwith any of the work then in progress, except those work which the COMPANY may, in writing, require to be done to safeguard any property or work, or installations from damages, and the COMPANY may take over the remaining unfinished work of the CONTRACTOR and complete the same through a fresh CONTRACTOR or by other means, at the risk and cost of the CONTRACTOR, and any of its sureties if any, shall be liable to the COMPANY for any excess cost occasioned by such work having to be so taken over and completed by the

COMPANY over and above the cost at the rate/cost specified in the schedule of quantities and rates/prices.

46.0 WITHOUT DETERMINING THE CONTRACT:

In such an event (i.e. termination under Article No. 44.4 to 44.9 above), the Company may take over the work of the CONTRACTOR or any part thereof and complete the same through a fresh CONTRACTOR or by other means, at the risk and cost of the CONTRACTOR. The CONTRACTOR and any of its sureties are liable to the COMPANY for any excess cost over and above the cost at the rates specified in the schedule of quantities and rates/prices, occasioned by such work having been taken over and completed by the COMPANY.

47.0 ERRING/DEFAULTING AGENCIES:

Erring and defaulting agencies like bidder, CONTRACTOR, supplier, vendor, service provider will be dealt as per OIL's Banning Policy dated 6th January, 2017 available in OIL's website: www.oil-india.com. Moreover, OIL reserves the right to take legal or any other action on the basis of merit of the case.

48.0 MISCELLANEOUS PROVISIONS:

CONTRACTOR shall give notices and pay all fees at their own cost required to be given or paid by any National or State Statute, Ordinance, or other Law or any regulation, or bye-law of any local or other duly constituted authority as may be in force from time to time in India, in relation to the performance of the services and by the rules & regulations of all public bodies and companies whose property or rights are affected or may be affected in any way by the services.

CONTRACTOR shall conform in all respects with the provisions of any Statute, Ordinance of Law as aforesaid and the regulations or bye-law of any local or other duly constituted authority which may be applicable to the services and with such rules and regulation, public bodies and Companies as aforesaid and shall keep COMPANY indemnified against all penalties and liability of every kind for breach of any such Statute, Ordinance or Law, regulation or bye-law.

During the tenure of the Contract, CONTRACTOR shall keep the site where the services are being performed reasonably free from all unnecessary obstruction and shall store or dispose of any equipment and surplus materials and clear away and remove from the site any wreckage, rubbish or temporary works no longer required. On the completion of the services, CONTRACTOR shall clear away and remove from the site any surplus materials; rubbish or temporary works of every kind and leave the whole of the site clean and in workmanlike condition to the satisfaction of the COMPANY.

Key personnel cannot be changed during the tenure of the Contract except due to sickness/death/resignation of the personnel or any other justified situation in which case the replaced person should have equal experience and qualification, which will be again subject to prior approval, by the COMPANY.

END OF SECTION-I

Part-3 SECTION-II

TERMS OF REFERENCE AND TECHNICAL SPECIFICATIONS

- **1.0 INTRODUCTION:** This section establishes the scope and describes the specifications, instructions, standards and other documents including the specifications for any tools or equipment, which the bidder shall satisfy or adhere to in the performance of the work.
- 2.0 **DEFINITION OF WORK**: To provide 01(one)/02 (two) number of mobile Work-over rigs with associated equipment / tools & services on hiring for an initial period of 3 (three) years with provision for extension for a further period of 1 (one) year or till the completion/ abandonment of last well on same terms & conditions and at mutually agreed rates but not higher than the original rates of the Contract. The rig provided by the contractor will be utilized by Oil India Ltd. for work-over operations either straight vertical holes or planned deviated holes Well depths are expected to be in the depth range of 2500 6000 metres. Depths of the wells, where operations are to be carried out, may somewhat increase or decrease at the discretion of the company within the rated capacity of the rig.

2.1 WORKOVER JOBS INCLUDING BUT NOT LIMITED TO THE FOLLOWING JOBS:

- a) Re-completion of well with/without Gas Lift valves, packer with/ without electrical submersible pumps and sucker rod pumps.
- b) Fishing operations e.g. fishing of swabbing tools, logging tools, tubing, drill pipe, packers, piano wire, scrappers etc. and re-completion of well.
- c) Extension of perforation/re-perforation with/without plugging back and subsequent operation to bring the well into production.
- d) Isolation of zones by setting cement plug/ packers and repairs.
- e) Stimulations acidization, hydro-fracturing propant
- f) Sand control using gravel packing/ screens consolidated pack
- g) Sand/cement cleaning and re-completion of wells.
- h) Milling operations e.g. milling of packers, bottom hole junks, bridge plug, cement retainer and metallic obstructions.
- i) Water shut off job e.g. squeezing cement, sodium ortho-silicate polymer solution or any other technique.
- i) Drilling of cement plug
- k) Surfactant jobs
- 1) Other allied miscellaneous work over jobs as may be decided by the company.
- 2.2 **GUIDELINES**: Recommended safe procedures & guidelines should be followed while carrying out work over & well stimulation operation. [OISD-182]

3.0 **AREA OF OPERATION**:

- 3.1 The area of the operation as planned is in Assam & Arunachal Pradesh.
- 3.2 The following information is for general guidelines to the bidders:
 - (a) Minimum width of the well site approach road: 3.66 m
 - (b) Turning Radius: 15 m (Generally), 12 m (exceptionally)
 - (c) Maximum allowable unit load inclusive of fare weight for Class AA loading: 50 tones

- (d) Maximum overhead clearance: 4.25 m.
- (e) Highest recorded wind velocity in Assam 80km/hour (60 MPH).
- (f) Max. Recorded ambient temp: 40° Celcius
- (g) Min. recorded ambient temp: 8° Celcius
- (h) Weather Pattern Frequent rains from March to September and occasional during the remaining period.
- (i) Nature of top soil usually Clay/Alluvium/ Unconsolidated.
- (j) Source of water: Through shallow bore wells. In rare cases, where water cannot be drawn from bore wells, water is to be drawn from nearby rivers, pond or water body etc. nearer to the well site.
- (k) Average annual rainfall: 250 / 300 cm.
- (1) Humidity: Max. 98%.
- (m) Allowable axle load rating of weakest section of road: 2 Tons/Sqm
- 4.0 **SCOPE OF SERVICE**: The successful bidder shall provide rig package along with all necessary equipment as listed to carryout Work-over operations in accordance with the completion programme. Apart from this, the successful bidder shall also provide spares for the entire rig package with operating crew at all time for uninterrupted progress of work and make available all items mentioned herein ready for use.
- 5.0 **PRESENCE OF CO2 & H2S**: Presence of CO2 in minor amounts is expected in the wells. The wells are expected to be H2S free. Accordingly, the equipment/ tools etc. to be offered by the Contractor shall be for generally H2 S free environment.
- 6.0 **TECHNICAL SPECIFICATION OF RIG PACKAGE TO BE OFFERED BY BIDDER**: The successful bidder shall mobilize all necessary equipment and tools for successful and economic completion of the Work-over operation. The necessary technical details & literature of the Rig, tools and equipment such as Engine, Pump, transmission, Reduction box, Torque Converter etc. are to be submitted along with the technical bid.
- 7.0 SPECIFICATIONS OF WORKOVER RIG AND ALL THE EQUIPMENTS/ ACCESSORIES TO BE PROVIDED ALONG WITH EACH RIG:
- 7.1 SELF-PROPELLED 550HP [min] 750 HP (Max) MOBILE WORK-OVER RIG complete with the following:

(a) **DRAW WORKS**:

- i) Min. Input horsepower rating: 550 hp (410 kW).
- ii) Nominal depth rating: 6096 m (20000 ft) with 2.7/8" OD EUE Tubing 3048m (10000ft) with 3.1/2"OD drill pipe
- iii) Hoisting capacity: 138 tons (125 MT or Tonnes).
- iv) Deleted
- v) HYDROMATIC BRAKE: Water-cooled Hydromatic brake or equivalent, driven by a suitable twin-disc clutch (any make) with independent oil bath chain case to serve as assist brake, with suitable capacity water tank, valves and piping installed on the carrier. Disc brake [shaft mounted] in lieu of hydromatic shall also be acceptable.

- vi) TWIN STOP DEVICE (CROWN & FLOOR SAVER): One (1) pneumatically or electronically activated or equivalent Twin-stop Device: Crown Saver to prevent collision between traveling block assembly and the crown block assembly, Floor Saver to prevent collision between the traveling block assembly and the drill floor
- (b) **DRILLER'S CONSOLE**: The following instruments should be provided as noted below:
 - i) Weight Indicator, Martin Decker or equivalent make with suitable sensator. Should be complete with 6 lines & 8 lines dials for 1" or 1.1/8" [Calibration certificate shall be provided].
 - ii) Mud pressure gauges 0-10,000/ 0-6,000 psi. The mud pressure gauge system should have one (1) gauge for standpipe and one (1) for annulus pressure.
 - iii) Suitable recorder for recording hook load.
 - iv) SPM indicator for mud pump at driller's console

<u>Note</u>: Rig instrumentation should be suitable for Hazardous area as per OMR-2017. (For electric and electronic instrument should be as per OMR 2017 and amend time to time)

(c) **MAST**:

- i) Two-section Telescoping Mast manufactured & monogrammed per API Spec 4F, with hydraulic mast tilting & extending systems and automatic locking device to lock the mast into its fully extended operating position.
- ii) Crown block assembly should be complete with sheaves for cat-line, sand-line, sheave units for rig tongs, power tong/pipe spinner.
- iii) Clear height (below crown) from the ground: 108-112 feet [Approx.]. 104-124 feet may also be agreed. However, the height should be sufficient enough to handle range-2 tubing.
- iv) Static hook load capacity: Min 250,000 lbs with 8 lines strung.
- v) Wind load resistance with full set back: Minimum 40 mph (64kmph) without guy lines.
- vi) Minimum 150 Ton (136 Tonnes) capacity Crown Block Assembly with adequate no. of sheaves for stringing up 8 lines.
- vii) Mast load & wind guy lines.
- viii) Sheaves for catline, sandline, sheave units for rig tongs, power tong / pipe spinner

(d) **SUB-STRUCTURE**:

Substructure assembly with provisions for mounting 17.1/2"/20.1/2" Rotary Table, manufactured & monogrammed per API Spec 4F.

- i) Floor height adjustable from 10 ft to 14 ft. Fixed heights of 14 ft also acceptable.
- ii) Minimum clear height under Rotary beams: 7 ft (When adjusted at 10 ft height).
- iii) Static Rotary Capacity: 138 tons (276000 lbs).
- iv) Pipe Setback Capacity: 70 tons (140000 lbs).
- v) Combined Static Rotary & Setback Capacity: 416000 lbs.
- vi) Work Floor Dimensions: Min. 15 ft x 15 ft
- (e) **TRAVELLING BLOCK AND HOOK**: 138 tons to 187 tons (125 MT to 170 MT) capacities unitized travelling block & hook assembly with 4 sheaves.
- (f) **ROTARY DRIVE**: Rotary drive, for driving 17.1/2"/20.1/2" Rotary Table by means of suitable pneumatic clutch drive or equivalent from the rotary counter shaft, sprocket for rotary table and with provision for reverse rotation.
- (g) **SERVICE WINCH**: Hydraulic winch with wire line, tail chain, control valve & hoses installed having bare drum line pull capacity of 5000lbs.
- (h) **HYDRAULIC SYSTEM**: Suitable for heavy duty power tubing tong, raising & lowering the mast, and hydraulic winch. May be single or double, hydraulic pumps of suitable capacity, completed with necessary hydraulic circuit and accessories. The system should be capable of operating properly the Telescopic Rams of the Rig for rigging up or down the mast, the hydraulic motor to operate the winch and hydraulic subs. Preferably, the hydraulic pumps should be driven by the PTOs fitted with the Transmission.
- (i) **ROTARY TABLE**: Rotary Table with 17.1/2" / 20.1/2" opening complete with master bushings with a static load rating of min 250 tons.
- (j) **ROTARY SWIVEL**: Swivel having dead load rating of 150-200 T with 5000 PSI working pressure and complete with bail bumper support, goose neck connection to rotary hose etc. Swivel pin connection should be 3.1/2" / 4.1/2" API regular left hand with matching cross-over.
- (k) **ELEVATOR LINKS**: 150 T Welds less elevator links. The links should be compatible to Travelling block & Hook. One set of extra long link for 2 Rigs (preferably 12 ft -15ft) shall have to be provided by the Contractor for some special operation.
- (l) **ROTARY HOSE**: Rotary hose of 2"/ 3" ID, 3000 psi working pressure, 50 ft long, conforming to API Spec. 7K with safety clamps at both ends & necessary fittings for connection to stand pipe & swivel goose neck.
- (m) **ROTARY KELLY**: Suitable Square/ Hexagonal Kelly compatible to rotary table with Kelly scabbard and matching Kelly bushing capable to work inside 5.1/2" casing.
- (n) **RIG ENGINE**: May be single or double, diesel engine with acoustic enclosure(s) [The acoustic enclosure shall be designed for minimum 25dB (A) insertion loss] capable of transmitting minimum Brake horse power of 540 HP on intermittent duty in total to the draw Works. While calculating HP of the engine (s), the entire load for accessories drive and transmission & other losses shall be taken into

account. If twin engines are supplied both the engines or either of the two engines should be capable of transmitting power either to Draw Works depending on load requirement or for road drive.

Note: Statutory requirement for SAFETY:

- (i) All the rotating parts, Belts etc. should be well guarded.
- (ii) Engine(s) should be equipped with" Emergency Kill" devices by shutting off air supply. This device should be operative from the Driller's Console.
- (iii) Engine(s) should have two systems for self starting: (a) Electrical starting system during rig movement period and (b) Air starting system during operation period inside the well plinth.
- (o) **AUXILIARY AIR COMPRESSOR**: Auxiliary Air compressor with air receiver of required capacity for operating Air starter for the Rig engines, Remote BOP control panel, Pneumatic operated Celler pump and other pneumatic controls. The prime mover engine of the Air compressor shall have to be either hand starting or electric starting. The Air compressor with Air receiver shall be mounted on a separate skid and shall be placed at a safe distance from the well. The air receiver supplied should be hydraulically tested at 1.5 times more than the working pressure. Details of testing report should be provided along with the Rig. Also date of testing should such as testing date pressure etc. to be painted in the air receiver.
- (p) **TRANSMISSION**: May be single or double, Torque converter type automatic Transmission with minimum 4 nos. Forward and 1 no. Reverse speed which is/are capable of transmitting minimum 550 HP to the Draw Works.
- 7.2(a) **WELL SERVICING PUMP**: One Diesel Engine driven well servicing pump set of following specification shall be attached with each Rig. The pumps should be equipped all the accessories such as re-adjustable safety valve, Pressure gauge, Bleed valve with manifold etc. mounted on the pump.

Type: Reciprocating, single acting-triplex or double acting duplex with replaceable liners & plungers / pistons to meet a range of discharge volumes and pressures as per operational requirements.

Discharge Capacity: 250 US GPM against 1000 PSI

50 US GPM against 5000 PSI

(Pump set should be equipped with various speed reduction Gear box to meet these parameters)

Pump Duty: Intermittent service

Well fluid to be handled:

- (i) Salt solutions: weighted & un-weighted salt solution of KCl, NaCl, Sodium Formate, Potassium Formate, CaCl2 of range 63 pcf to 82 pcf (Sp Gravity, 1.01 to 1.32).
- (ii) Other fluids like HSD, LWC, Drilling Mud, Xan-vis, Hi-vis fluid etc.
- (iii) Cement Slurry of maximum density 120 pcf (s.g 1.92)

- (iv) Acid having 10 15 % HCl, + 3 5 % HF + Water, Fluoroboric acid 8% etc.
- (b) **CEMENTING PUMP [01(One) no. between 02(Two) Rigs)]**: One Diesel Engine driven cementing Pump of following specification shall be available between the 02(Two) Rigs. The pumps should be equipped all the accessories such as readjustable safety valve, Pressure gauge, Bleed valve with manifold etc. mounted on the pump.

Type: Reciprocating, single acting-triplex or double acting duplex with replaceable liners / pistons to meet a range of discharge volumes and pressures as per operational requirements.

Discharge Capacity: Min. 200 US GPM against 450 PSI

Min 25 US GPM against 2000 PSI

(Pump set should be equipped with various speed reduction Gear box to meet these parameters)

Pump Duty: As and when required and should be available at the Rig for cementation and other related jobs

Note:

- (i) Cementation and Acidization jobs are not of regular type. These jobs may be required to carry out as per individual well's completion policy occasionally.
- (ii) The prime mover engine should preferably be Air starting.
- (c) **SOURCE WATER PUMP SETS**: 2 nos. source water pumps one running & other standby (preferably Electric motor driven) required to lift underground water for industrial uses of capacity of each 17 KL /Hr against a head of 80 M & suction lift of 8 M. Normally, water is available at 15 30 feet below the ground level.

(Note: Where source water is not available at particular well site, successful bidder will have to arrange water on their own)

(d) **PUMP SET for FILTER UNIT & BLENDER UNIT**: A separate pump set of suitable capacity (preferably Electric motor driven) which will be exclusively used for running the Filter unit and Blender unit. The electrical motors and starters/PBSs for centrifugal pumps of filter unit & blender unit shall be suitable for use in hazardous area of Zone-I and gas group IIA & IIB in oil mine and shall conform to IS/IEC/EN: 60079-0:2011 & IS/IEC/EN: 60079-1:2007.

The bidders shall submit test reports conforming to the above relevant standards from an Indian Government Laboratory or NABL accredited laboratory or IECEx accredited laboratory or ATEX notified body, which is not a part of manufacturer's facility.

7.3 **GENERATING SET**: A diesel Generating set (Twin set one running & one standby) of required KVA power considering all electrical loads which should be noise proof.

7.4 **TANKAGES for storing**:

- A. Water Tank: 1 no.: 40kl capacity
- B. For well fluid storing: 2 nos. tanks of 40 KL capacity each, 2 nos. tanks of 22Kl capacity each
- C. 01 (one) no Acid Tank of 09 KL capacity
- D. Filtered / Blended solution tank: 1 no. tank 9 KL capacity
- E. One no.: Trip tank with accessories like centrifugal pump, line to feed in hole during tripping out with arrangement to fill up tank with workover fluid from mud tank system. Trip Tank level indicator shall also be provided. The electrical motors and starters/PBSs for centrifugal pumps of trip tank shall be suitable for use in hazardous area of Zone-I and gas group IIA & IIB in oil mine and shall conform to IS/IEC/EN: 60079-0:2011 & IS/IEC/EN: 60079-1:2007. The bidders shall submit test reports conforming to the above relevant standards from an Indian Government Laboratory or NABL accredited laboratory or IECEx accredited laboratory or ATEX notified body, which is not a part of manufacturer's facility.

Note:

Mud/ Workover fluid preparation & mixing facilities:

- (i) Ramp fitted with mixing hoppers at ramp floor height, ramp area min. 300 sq. ft
- (ii) Agitators: The electrical motors and starters/PBSs for agitators shall be suitable for use in hazardous area of zone-I and gas group IIA &IIB in oil mine and shall conform to IS/IEC/EN: 60079-0:2011 & IS/IEC/EN: 60079-1:2007. The bidders shall submit test reports conforming to the above relevant standards from an Indian Government Laboratory or NABL accredited laboratory or IECEx accredited laboratory or ATEX notified body, which is not a part of manufacturer's facility.
- (iii) Bottoms guns (rotatable)
- (iv) Dedicated pumps for preparation of mixing fluid / chemicals/ mud additives. The electrical motors and starters/PBSs for pumps of chemical mixing hoppers shall be suitable for use in hazardous area of zone-I and gas group IIA &IIB in oil mine and shall conform to IS/IEC/EN: 60079-0:2011 & IS/IEC/EN: 60079-1:2007. The bidders shall submit test reports conforming to the above relevant standards from an Indian Government Laboratory or NABL accredited laboratory or IECEx accredited laboratory or ATEX notified body, which is not a part of manufacturer's facility.
- (v) Facility for inter tank fluid transfer shall be such that suction can be taken from each tank as well as delivery can also be given to any tank.
- (vi) Facility for taking fluid return during cement cleaning, milling etc.
- (vii) Suitable screen for placing over tank in well return line.
- (viii) Acid tank should have bottom suction facility without dead volume
- 7.5 **SUCTION AND DELIVERY SYSTEM**: Suction hose for pump suction lines. From pump delivery manifold suitable bleed line and valve shall be provided. Pump delivery manifold shall have arrangements for hole fill-up line and kill-line connection.

GENERAL NOTE:

(i) All the necessary pipes, fittings, valves etc. required to rig up the static and hook up the pumps shall be provided by the Contractor.

- (ii) Any other pipes, fittings, valves etc. which may be required during operation period shall be provided by the Contractor.
- (iii) Adequate length of high pressure pump delivery lines from Well Killing pump, for placement of pump at recommended distance from wellhead be provided by the Contractor.
- (iv) DELETED
- (v) Approximate transportable dimension of one rig load should be confined to 9 M (L) x 3.5 M (W) x 3 M (H).
- (vi) Supply, storage, consumption / regulation of water & fuel at the well sites as well as at the camp site shall be the contractor's responsibility. Any shut down of operation due to non-availability of water and fuel shall be on the contractor's account.
- (vii) Supply of LDO / LWC for mud preparation and for meeting other downhole eventualities will be the company's responsibility. The Contractor shall also provide fuel for all of their vehicles and other stationary engines.
- (viii) All sorts of lubricants for day to day operation of various rig equipments shall be supplied by the Contractor. Also, various spares for rig components shall be stocked / supplied by the Contractor.
- (ix) Well Logging Service: All logging requirements as depicted in the Work over programme will be met by OIL through its in-house or logging contractors' service.
- (x) Well killing: During well killing, OIL will supervise the operation, the necessary service shall be provided by the Contractor.
- 7.6 **<u>LIGHTING SYSTEM</u>**: Explosion proof, suitable for hazardous location with adequate lighting at all the important points. Mast lighting system and area lighting system should be provided with proper fixing arrangements, poles etc.

NOTE: STATUTORY REQUIREMENTS FOR ELECTRICAL ITEMS

All electrical equipment such as AC motor, starter, pressure switch, cables & conductor fittings, light fittings, Driller Remote Control Panel with all electrical accessories etc. should be suitable for use in hazardous area of zone-I and gas group IIA &IIB in oil mine and shall conform to IS/IEC/EN: 60079-0:2011 & IS/IEC/EN: 60079-1:2007 and bidders are to confirm the same while quoting.

The bidders shall submit test reports conforming to the above relevant standards from an Indian Government Laboratory or NABL accredited laboratory or IECEx accredited laboratory or ATEX notified body, which is not a part of manufacturer's facility. Copies of above certificates should be enclosed with the quotation as well as with the supply of materials.

The bidder should ensure that RED AVIATION WARNING LIGHTS on the crown of the mast have been provided as per Aviation Standards.

7.7 **OTHER EQUIPMENT**: Shall be provided under each rig:

a) Rig wise Equipment:

- i) 3.1/2" OD Drill collar: 6 Nos.
- ii) 3.1/2" Mud Motor for 5.1/2" Casing & 4.3/4" Mud motor for 7" Casing: For cement cleaning/ milling purposes. [At least one each should be ready for operation whenever required with working spares].
- iii) Casing scrapper: Suitable for 5.1/2" [17-23 ppf], 7" [23-29ppf].
- iv) Electric motor driven Blender unit: For blending/mixing viscous fluids at Work over well-sites. The blender unit tank should be cylindrical in shape (capacity 4 kl) with electrical motor driven mixer/ agitator. [With a Provision for Hopper connectivity]. The electrical motor and starter/PBS for blender unit shall be suitable for use in hazardous area of zone-I and gas group IIA &IIB in oil mine and shall conform to IS/IEC/EN: 60079-0:2011 &IS/IEC/EN: 60079-1:2007. The bidders shall submit test reports conforming to the above relevant standards from an Indian Government Laboratory or NABL accredited laboratory or IECEx accredited laboratory or ATEX notified body, which is not a part of manufacturer's facility.
- v) Filtration unit with accessories: For removing up to 2 micron fine solid contaminants from work over fluid so as to minimize damage to the formation. The filtration unit should be compact, skid mounted with motor driven centrifugal pump mounted on the same skid. The electrical motor and starter/PBS for filtration unit shall be suitable for use in hazardous area of zone-I and gas group IIA &IIB in oil mine and shall conform to IS/IEC/EN: 60079-0:2011 & IS/IEC/EN: 60079-1:2007. The bidders shall submit test reports conforming to the above relevant standards from an Indian Government Laboratory or NABL accredited laboratory or IECEx accredited laboratory or ATEX notified body, which is not a part of manufacturer's facility.
- vi) Suitable size bell nipple and flow nipple for making up at the wellhead.
- vii) FOSV for tubing: FOSV for both 2.7/8" EUE & VAM tubing

b) Other items:

- i) Dedicated Skid mounted Well site Chemical Go-down
- ii) Crew Basha
- iii) AC Tool Pusher Office
- v) AC Company Representative office
- iv) Rig Ware House
- v) First Aid Hut
- vi) Thread dope (Z-50 type) for lubrication of threads.
- 7.8 **HANDLING TOOLS**: shall be provided under each rig [All handling tools (not mentioned elsewhere) required to handle/operate tubular / equipment should be sufficiently available in working condition at site.

- (a) **Elevators**:
 - (i) For 2.7/8" EUE Tubing 2 Nos.
 - (ii) For Vam Tubing (2.93" opening) 2 Nos.
 - (iii) For 3.1/2' Drill Collar 1 No.
- (b) **Slips**:
 - (i) Rotary Hand Slip for 2.7/8" Tubing 2 Nos.
 - (ii) Rotary Hand Slip for 3.1/2" Drill Collar 1 No.
 - (iii) Spider Slip for 2.7/8" Tubing & 2.7/8" Drill pipe 1 No.
- (c) **Rig Tongs**: Complete sets of Rotary tongs in pairs with 2 sets of extra jaws and replaceable spares of required capacities & sizes to handle the following tubular:
 - (i) 2.7/8" OD Drill pipes & 3.1/2" drill collars.
 - (ii) Tubing tongs (both 2.7/8" EUE and Vam)
- (d) Power Tubing Tong: For 2.7/8" tubing
- (e) Drill Collar safety clamps: For 3.1/2" Drill Collars
- (f) Cross-over subs: For various sizes of tubular mentioned above [The bidder should provide necessary substitutes required to use 2.7/8" EUE and 2.7/8" VAM tubing connection.]
- (g) Tubing Shut-in valve (2" x 5000 psi suitable for 2.7/8" EUE and 2.7/8" Vam tubing 2 Nos.
- (h) Tubing Circulating Head suitable for 2.7/8" EUE and 2.7/8" Vam tubing: Two each
- (i) Choke and Kill Manifold: One no. Choke and Kill manifold of not less than 10M working pressure fitted with NRV in kill lines.
- (j) Chicksan Hoses: Flexible steel piping [2" 1502 chicksans 10 lops and 2" 1502 swivels 10 loops], 2" size 1502 of 10M working pr straight pipes of minimum length 170 feet.
- (k) Tubing Wiper: with heavy duty frame should be provided.
- (l) Short Joints: The following short joints of assorted length shall be provided as follows for each rig:
 - i. 2.7/8" EUE N-80 tubing short joint

= 03 nos.

ii. 2.7/8" VAM tubing short joint

= 03 nos.

- iii 2.7/8" SLH-90 drill pipe short joint (E- grade or Higher grade) = 06 nos.
- 7.9 **FISHING TOOLS**: All items, mentioned below shall have to be provided by the Contractor for each rig operations individually:
- (a) Series 150 Bowen or equivalent releasing and circulating overshot suitable for catching 2.7/8" tubing (EUE, VAM) and 2.7/8? Drill pipe and for various cross over subs to operate inside 5.1/2" OD (17-23 ppf) & 7" OD (23-29 ppf) Casings.

(Note for overshot: Overshot should be complete with standard accessories like top sub, packer, different sizes of spiral grapple with control, different sizes of basket grapple with control & mill control packer, lock rings, standard guide, oversize guide, extension sub, hook wall guide, etc. The top sub connection of the overshot should be of tubing connection.

- b) Wire line grabs, both internal & external to catch piano wire fish and sinker bars inside 5.1/2" OD (17-23 ppf) & 7" OD (23-29 ppf) Casings.
- c) Impression blocks to operate inside 5.1/2" OD (17-23 ppf) & 7" OD (23-29 ppf) Casings.
- d) Junk subs [OD: 4.1/2" & 6"] to operate inside 5.1/2" OD (17-23 ppf) & 7" OD (23-29 ppf) Casings.
- e) Reverse Circulating Junk Baskets to work inside both 5.1/2" OD x 17-23 PPF Casing & for 7" OD x 23-29 PPF Casing
- f) Skirted mill with Junk subs to work inside both 5.1/2" OD x 17-23 PPF Casing & for 7" OD x 23-29 PPF Casing for dressing fish top etc.
- g) 4.1/2" & 4.5/8" Flat Bottom Mill to work inside both 5.1/2" OD x 17-23 PPF Casing & 5.7/8" Flat Bottom Mill for 7" OD x 23-29 PPF Casing for milling Bridge Plug / Retainer Packer etc.
- h) Peripheral Milling Tool to operate inside 5.1/2" OD (17-23 ppf) & 7" OD (23-29 ppf) casing.
- i) 4.1/2" OD Tapered Mill (15 degree 7.5 degree on each side & 30 degree 15 degree on each side) to work inside 5.1/2" OD x 17-23 PPF Casing.
- j) Bowen or equivalent makes Eutectic Electrodes, Flux etc. for dressing of Mill.
- k) String Magnet to work inside 5.1/2" OD x 17-23 PPF Casing & for 7" OD x 23-29 PPF Casing.
- 1) Casing roller to work inside 5.1/2" OD x 17-23 PPF Casing.
- m) Die collar to work inside 5.1/2? (17 ppf to 23 ppf) casing and for fishing operation of different sizes of tubular and tools & equipment (one complete set with connections for 2 Rigs).
- n) Rotating and Releasing spear to work inside 5.1/2" OD x 17-23 PPF Casing
- o) Washover Shoe to work inside 5.1/2" OD x 17-23 PPF Casing
- p) Pilot Mill to work inside 5.1/2" OD x 17-23 PPF Casing
- q) Casing Scrapper to work inside 5.1/2" OD x 17-23 PPF Casing
- r) Concave Mill to work inside 5.1/2" OD x 17-23 PPF Casing.
- s) Tapered Mill to work inside 5.1/2" OD x 17-23 PPF Casing

<u>Note</u>: Sufficient stock of all the above items should be kept available at well site for necessary fishing and milling operation without any down time. All the Mills should be preferably new and shall be avoided any dressing etc.

- 7.10 **BLOW OUT PREVENTER**: [As per applicable API specifications]
 - a) One Double RAM hydraulic BOP [Cameron/Shaffer/Hydril/ Worldwide Oilfield Machine (WOM) make only] 7.1/16" x 5,000 psi flanged bottom connection and 7.1/16" x 5M studded top connection, dressed with 2.7/8" & blind rams.
 - b) 01(One) No. between 02(Two) Rigs Double RAM hydraulic BOP [Cameron/Shaffer/Hydril/ Worldwide Oilfield Machine (WOM) make only] 7.1/16" x 10,000 psi flanged bottom connection and 7.1/16" x 10M studded/flanged top connection, dressed with 2.7/8" pipe & blind rams.
 - c) Crossover flange double studded: 7.1/16" x 5M 7.1/16" x10M each rig.
- 7.11 **BOP CONTROL UNIT**: [As per API Spec. 16D]: One 20 gallon capacity BOP control unit with remote panel and accessories for each rig.

Accumulator: 4 nos. of 5 gal capacity bladder type accumulators BOP control unit shall be complete with electrical and air operated pressurizing system, with auto pressure switch for both, capable of pressurizing up to 3000 psi. BOP remote control panel with graphic visual display to be placed near to the driller console. All electrical items should be suitable for hazardous area, zone-1 gas group IIA & IIB. The electrical motor and starter/PBS for BOP control unit shall be suitable for use in hazardous area of zone-I and gas group IIA &IIB in oil mine and shall conform to IS/IEC/EN: 60079-0:2011 & IS/IEC/EN: 60079-1:2007. The bidders shall submit test reports conforming to the above relevant standards from an Indian Government Laboratory or NABL accredited laboratory or IECEx accredited laboratory or ATEX notified body, which is not a part of manufacturer's facility.

Note:

- 1.0 Portable pressure testing unit & Recorder for pressure testing & recording of high pressure lines, BOP should be available at site.
- 2.0 All wellhead equipment/ BOP/ BOP control unit should be pressure tested to its rated capacity and should be certified as per API recommended practice.
- 7.12 **Welding Machine** Two set (one set for each rig): Powered by Diesel Engine/Electric transformer with all associated welding and cutting accessories is to be made available at all times at well site against each rig.
- 7.13 **40 Ton Crane** 01(one) No. against each rig operation: Diesel Hydraulic, Truck mounted, and Telescoping Boom mobile crane of 40 Tonne minimum capacity is to be made available at all times at well site for each Rig operations.
- 7.14 **Close Circuit TV**: Bidder has to provide CCTV coverage for the following minimum specified area:
 - Well Head Area Focus
 - Well servicing Pump
 - Tankage Area

7.15 **SAFETY DEVICES**:

- (a) Fall Protection Device: An anti-fall coupled with safety harness/ belt shall be provided for personnel working on mast while exposed to a fall of 3 meters or greater or climbing unprotected vertical ladder with same exposure.
- (b) DGMS approved Top man's Escape Line & Device: For evacuation of Top Man from racking platform level in case of emergency.
- (c) Portable Gas Detectors: A portable DGMS approved gas detector capable of determining/ monitoring level of combustible gases in air should be made available at site.
- (d) All contractor's vehicles should be equipped with Spark arrestors.

Note: All safety equipment are to be in prime working condition.

7.16 General Statutory requirements for SAFETY NORMS:

- a. All the moving / rotating parts like belts, couplings, drive lines etc., of the equipment should be well guarded and painted with red colour.
- b. SRV of the pumps and air reservoir tanks should be tested regularly and records of such testing should be kept available all the times.
- c. Proper colour codes as per safety norms should be applied on the high pressure lines, gas lines and water lines.
- d. Anchoring and grouting of the delivery & bleed lines of the pumps should be done before running the pump.
 - **Note**: Any other item/ assembly not incorporated above and needed for meeting the scope of work in the tender should be provided by the contractor.
- 7.17 The following items are to be provided for two rig operations and in case the bidder is quoting for 01(One) Rig, the same has to be provided by the bidder
- a. TUBULAR/ CROSS OVER SUBS: (One lot against 2 Rigs): SLH-90 Drill Pipe: 73.83 mm (2.7/8") OD x 15.5 Kg/m (10.4 lbs/ft), Outside diameter of Tool Joint of drill pipe: 3.7/8", API Grade "E' or higher Grade = 5000 Mtrs
 - (i) One lot of necessary substitutes between drill pipe and drill collars, between drill collar and bit, required for drill string as well as for combination string

Handling Tools for above:

- (i) Elevators for 2.7/8" SLH-90 Drill pipe 2 Nos.
- (ii) Slips for 2.7/8" SLH-90 Drill pipe- 2 Nos

b. Light Truck -One No (for two rig operation): One truck with jugalis is to be provided for transportation of Bits/Mills and chemicals from Company's yard/Godown. Loading/ Unloading at well site is to be carried out by the contractor.

General Notes:

Contractor shall have to mobilize all the goods/services covered under item No. 7.14 above along with the rig package.

GENERAL NOTE: The offered Rig package including all Handling, Fishing and Milling tools & equipment, tubulars etc. shall have to be manufactured as per relevant API standards (wherever applicable) and also shall have to be completed with NDT inspection, report of which shall have to be submitted prior to mobilisation of the Rig package. In case of new items, the NDT inspection is not required.

7.18 OTHER SERVICES TO BE PROVIDED FOR EACH RIG OPERATION

A. WORKOVER FLUID & MUD ENGINEERING SERVICES

- i) OIL shall provide a mud/ workover fluid programme based on the depth data/casing policy as indicated in this document including their recommended dosage for mud/ workover fluid additives and optimum range of mud/ workover fluid parameters which need to be maintained by Contractor at the well site for achieving trouble free operations.
- ii) Scope of work: Preparation of salt solution using KCl, NaCl, Sodium Format, Potassium Format, CaCl2 of required density, bentonite mud & special workover fluid as per well programme and preparation Hi-Vis, Xan-Vis pill as per requirement.
- iii) Shift wise fluid report covering the following details as per OIL's format/ standard IADC Proforma- (a): Fluid density, MF viscosity, PH etc shall be prepared and submitted to the company representative.
- iv) The Contractor must ensure proper maintenance of mud parameters to avoid damage to producing formations. He should also ensure the availability of mud chemicals at well site by submitting his requirement to the company's representative well ahead of time.
- v) In case of any difference of opinion at any stage, with regard to mud policy, OIL's mud programme shall prevail and the Contractor must use OIL's mud policy at that point of time.
- vi) Contractor shall provide mud balance, MF viscometer, PH meter, PH paper, dip stick

B. WELL COMPLETION SERVICES

- i) Schedule -1: For / during well testing (Production Testing)
 - 1. Making & breaking including stacking and running in of production tubing (both 2.7/8" OD EUE N-80 and VAM tubing) as per the standard practice.
 - 2. Installation of Tubing Head Spool, packing of secondary seal and testing of the same as per the rating.

- 3. Testing of X-Mass tree and installation of the same.
- 4. Making necessary tubing/ casing connections to the well head set up.
- 5. Hooking up of the production equipment namely Tanks, Separator, Steam jacket, ground X-Mas tree etc. and test the same before commissioning as per the requirement.
- 6. To make the gas flare line to the flare pit.
- 7. To maintain the tubing tally including any down hole production equipment run.
- 8. All necessary surface connections to be made by the contractor for enlivening of the wells using nitrogen pumping unit.
- 9. Hooking up of the steam lines to production tanks and steam jacket.

ii) Schedule -2

- 1. All production equipment's namely X-Mass tree, Tubing head spool, Hanger flange / Tubing hanger, Separators with all accessories, Tanks, Steam jacket, Ground X-Mass tree, Tubing's (both EUE N-80 and VAM), Pipes for surface fittings and flare line etc. will be provided by OIL.
- 2. All tools required for making up of the above equipments are to be supplied by the contractor.
- 3. Consumables as thread dopes to be provided by the contractor.

C. TRANSPORTATION SERVICES

i) OIL's Responsibility

- 1) Transportation of company's personnel and materials/ Equipment (those not attached with the rig) will be company's responsibility.
- 2) Cement shall be supplied by OIL. To & fro collection, transportation, loading / unloading, stacking etc. of these cement shall be carried out by OIL, as and when required.
- 3) In case of well emergency, it is the responsibility of OIL to supply/ transport Chemicals, Cement etc. to well site.
- 4) Well consumables like casing, tubing, well head etc. shall be supplied by OIL. To & fro' collection, transportation including loading/unloading, stacking etc. at well site of these consumables will be provided by OIL.
- 5) Any additional requirement of crane(s) for any specific purpose at site during well operation shall also be provided by the OIL.

6) Readiness of approach road to forward location and plinth shall be the responsibility of OIL. Clearance of Electrical overhead lines belonging to state electricity board (APDCL), tea gardens etc. shall be the responsibility of OIL. However, contractor shall arrange for clearance of other overhead lines (like LT Service lines, leadings etc.) belonging to local people in consultation with OIL.

ii) Contractor's Responsibility

- 1) Transportation of contractor's personnel & their material from camp site to drill site and between drilling sites shall be the responsibility of the contractor. All vehicles deployed for this purpose should be in prime condition.
- 2) All requirements of crane(s), during rig up/rig down & inter-location movements are to be provided by the Contractor.
- 3) The contractor must provide at their cost, equipment & services of the following minimum number:
- a) Sufficient number of load carrying vehicles and cranes so that the interlocation movement is completed without any delay.
- b) Rig down / Rig up / transportation / maintenance of Company's materials / items like Well killing pump, Production installations (if any) attached to the rig shall be done by the contractor.
- c) One truck with jugalis is to be provided for transportation of Bits/Mills and chemicals required for preparation of mud and completion fluid, from Company's yard/Go-down. Loading/ Unloading at well site is to be done by the contractor.
- d) The contractor is solely responsible for any damage to existing Electrical infrastructure belonging to third parties viz. state electricity board (APDCL), tea gardens etc. resulting from the movement of the contractor's vehicle during ILM. In case of such damage, contractor is fully responsible for repairing of the damaged Electrical infrastructure.
- D. **ELECTRICITY**: Generation and supply of electrical power for running the entire operation and for various uses in the camp and well site shall be done by the contractor.

Statutory Provisions - Bidder to note that all relevant provisions of the following minimum acts/statutes/instructions by statutory authority shall apply:

- CEA (Measures relating to safety and Electricity supply) Regulations, 2010, and latest amendments thereto.
- Oil Mines Regulation, 2017, and latest amendments thereto.
- DGMS advisories / instructions
- OISD advisories / instructions

In case statutory authorities issue relevant instructions regarding operation of the Workover rig/s after the start of operations under this contract, the contractor shall implement such instructions at his own cost.

i) RIG LIGHTING

- 1) All lighting fixtures, plug & sockets, junction boxes etc. used in hazardous area shall be explosion proof or increased safety type and shall be suitable for use in hazardous area of zone-I and gas group IIA &IIB in oil mine and shall conform to IS/IEC/EN: 60079-0:2011 & IS/IEC/EN: 60079-1:2007. The bidders shall submit test reports conforming to the above relevant standards from an Indian Government Laboratory or NABL accredited laboratory or IECEx accredited laboratory or ATEX notified body, which is not a part of manufacturer's facility.
- 2) Lighting cable should be multi core flexible copper cables, 1100 volts grade (armoured or screened), Ethylene propylene rubber (EPR) insulated, CSP/NBR sheathed. All electrical cables shall conform to the provisions stipulated in line with IS-9968 read with the latest BHEL specifications (OR12003, OR12002 & OR12005) as the case may be.
- 3) Power supply to the lighting circuit shall be from phase-to-phase, 230volt, 50Hz (or 60 Hz). Separate lighting transformer of suitable capacity may be used for this purpose.
- 4) Red flasher type aviation warning lights should be mounted at the mast top. This light shall be operational at all times from the moment the mast is raised and until the mast is finally lowered irrespective of well operation.
- 5) Minimum illumination levels to be maintained are as follows-
 - # Sub-structure (derrick-floor) 80 lux
 - # Peripheral/area 10 lux
 - # Double board 30 lux
- ii) **RIG MOTORS**: All rig motors, starters, push button stations, junction boxes used in hazardous area shall be suitable for use in hazardous area of zone-I and gas group IIA &IIB in oil mine and shall conform to IS/IEC/EN: 60079-0:2011 & IS/IEC/EN: 60079-1:2007. The bidders shall submit test reports conforming to the above relevant standards from an Indian Government Laboratory or NABL accredited laboratory or IECEx accredited laboratory or ATEX notified body, which is not a part of manufacturer's facility.

Cable used for motor operation should be multi core flexible copper cables (armoured or screened) of 1100 volts grade, EPR insulated, CSP/NBR sheathed. All electrical cables shall conform to the provisions stipulated in line with IS-9968 read with the latest BHEL specifications (OR12003, OR12002 & OR12005) as the case may be.

iii) **EARTH LEAKAGE PROTECTION DEVICE**: All out going feeders for motor, lighting etc. shall be provided with earth leakage protection device so as to disconnect the supply instantly at the occurrence of earth fault or leakage current. [Ref: CEA (Measures relating to safety and electric supply) Regulations, 2010; regulation no.42]

iv) **GENERAL CONDITION**

- 1. All electrical equipment such as motors, light fittings, push button station, plug & sockets, junction boxes, motor starters etc. used in hazardous areas shall be suitable for use in hazardous area of zone-I and gas group IIA &IIB in oil mine and shall conform to IS/IEC/EN: 60079-0:2011 & IS/IEC/EN: 60079-1:2007. The bidders shall submit test reports conforming to the above relevant standards from an Indian Government Laboratory or NABL accredited laboratory or IECEx accredited laboratory or ATEX notified body, which is not a part of manufacturer's facility.
- 2. The bidder should furnish the following along with the offer:
 - i) Single line power flow diagram showing major equipment viz. Generators, CBs, Busbars, ELRs for feeders, NGR system, Motors, Lighting transformer, Starters etc.
 - ii) Plan layout of electrical equipment used in rig.
 - iii) List of all electrical equipment used in the W.O. rig with test reports conforming to IS/IEC/EN: 60079-0:2011 & IS/IEC/EN: 60079-1:2007 from an Indian Government Laboratory or NABL accredited laboratory or IECEx accredited laboratory or ATEX notified body, which is not a part of manufacturer's facility.

In case of such certificate is not available at the time of submitting the offer, the same shall be submitted prior to commencement of operation. The bidder shall categorically confirm the same in their offer.

- iv) Earthing scheme showing double and distinct earth connections for each equipment along with numbering of earth electrodes.
- 3. Electrical job precautions shall be adopted in the oil field as specified in the CEA (Measures relating to safety and electric supply) Regulations 2010, Oil Mine Regulation 2017, and DGMS guidelines; as amended from time to time.
- 4. The frame of every electrical equipment viz. generators, motors, transformers, PBS, starters, junction boxes, light fittings, switchboards, PCRs etc. as well as Diesel tanks, Mud tanks, vessels, Work over rig outfit, Bunk houses etc. shall be earthed by two separate and distinct connection with earth. [Ref: CEA (Measures relating to safety and electric supply) Regulations, 2010; regulation no.41]
- 5. Proper insulating mat conforming to IS-15652:2006 shall be provided in front of the electrical panels, switchboards etc. for the safety of operating personnel. [Ref: CEA (Measures relating to safety and electric supply) Regulations, 2010; regulation no.19]
- 6. Following tools shall be maintained for electrical jobs -
 - (i) FLP torch
 - (ii) Intrinsically safe Insulation Tester
 - (iii) Multimeter
 - (iv) Earth Tester

- (v) Safety belt
- (vi) Rubber insulated gloves for electrical purpose
- (vii) Discharge sticks & lamp tester
- (viii) Electrician's Tool Kit
- (ix) Lux meter
- 7. Neutral Grounding Resistor (NGR) system: Contractor shall have to provide Neutral Grounding Resistor (NGR) in the incoming power supply. The neutral system should be such that, the earth-fault current shall not be more than 750mA in installations of voltage exceeding 250V and upto 1100V for oil fields. The magnitude of the earth fault current shall be limited to the above value by employing suitably designed restricted neutral system of power supply, provided with fail-safe NGR monitoring systems so as to sense the failure of NGR or open-circuit in neutral circuit.
- 8. Lockout and Tagout system shall be provided for electrical panels.
- 9. Danger boards/ Danger notices (with skull & bones, designed as per IS:2551) shall be affixed permanently on every motor, generator, transformer, switchboard, starter, junction box etc. [Ref: CEA (Measures relating to safety and electric supply) Regulations,2010; regulation no.18]
- 10. Following items shall be affixed / displayed in a conspicuous place
 - i) Electrical single line power flow diagram
 - ii) Electrical earthing system schematic
 - iii) Plan layout of electrical equipment
 - iv) Electric shock treatment chart
 - v) One commissioning and statutory record register should be maintained by contractor to record the following
 - a) i) Specifications/nameplate details including IS/IEC/EN: 60079-1:2007 as per OMR-2017 and subsequent DGMS guidelines for each electrical equipment.
 - ii) Insulation resistance of all motors, generators, cables, distribution board, transformer etc. (in each rig up and monthly.
 - b) Register for recording earth resistance of all electrodes. (in each rig up and monthly).
 - c) Register for Test record of ELRs (monthly).
 - d) Schedule -XIII [of CEA (Measures relating to safety and electric supply) Regulations,2010]
 - e) Electrical isolation/ energization permit.
 - f) Register for flange gap measurement records of FLP equipment (yearly).
 - g) File containing details of Electrical workman permit and Electrical supervisor certificate of competency of electrical personnel
 - h) Electrical log sheet to maintain records of operational parameters and energy consumption data. (every shift)
 - i) Illumination survey records.

E. **CEMENTING SERVICES**

- i) OIL shall perform the cementation jobs such as Squeeze cementation, Cement plug job etc. as per the requirement of well completion policy at the wells planned for work over jobs. The Contractor shall provide the following equipment and services to enable OIL to carry out the jobs successfully. Contractor's pump shall be used to pump cement slurry. Expected parameters are 2500 psi, (max.)
- ii) The Contractor shall be required to assist OIL in performing all secondary cementation jobs at all the wells.
- iii) OIL may at any time decide to utilise a cementing unit for carrying out the cementation job. Further the Contractor will carry out cleaning / flushing of cementing unit and associated surface lines after completion of the cementing jobs.
- iv) During cementation readiness: The Contractor shall, during the cementing job, attend to all problems, render help and rectify all defects to the satisfaction of OIL's cementing Engineer. These shall include equipment and accessories supplied by OIL also.
- v) Post Cementation follow up action: The Contractor shall carry out cleaning and flushing to remove all traces of cement from unwanted locations. They shall also disassemble and remove/ load all OIL's equipment, which are required to be removed after the mandatory period.

F. **FIRE FIGHTING AND SAFETY EQUIPMENT/SERVICES**:

(As per API wherever applicable)

- i) Safety: Contractor shall observe such safety regulations in accordance with acceptable oilfield practice and applicable Indian Laws. Contractor shall take all measures reasonably necessary to provide safe working conditions and shall exercise due care and caution in preventing fire, explosion and blow out and maintain fire and well control equipment in sound condition at all times. Contractor shall conduct such safety drills, BOP tests, etc. as may be required by company at prescribed intervals.
- ii) Contractor shall provide all necessary fire fighting and safety equipment as per laid down practice as specified under OISD STD 189 and OMR.

FIRE FIGHTING EQUIPMENTS:

Fire fighting arrangements should as per OISD-189.

- 1. Fire Water Flow Rate: 1750 LPM
- 2. Fire Water storage: 1750 LPM X 30 Min = 52500 Ltrs. (Minimum 52.5 KL)
- 3. Fire Water Line of minimum 4" size shall be located at a minimum distance of 15 m from the wellhead area.
- 4. Trailer / skid mounted (with Fire water Tank) Fire Pump = Min 1800 LPM @ 7 Kgf/cm2
- 5. Single headed hydrants 01 Nos.
- 6. Water-cum-foam Monitor 01 No. of 1750 LPM Cap.
- 7. Hose box 01 Nos.
- 8. Fire hoses 04 Nos.

- 9. Multipurpose nozzle- 03 No.
- 10. Inline foam eductor- 1 Nos.
- 11. Foam branch pipe 1 Nos.
- 12. Foam compound minimum 200 lts.
- 13. Weather-proof facility for storing above items.
- 14. Fire Extinguisher
 - a) 25 Kg trolley mounted DCP Fire Extinguisher 02 Nos.
 - b) 10 Kg DCP extinguishers 19 Nos.
 - c) 6.5 Kg CO2 extinguisher 08 Nos.
 - d) Sand drum with Scoop 05 Nos.
 - e) Fire Extinguisher Shed 01 No.
- 15. Fire bell/alarm

[Contractor shall provide necessary hose, TCP with fittings]

First Aid Kit: An adequate and approved first aid kit should be provided on each rig and should have all medicines as recommended as per Mines Rule 1955, Rule 43(3), Second Schedule.

- iii) Fire protection at well sites shall be the responsibility of the Contractor. Necessary action shall be taken and prior arrangements to be made for providing competent person s trained in the field.
- iv) Documentation, record keeping of all safety practices should be conducted as per international/Indian applicable laws, act, regulations etc, as per standard Oilfield practice and these records should be made available for inspection at any point of time. The H.S.E (Hygiene Safety and Environment) policy as well as emergency procedure manual should be kept at site. Compliance of these shall be the sole responsibility of the contractor.
- v) Contractor shall have to mobilise 1(one) brand new factory build ambulance with dedicated driver for deployment at well site against each Rig round the clock to meet any emergency situation with all mandatory accessories like stretchers, oxygen cylinders, first aid facilities, etc. The Ambulance facility should comply OMR-2017 requirement.

G. CIVIL WORK INVOLVEMENT

i) OIL's Responsibility:

- 1. Company shall provide foundation for the standard rig equipment including hard standing and cement concreting areas, effluent pit provision etc.
- 2. Digging of pilot pit & strengthening of effluent pit
- 3. Maintenance of approach road during operation.
- 4. Supply of only cement & other civil materials (for grouting jobs).
- 5. Maintenance of plinth including preparation of proper drainage System as per OIL's standard to evacuate rain water and mud sludge etc. to effluent pit.

Regular jobs at plinth i.e. cutting of small drains/nallah leading to pit, levelling of plinth with Company's civil materials, shall be done by Company.

- 6. To provide toilets, both for Contractor's personnel and Company's personnel including supply of all the required materials and subsequent dismantling after completion of the well.
- 7. Sand bagging of adjacent wells. Company shall provide the appropriate barrier of sand bags to the adjacent live wells, located in the same plinth.
- 8. Enclosure to stop spillage of LWC, HSD etc. in the respective tanks.
- 9. The digging of deep tube wells at the well sites and installation
- 10. All grouting required for anchoring guy post & delivery lines including cement and other civil materials.
- 11. The External guy posts should be anchored with RCC, as per OIL design.
- 12. Erecting of contractor's Panel fencing in well site with all materials.
- 13. Construction of all types of sheds required during operation i.e. Telephone shed, sheds over mud tank and chemical storage etc, including supply of all the required materials and subsequent dismantling after completion of the well.

ii) Contractor's Responsibility

Supplying all equipments / materials for sinking of the tube well is contractor's responsibility. For the sake of the Contractor's knowledge, the depth of deep tube well in the region will be approximately 15-50 m (with double filter installed). The operation of the water pumps, extraction of water from deep tube well for the rig as well as camp shall be Contractor's responsibility. Supply of water from alternate sources shall be the responsibility of the Contractor, if no water is found at the exact camp or well site.

Supplying of panel fencing at well site as per OIL's standard drawing no OIL/0825/E.

NOTE TO BIDDERS:

- i) Bidders to provide Rig Lay out Drawing for the Rig Package along with the bid.
- ii) Any additional civil work involvement besides the standard indicated plinth area / civil work should be highlighted by the contractor in their technical bid.

H. **SECURITY SERVICES**:

Contractor shall be wholly responsible for complete Security of their personnel, their Rig packages, Base Camp and during ILM, operation, transit etc. and arrange suitable & comprehensive Security services accordingly on round the clock basis for their personnel and equipment/ material throughout the tenure of the contract. All security related issues shall be dealt by the Contractor on their own including dealing with Government agencies. The Contractor shall provide pre-fabricated XPM/panel re-usable type fencing, gate in the drill site, camp site etc. Company

in no case will be involved in security related issues, relating to Contractor's personnel and equipment/material. Contractor shall also be responsible for the safety and security of Company's personnel, equipment/ material etc. in the well site and camp site.

I. MEDICAL SERVICES:

Suitable first aid medical services shall be provided by the Contractor round the clock on call 24 hrs a day. The contractor shall make available at all times during the entire Contractual period sufficient quantity of first aid equipment and medicines to meet any emergency.

J. **CAMP AND OTHER ESTABLISHMENT**: Suitable camp facilities for Contractor's personnel including catering services shall be provided by the contractor.

K. **COMMUNICATION SYSTEM**:

Suitable communication system is to be provided by the contractor and same to used only in the safe zones. However, OIL will have option to provide the OIL telephone in some locations, if found suitable.

L. PERSONNEL TO BE DEPLOYED

i) The Contractor will have to deploy adequate manpower to carry out the required operations. The deployment pattern will be as per the contractor's discretion for all the required services except for the rig operations during Work over & completion phases for which the deployment pattern has to be as per the following norm, for per rig operation, with the indicated key personnel:

S1. No.	Key Personnel	Classification	Number per location per shift	Working Hours
1	Rig manager/Rig Superintendent	N.A	1	On call 24 Hrs(On/Off Duty
2	Tool Pusher	N.A	1	Pattern) 12 Hrs
3	Tour Pusher/Night Tool Pusher	N.A	1	12 Hrs
4	Driller	N.A	1	12 Hrs
5	Asstt. Driller	Highly Skilled	1	12 Hrs
6	Top man	Skilled	1	12 Hrs
7	Floorman/ Rig Man	Semi-skilled	4	12 Hrs
8	Master Mechanic	Highly Skilled	1	12 Hrs
9	Rig Electrician	Skilled	1	12 Hrs
10	Mud Supervisor	Highly Skilled	1	12 Hrs
11	HSE Officer	N.A	1	12Hrs (During General shift and as and when required)
12	Welder	Skilled	1	12 Hrs (During General shift and as and when required)

13	Heavy Crane Pipe	Highly Skilled	1	12 Hrs (During
	Layer Operator			General shift and
				as and when
				required)
14	Electrical	Highly Skilled	1	12 Hrs (During
	Supervisor			General shift and
				as and when
				required)

NOTE:

- i) One Rig Manager/Rig Superintendent for two rig operations. Rig Manager will avail due off after completion of 14/21 days. So, 2 (two) Rig Managers shall be appointed by the Contractor for On/Off Duty.
- ii) The Rig Manager / Rig Superintendent has to be present at station all the times and should report to Drilling Deptt's office as and when asked for to receive instruction/resolving any issue on contractual obligation.
- iii) KEY PERSONNEL: The qualification and experience of the key personnel are to be as under:
- 1) **RIG MANAGER**: Should be engineering degree/diploma holder /Science Graduate of sound health and have work experience of minimum 1 year as rig manager and three years experience as tool pusher. The candidate having five years experience in work over/ Drilling operations in deep oil / gas wells as tool pusher may be considered for Rig Manager at the discretion of OIL. Should be conversant with well control methods to take independent decisions in case of well emergencies.
- 2) **TOOL PUSHER/ TOUR PUSHER**: Should be of sound health and have work experience in Drilling work over operations as listed in this tender in deep oil/gas wells. The minimum qualification should be HS/PU/I. Sc (10+2) and should be capable of writing and speaking English having minimum 1 year experience as tool pusher and three years' experience as driller. The candidate having five years experience in work over/ Drilling operations in deep oil / gas wells as driller may be considered for tool pusher at the discretion of OIL.
- i) Must possess valid well control certificate (IWCF) / IADC well cap; and should be conversant with well control methods to take independent decisions in case of well emergencies.
- ii) Should be conversant about mud chemicals & maintenance of mud property.
- 3) **DRILLER**: Preferably should be of sound health and have sufficient work experience as driller in drilling or work over oil/gas wells. The minimum qualification should be HS/PU/I. Sc (10+2) and should be capable of writing and speaking English. He must have 1 year experience as driller and three years experience as Assistant driller. The candidate having five years experience in work over/ drilling operations in deep oil / gas wells as Assistant driller may be considered for driller at the discretion of OIL.
 - Must possess valid well control certificate (IWCF) / IADC well cap; and should be conversant with well control methods to take independent decisions in case of well emergencies.

- Should be conversant about mud chemicals & maintenance of mud property.
- ** NOTE: Company reserves the right to accept suitable candidates of not having required qualification.
- 4) **HSE Officer**: Qualification: Should be graduate/ Diploma in safety / fire Engineering after completion of HS/PU/I. Sc (10+2).

Job Description:

Duties & responsibilities include safety during drilling site preparation, rig up, rig down & rig move, raising & lowering mast, rig floor operations like making & lowering BHA, cementing job, tripping in /tripping out tubular, safety meeting during crew change, pre job safety meetings, routine inspections & workover rig inspections, preparation of job specific SOP in local language, ERP (Emergency Response Plan), Risk Register, preparation of Job Safety Analysis, Permit to Work systems, investigation & analysis of accidents, incidents & near miss. To follow all DGMS, OISD & MoEF guidelines and submit return at specified intervals.

- a) Responsible for designating 'Safe Briefing Area' and advising all personnel of the 'current' safe briefing area.
- b) Responsible for issuing safety equipment to all personnel arriving at rig and ascertain that all personnel use and maintain these equipment properly.
- c) Responsible for designating location entrance and exit.

Experience: Experience as HSE officer of about 1 year. Health, Safety & Environment experience includes formation and implementation of HSE policies, Work Site Inspection & hazard Identification, Training of employees, Task risk Assessments, Permit To Work systems, pre job safety meeting, Accident, incident and Near Miss Investigation & analysis, Report making & Record Keeping, Selection of PPEs suitable for work activity & work environment, Work site Inspections & Audits, and Emergency Response Planning & Loss Control programs, taking precaution for pollution control and environmental management. Should have knowledge on ISO, ISRS certifications etc.

- 5) **ASSISTANT DRILLER**: Must be a Diploma in Engg/Science graduate with minimum 2 years' experience including 1 year as Assistant Driller in Drilling/Workover Rig OR minimum 10+2 pass with minimum 3 years' experience including 1 year as Assistant Driller in Drilling/Workover Rig.
- Must possess valid well control certificate (IWCF) / IADC well cap; and should be conversant with well control methods to take independent decisions in case of well emergencies.
- 6) **TOPMAN (TM):** Minimum qualification- Read up to 10+2 /ITI with minimum 4 years' experience including 2 years as TM, OR Read up to Class-X with minimum 6 years' experience including 2 years as TM, OR Read up to Class-VIII with minimum 8 years' experience as Floor Man including 2 years as TM.

- 7) **FLOORMAN (FM)/RIGMAN (RM)**: Minimum qualification Read up to Class-X with minimum 2 years Oil Field experience with 1 year as FM OR Read up to Class-VIII with minimum 3 years Oil Field experience with 1 year as FM.
- 8) **Roustabout**: Minimum qualification Read up to Class-VIII with minimum 1 year Oil Field experience.
- 9) MASTER MECHANIC: Must be a Diploma in Mechanical. /Automobile Engg. with minimum two years related experience including 1 year as Assistant Mechanic OR ITI in Diesel Mechanic/Fitter/Motor Mechanic with minimum 3 years related experience including 1 years as Assistant Mechanic OR HSLC/HS or equivalent with minimum 5 years related experience including 1 years as Assistant Mechanic.

He should have the knowledge of preventive/ breakdown maintenance procedure of the equipment. He should be able to detect the breakdown of outfit engines, pump and other engines at well site and rectify the problems.

- 10) **RIG ELECTRICIAN**: The minimum qualification and experience of rig electrician should be as under:
 - i) Shall have Diploma in Electrical Engineering from a recognized institute or university, OR shall possess a certificate in Electrical Trade, preferably with 2 yrs. course from an Industrial Training Institute recognized by the Central Govt. or State Govt.
 - ii) Shall have minimum 3 years. (for Diploma) or 6 yrs (for ITI) of experience in the operation and maintenance of electrical equipment in workover/drilling rigs. He should be able to read circuits, communicate, detect and rectify faults.
 - iii) Shall possess valid Electrical Work Permit (with Parts I & II) issued by State Licensing Board. [Ref: CEA (Measures relating to safety and electric supply) Regulations, 2010; regulation no.3, 6 & 115 and Oil Mines Regulations, 2017; regulation no.114].
- 11) **<u>Electrical Supervisor</u>**: The minimum qualification and experience of electrical supervisor should be as under:
 - (i) Shall have Degree or Diploma in Electrical Engineering from a recognized institute or university.
 - (ii) Shall have minimum 3 yrs. (for Degree) or 5 yrs (for Diploma) of experience in workover/drilling rigs. He should be confident in independently carrying out the fault finding analysis, rectification of fault, operation and maintenance of all the electrical items of workover rig.
 - (iii) Must possess valid Electrical Supervisor's Certificate of Competency (with Parts 1, 2, 3, 4 & 8) issued by State Licensing Board.

[Ref: CEA (Measures relating to safety and electric supply) Regulations, 2010; regulation no.3,6&115 and Oil Mines Regulations,2017; regulation no.114]

NOTE: Prior approval from CE (Electrical) should be obtained for employment of electrician. Complete bio-data should be forwarded to CE (Electrical) for scrutiny and approval.

- 12) **MUD SUPERVISOR**: The minimum qualification and experience of mud supervisor should be as under:
 - HS/PU/I. Sc in science or equivalent.
 - Should have knowledge in Drilling /Workover wells, experience of at least 4 years in handling drilling/ workover fluids out of which atleast one year as mud attendant.

Candidates having B.Sc. qualification with Chemistry as one of the subjects, should have min 2 (two) years' experience in handling drilling / workover fluid system out of which at least one year as mud attendant.

- 13) **WELDER**: Should be provided along with the welding machine. The welder should have minimum 2 years related experience in working in drilling/ work-over wells and must be conversant of welding of casing and well head accessories. He must possess the certificate of welding trade from any recognized institute of State Govt. (One year course).
- 14) **HEAVY CRANE / PIPE LAYER OPERATOR**: Should be provided along with the Crane. The crane operator should have a minimum of 2 years work experience in operating a heavy crane/pipe layer and possess license for driving heavy motor vehicle.
- 15) On top of the experience of the personnel as listed above, they all should be conversant with BOP drill as per standard oilfield practice.

NOTES:

- 1) An undertaking from all the personnel as per Proforma (Annexure-V) should be forwarded after deployment of manpower prior to mobilization.
- 2) The personnel deployed by the contractor should comply with all the safety norms applicable during operation.

3) Medical Fitness:

- The Contractor shall unsure that all of the Contractor Personnel shall have had a full medical examination prior to commencement of the Drilling operation.
- A qualified and registered doctor shall conduct all such medical examinations in accordance with accepted medical standards.

4) Training Courses:

- The Contractor shall ensure that all of the Contractor Personnel performing services hereunder shall have attended all safety and operational training courses such as mines vocational training etc. required by applicable law and as is generally consistent with international petroleum industry practice and/or as otherwise required by the Company. The Contractor shall, if requested, forthwith produce valid and current
- The Contractor shall, if requested, forthwith produce valid and current certificates of completion or attendance for the Company's inspection.

- 5) Personnel should be well verged in fire fighting, BOP control, gas testing etc. The appropriate certificates to this effect, issued by ONGCL/OIL or any other organization, also should be submitted prior to mobilization.
 - (In case, the above training course for contractor's personnel is to be arranged by OIL, the contractor will be charged accordingly).
- 6) Rig Manager shall be stationed at base office. In case of operational requirement he shall visit well sites and can leave station only on specific permission of OIL.
- 7) Contractor should deploy other personnel at rig site, which shall include drivers, Rig fitters, carpenters warehouse personnel, security men, (both at well site and camp site), power tong operator, services of unskilled labour as and when required for following multiple jobs:
 - Chemical Helper
 - Engineering helper (Additional)
 - Electrical helper
 - Persons on rack during casing job.
- 8) On/off duty details of rig and associated service personnel should be indicated.
- 9) Employment of personnel other than key persons shall be at the discretion of the contractor to run all operations at well site and camp successfully.
- 10) The Contractor shall forward the list of personnel deployed in each Rig along with bio-data / qualification/ experience / track record of the personnel prior to mobilization of the Rigs with all supporting documents. Any additional manpower deployed by the contractor shall be at the expense of the Contractor.
- 11) The age of the key personnel except Rig Manager/Rig superintend should not be more than 50(fifty) years (supporting document to this effect should be submitted). However, OIL deserves the right to accept the personnel of above 50 years with good health conditions.
- 12) The contractor shall be responsible for arranging relief of personnel during vacation, statutory off days, sickness etc. entirely at their cost. However, the relief personnel also must have the qualification and experience as indicated above. Contractor shall submit the bio-data/ qualification/ experience/ track record of the relief personnel along with recent photographs for OIL's scrutiny. Contractor will have to obtain prior approval from Company for the relief personnel of the contractor.
- 13) Company reserves the right to instruct for removal of any Contractor's personnel who in the opinion of Company is technically not competent or not rendering the services faithfully, or due to other reasons. The replacement of such personnel will also be fully at cost of the Contractor and the Contractor shall have to replace this/these personnel within Ten (10) days of such instruction. The replacement personnel must have the requisite qualification and experience as indicated in the contract and their credentials along with

recent photographs must be submitted to Company for approval prior to their engagement.

14) All charges for personnel are included in Day rates. No. separate charges shall be payable for the personnel deployed.

NOTE: In case the bidder is quoting for 01(One) Rig as per the Tender, all equipment/ tools / Crane/ Welding Machine / Trucks or any other items not specified as required for under 02(Two) Rig operation has to be provided by the bidder.

END OF SECTION-II

Part-3 SECTION-III SPECIAL CONDITIONS OF CONTRACT (SCC)

The following Special Conditions of Contract (SCC) shall supplement and / or amend the General Conditions of Contract (GCC). Whenever there is a conflict, the provisions herein shall prevail over those in the GCC.

1.0 DEFINITIONS

Following terms and expression shall have the meaning hereby assigned to them unless the context otherwise requires:

- a. "'Work over Unit" means work over rig complete with pumps, power packs, and other accessories and equipment as listed in the Contract to perform the service.
- b. "Associated services" means equipment and services, means equipment and services, asked for, along with work over unit in this bid document. These include but not limited equipment & services; camp/catering/ medical services, communication, safety & firefighting services, well control services etc.
- c. "Operating Area" means those areas in onshore India in which company or its affiliated company may from time to time be entitled to conduct drilling operations.
- d. "Operation Base" means the place or places, onshore, designated as such by company from time to time.
- e. "Site" means the land and other places, on/under/in or through which the works are to be executed by the Contractor and any other land and places provided by the company for working space or any other purpose as designated hereinafter as forming part of the Site.
- f. "Company's items" means the equipment, materials and services, which are to be provided by company at the expense of company and listed in the Contract.
- g. "Company Representative" means Installation Manager of the Rig / DGM-Workover Operations where ever defined in this document.
- h. "Contractor's items" means the equipment; materials and services, which are to be provided by Contractor or company at the expense of the Contractor which, are listed in section under terms of reference and technical specifications.
- i. "Contractor's personnel" means the personnel as mentioned under section terms of reference and technical specification, to be provided by Contractor from time to time to conduct operations hereunder.
- j. "Commencement Date" means the date on which the contractor commences the work over operation at the first well under this contract.

- k. "Facility" means and includes all property of Company owned or hired, to be made available for services under this Contract and as described in this agreement which is or will be a part of the Company.
- 1. "Certificate of Completion" means certificate issued by the Company to the Contractor stating that he has successfully completed the jobs/works assigned to him and submitted all necessary reports as required by the Company.
- m. "Inter-location movement" means transferring of complete Workover Unit from present well after demobilisation notice is issued by the Company till the start of Workover unit operation at next location.
- n. "Workover Operation": Means all operations as generally understood for workover operations in Oil/Gas wells, more particularly all the operations required to be carried out pursuant to this contract.

2.0 MOBILIZATION:

- 2.1 The mobilization of the Work over Unit and associated services shall commence on the date of receipt of the 'letter of Award' awarding the Contract and continue until the complete Work over unit is properly positioned at the first location, rigup of rig is completed and the Unit is ready for operation
- 2.2 The mobilization of Workover Unit, equipment, personnel etc. of should be completed by Contractor within 60 days from the 'letter of Award' awarding the Contract. Mobilization of Workover Unit shall be deemed to be completed when Contractor's unit complete with all equipment and manpower are placed at the nominated location in readiness to commence operations as envisaged under the Contract duly certified by the Company's authorized representative.
- 2.3 Company at its discretion may allow to commence the operation without complete mobilization, however necessary deduction for short supplied items will be made as per cost evaluated by OIL.
 - (i) For any items supplied by the company rental will be calculated after amortizing the cost of the item over a period of 5 years applying 15% PTRR (Post tax rate of return). Similar deductions will also be made for short supplied items (neither supplied by company nor by the contractor).
 - (ii) Deduction will be calculated based on company's determined cost, which shall be treated as final, basis of which shall provide to the contractor.
 - (iii) Notwithstanding this provision for partial mobilization bidder must quote in accordance with relevant clauses for full mobilization.
- 2.4 **Final de-mobilization**: Workover Unit and Personnel as per the scope of work as indicated by OIL shall have to be de-mobilized by the Contractor within 60(Sixty) days from the date of issuance of final de-mobilization letter. However, no charges will be payable from the date of issue of the final de-mobilization notice.

2.5 Mobilization charges will be payable after the commencement date as certified by the company.

Note: The succeeding day of issue of mobilization/demobilization notice shall be counted as day 1 for the purpose of Mobilization/Demobilization period.

3.0 **DURATION OF CONTRACT**: The contract shall be initially for a period of 03 (three) years from the commencement date of the Workover unit(s) with an option to extend the contract period for another 1(one) year at the discretion of Company at the mutually agreed rates, terms and condition, but with a rate not higher than the originally quoted rate. The rates, terms and conditions shall continue until the completion or abandonment of the last well until the completion of testing operation at the time of the end of the Contract.

4.0 PLACE OF ARBITRATION:

The place for arbitration against this contract shall be Guwahati, Assam.

5.0 WARRANTY AND REMEDY OF DEFECTS:

The defect liability period against this contract shall be 3 (three) months after final demobilization notice against each workover unit.

6.0 SUB-CONTRACTING: Sub-contracting shall not be allowed under this contract.

7.0 CONTRACTOR'S PERSONNEL:

- 7.1 Except as otherwise hereinafter provided, the selection, replacement, and Contractor shall determine remuneration of contractor's personnel. Such employees shall be employees solely of Contractor. Contractor shall ensure that its personnel will be competent and efficient. However, the contractor shall provide details of experience, qualification and other relevant data of the personnel to be deployed for scrutiny and clearance by the company before the actual deployment. The contractor shall not deploy its personnel unless cleared by the company.
- 7.2 The Contractor shall appoint a Project Manager/ Co-Coordinator as the Contractor's representative who shall be in charge of Contractor's personnel /equipment and who shall have full authority to resolve all day to day matters, which arise at the site.
- 7.3 **Contractor's Personnel:** Contractor shall provide all manpower for necessary supervision and execution of all work under this contract to company's satisfaction except where otherwise stated. The minimum number of key personnel to be deployed is mentioned in this document.
- 7.4 **Replacement of Contractor's Personnel:** Contractor will immediately remove and replace any Contractor's personnel, who in the opinion of company, is incompetent, or negligent or of unacceptable behaviour or whose employment is otherwise considered by company to be undesirable.
- 7.5 Contractor shall deploy on regular basis, all category of their employee required for efficient operations.

- 7.6 In case Contractors deploying foreign nationals required for execution of all work under the Service are required to have all necessary clearances as per the Govt. of India regulations.
- 7.7 Foreign Nationals in case deployed under the service should have proper work Visa as per the Govt. of India regulations.
- 7.8 Transportation of Contractor's personnel shall be the responsibility of Contractor.
- 7.9 Medical Facilities: OIL may provide services of OIL Hospital to Contractor's personnel on payment basis subject to availability.
- 7.10 Contractor shall provide standard food & services for all its own & its subcontractor's personnel.

8.0 CONTRACTOR'S ITEMS:

- 8.1 Contractor shall provide contractor's items and personnel to perform the services under the contract as specified in this document.
- 8.2 Contractor shall be responsible for maintaining at his cost adequate stock levels of contractor's items including spares and replenishing them as necessary.
- 8.3 Contractor shall be responsible for the maintenance and repair of all contractors' items and will provide all spare parts, materials, consumables etc. during the entire period of the contractual period.
- 8.4 Contractor will provide full water requirement at rig site and campsite.
- 8.5 Contractor will provide all POL for operation of contractor's equipment both at well-site and campsite at contractor's cost. There shall be no escalation in the day rates throughout the duration of the contract including extension, if any, on account of any price increase in fuel / lubricants.
- 8.6 Contractor will provide electricity at both well-site and campsite for meeting both contractors' as well as company's requirement.
- 8.7 Zero day rates will be applicable for shutdown of rig operations on account of inadequate supply of contractor's items, including but not limited to, electricity, lubricants, water, and personnel.

9.0 CONDUCTING WORK OVER OPERATIONS

- 9.1 The Contractor shall carry out all operations mentioned hereunder with due diligence in a safe and workmanlike manner and in accordance with accepted international oilfield practices.
- Wells shall be completed as specified in the work over programme within the depth range of the rig.
- 9.3 The work over Unit and all other equipment and materials to be provided by Contractor shall be in first class working condition.

- 9.4 The work over/ Well testing programme provided by company shall primarily include planning of the following:
 - a) Well testing programme.
 - b) Well history with perforation details, BHP etc.
 - c) Details of casing string.
 - d) Mud hydraulic programme.
 - e) Cement repair programme (if any).
 - f) Wire line logging programme.
 - g) Drill out plug and packers (if any).
 - h) Casing repair job.
 - i) Gas and water injection programme.
 - i) Wire line operation including perforation.
- 9.5 Completion of work over shall occur when the well has been killed with Brine/Mud, carried out all the operations as per well completion policy and initial production testing carried out unless otherwise advised by Company.
- 9.6 Upon completion of a work over well, statement stating that the well has been completed in accordance with the terms of this Contract and signed by the representatives of both Contractor and Company, will be made available to Company.
- 9.7 Operation of Work over Unit: Contractor shall be solely responsible for the operation of the Work over Unit including but not limited to supervising rig move operations and positioning and rigging up at designated location as required by Company as well as such operations as may be necessary or desirable for the safety of the Work over Unit.
- 9.8 Safety: Contractor shall observe such safety regulations in accordance with acceptable oilfield practice and applicable Indian Laws such as Mines safety rules etc. Contractor shall take all measures reasonably necessary to provide safe working conditions and shall exercise due care & caution in preventing fire, explosion and blow out, and maintain fire-fighting and well control equipment in sound condition at all times. Contractor shall conduct such safety drills, BOP tests etc. as may be required by company at prescribed intervals.

In case Contractor is found non-compliant of HSE laws as required by Company will have the right for directing the contractor to take action to comply with the requirements, and for further non-compliance, the contractor will be penalized. The contractor shall be penalized @5% of the operating day rate for the period of non-compliance.

- 9.9 Contractor shall assist in performing any tests to determine the productivity of any Formation encountered as may be directed by company. Such tests and services may include, but not limited to electric logging, drill stem tests, perforation of casing, acidizing, swabbing, fracturing and acid fracturing.
- 9.10 Depth Measurement: Contractor shall at all times be responsible for keeping accurate record of the depth while lowering any string in the hole and record such depth on tally books. OIL shall have the right at any time to check measurements of the string in any manner.

- 9.11 The Contractor will maintain the well fluids in a manner satisfactory to the company. The parameter of the well fluid shall be maintained by the contractor in accordance with specifications and/or formulations set forth by the company.
- 9.12 In the event of any fire or blowout, contractor shall use all reasonable means at his disposal to protect the hole and bring the said fire or blowout under Control.
- 9.13 Adverse Weather: Contractor, in consultation with company, shall decide when, in the face of impending adverse weather conditions, to institute precautionary measures in order to safeguard the well, the well equipment, the Work over Unit and personnel to the fullest possible extent. Contractor and company shall each ensure that their representatives for the time being at well site, will not act unreasonably in the exercise of this clause.
- **AMENDMENTS OF COMPLETION PROGRAMME**: It is agreed that contractor shall carry out work over operations, testing, completions, abandonment, if any, and all other operations, in accordance with the well completion programme to be furnished by OIL, which may be amended from time to time by reasonable modification as OIL deems fit, in accordance with good oil field practices.
- **WELL POLICY**: The well completion programme may vary depending on the actual requirement at and during the time of commencement of the operation. The contractor shall be bound to obey those changes made by OIL from time to time.

12.0 CONTRACTOR'S SPECIAL OBLIGATIONS

- 12.1 It is expressly understood that contractor is an independent contractor and that neither it nor its employees and its subcontractors are employees or agents of company provided, however, company is authorised to designate its representative, who shall at all times have access to the Work-over Unit, related equipment and materials and all records, for the purposes of observing, inspecting and designating the work to be performed hereunder by contractor. The contractor may treat company's representative at well site as being in charge of all company's and company designated personnel at well site. The company's representative may, amongst other duties, observe, test, check and control implementation of work over, testing programmes, equipment and stock, inspect works performed by contractor or examine records kept at well site by contractor.
- 12.2 Compliance with company's Instructions: Contractor shall comply with all instructions of company consistent with the provision of this Contract, including but not limited to completion programme, well control, safety instructions, confidential nature of information, etc. Such instructions shall, if contractor request, be confirmed in writing by company's representative.
- WELL RECORDS: Contractor shall keep the history of each well on the daily work over report prescribed by the Company and upon completion or abandonment of the well, deliver to Company, the original history and log book (if any), properly signed and all other data and records of every nature, relating to the completion of the well

- a) Contractor shall also provide the following report every day at 7 am positively at the office of the Head Drilling (Work over & Services)
 - i) Daily work over report on IADC proforma duly certified by Company's representative along with daily record-o-graph or drillometer chart.
 - ii) Daily mud report on IADC proforma including mud stock, daily consumption and stock position of chemicals.

However the following records should be maintained at well sites

- i) Gas testing records.
- ii) Conditions of mud mixing facilities like guns, agitators etc.
- iii) Daily report on P.O.L. consumption.
- iv) Daily roster of Contractor's personnel.
- b) Contractor shall also provide the following list /reports to Company
 - i) Contractor shall maintain inventory of rig equipment & accessories at site indicating their respective models, serial Nos., vintage, specifications etc. The Contractor shall provide inventory list endorsed by Company representative and any addition & deletion of items will be intimated by Contractor to Company representative.
 - ii) All items including consumables imported under 'Nil' customs duty utilizing the Essentiality Certificates (EC) shall be recorded in the proper format indicating date of receipt, type, consumption, date of replacement etc.
 - iii) Contractor shall provide the list of the items, equipment, consumables etc. to be re-exported by them after completion of services under this Contract along with all relevant documents.
- 12.4 Confidentiality of Information: All information obtained by contractor in the conduct of operations hereunder, including but not limited to, depth, formations penetrated, testing, surveying etc. shall be considered confidential and shall not be divulged by Contractor or its employees to anyone other than company's representative. This obligation of contractor shall be in force even after the termination of the Contract.
- 12.5 Contractor shall carryout normal maintenance of company's items at well site excepting for those items which contractor is not qualified to, or cannot maintain or repair, with its normal complement of personnel and equipment.
- 12.6 Contractor should provide the list of items to be imported in the format specified in **Proforma-A** for issuance of recommendatory letter to Directorate General of Hydrocarbons (DGH), New Delhi for clearance of goods from Indian customs at concessional (nil) rate of customs duty.
- 12.7 Contractor shall arrange for inland transportation of all equipment, etc. from the port to the place of work and back at the end of the work at their own expense. Arrangement of Road Permits and payment of Assam Entry Tax for bringing Contractor's equipment/material to Work place shall be Contractor's responsibility.

- 12.8 In case the Contractor imports the equipment etc. on re-export basis, the Contractor shall ensure for re-export of the equipment and all consumables and spares (except those consumed during the contract period) and complete all documentation required. Company will issue necessary certificates etc. as required. The Contractor should arrange for re-export of equipment within 60 days of notice of demobilisation issued by the Company. If the re-export is not completed within the specified period, customs duty, penalty etc. levied by customs authorities for such delay shall be to Contractor's account and same will be deducted by the Company from Contractor's bills and security deposit.
- 12.9 Contractor shall strictly comply with all statutory requirements including but not limited to following:
 - (i) Comply with all guidelines under Labour Act including but not limited to:
 - a) Wages of the workers working under the contract shall have to be made by the Contractor within 7th day of the following month. The payment shall have to be made in the respective Bank account of the workers and copy of the bank payment statement shall have to be submitted to Company representative by 8th of that month.
 - b) Contractor shall have to issue appointment letter and wage slip to each of the workers.
 - c) Contractor shall have to make payment to its workers complying with Minimum wage act to different class of workers, which gets revised time to time.
 - d) Contractor shall have to provide its workers UAN No. in respect of PF.
 - e) Contractor shall provide PPEs to its workers working under the contract.
 - f) Contractor will pay Bonus to its workers working under the contract as per payment of Bonus (Amendment) Act.
 - (ii) Comply with all DGMS statutory guidelines and OISD regulation.
 - (iii) Comply with all other statutory Act relevant during execution of the Contract.

13.0 COMPANY'S SPECIAL OBLIGATIONS:

- 13.1 Company shall at its cost, provide items and services as shown in this document.
- 13.2 Company shall be responsible at its cost, for maintaining adequate stock levels of its items and replenishing the same as deemed necessary, unless specified to the contrary elsewhere in the contract.
- 13.3 **Ingress and Egress at location**: Company shall provide contractor requisite certificates for obtaining rights of ingress to egress from the locations, where

wells are to be drilled, including any certificate required for permits or licenses for the movement of contractor's personnel. Should such permits/licenses be delayed because of objections of appropriate authorities in respect of specific Contractor's personnel, such personnel should be promptly removed from the list by the Contractor and replaced by acceptable personnel. For any stoppage of operations for such delays, no day rate shall be payable.

14.0 LOSS OR DAMAGE TO HOLE:

- OIL shall be liable for the cost of regaining control of any wild well, blowout, as well as the cost of removal of debris, and indemnify contractor.
- 14.2 In the event, the well is damaged by dropping of any tool/ tubing/fish or any reason of wilful acts or contractor's gross negligence or other legal fault, contractors liability shall be to carry out the operations as required for completion of the well to the reasonable satisfaction of company at contractor's cost. The fishing rate will be payable, in the event of Contractor dropping any tool/tubing/fish during the operation. However, the damaged to well is caused due to any reason of wilful acts or contractor's gross negligence or other legal fault, no rate will be payable during the period.

15.0 DAMAGE OR LOSS OF THE WORKOVER UNIT:

- a) The Contractor shall at all times be solely responsible for any damage to or loss or destruction of the Work over Unit and its other property irrespective of how such loss, damage or destruction is caused, and even if caused by the negligence of the Company and/or his servants, agents, nominees, assignees, Contractors and subcontractor, and Contractor shall hold harmless and indemnify the Company from and against any expenses, loss or claim related to or resulting from such loss, damages or destruction.
- b) If the Work over Unit is declared to be a total loss and/or construed to be total loss, as determined by the applicable insurance coverage, this contract shall terminate in respect of the Work over unit(s) as of the occurrence of the event causing such loss and each party shall thereupon be released of all further obligations hereunder in respect of that Work over unit(s), except for its payment of monies then due or liabilities to be charged in respect of work already done under this contract in respect of that Work over unit(s).

16.0 LOSS OR DAMAGE OF CONTRACTOR'S WORK OVER UNIT OR SUBSURFACE EQUIPMENT

a) Except as otherwise specifically provided in the contract, any damage to or loss, of the Drilling/Work over Unit and/or subsurface tools/equipment regardless of the cause or reason for said loss, shall be the loss of the Contractor, its underwriters or insurers. Contractor indemnifies OIL, its Co-licensees and its and their affiliates Companies, Agents, employees, invitees, servants, their underwriters or insurers (other than Contractor's) and their employees, agent any claim whatsoever or responsibility for any damage to or loss of the Drilling/Work over Unit or any other equipment or property of Contractor or Contractor's sub-contractors furnished or intended for use in the operations herein undertaken.

- b) If the Drilling/Work over Unit or any part thereof or subsurface tools/equipment is lost or damaged beyond repair or becomes an actual or constructive compromised, arranged loss or is otherwise abandoned, the Contractor shall, if required by OIL or by the laws, regulation or order of Governmental Authorities or Agency remove the Drilling/Work over Unit from operating areas to the satisfaction of the OIL. If the contractor unreasonably delays in removing the Drilling/ Work over Unit or any part thereof, the OIL may remove it and the contractor shall indemnify and reimburse OIL for all cost and expenses incurred by OIL in connection therewith. Any expense incurred by OIL in connection with or for locating the area/price of such loss/damage and/or ascertain whether such loss/ damage has resulted in any pollution or not, shall also be reimbursed by the Contractor to OIL.
- 17.0 <u>OIL'S EQUIPMENT</u>: Contractor shall assume the risk of and shall be solely responsible for, damage to and loss or destruction of materials and equipment or supplies furnished by OIL. In case there is a loss or damage to OIL's equipment for causes attributable to contractor, the contractor shall compensate OIL.
- **BLOWOUT OR CRATER**: In the event any well, while carrying out work over operation hereunder, shall blowout or crater due to negligence of contractor, contractor will bear the entire cost and expenses of killing the well or otherwise bringing the well under control and shall indemnify and hold company harmless in this regard. This provision is not to be interpreted as company assuming any liability for loss of property, damages, loss of life or injuries caused by such a blowout, except as otherwise provided under the terms and conditions of the contract.
- 19.0 **USE OF CONTRACTOR'S EQUIPMENT**: Company shall have the right to use the drilling / Work over unit and the entire contractor's equipment provided under the contract during such times as company or both company and the contractor are engaged in bringing the well under control.
- **OIL'S EQUIPMENT:** Contractor shall assume the risk of and shall be solely responsible for, damage to and loss or destruction of materials and equipment or supplies furnished by OIL. In case there is a loss or damage to OIL's equipment for causes attributable to contractor, the contractor shall compensate OIL.
- **21.0 POLLUTION AND CONTAMINATION**: Notwithstanding anything to the contrary contained herein, it is agreed that the responsibility and liability for pollution or contamination shall be as follows:
- a) Contractor shall assume all responsibility and liability for cleaning up and removal of pollution or contamination which originates above the surface from spills of fuels, lubricants, motor oils, pipe dope, paints, solvents and garbage wholly in Contractor's possession and control and/or directly associated with Contractor's equipment and facilities, caused, and that originating from normal water base drilling fluid and drill cuttings.
- b) Contractor shall assume all responsibility and liability for all pollution or contamination(attributable to the contractor), howsoever caused including control and removal of same, which may occur during the term of or arising out

of this contract and shall indemnify company from and against all claims, demands and causes of action of every kind and character arising from said pollution or contamination, including but not limited to that which may result from fire, blowout, cratering seepage or any other uncontrolled flow of oil, gas, water or other substance, as well as the use or disposal of oil base mud.

- c) In the event a third party commits an act of omission which results in pollution or contamination for which either the contractor or company, by whom such party is performing work is held to be legally liable, the responsibility shall be considered as between Contractor and company, regardless of the party for whom the job was performed and bidders liability will be limited to effluent collection point only.
- d) Contractor shall assume all responsibility and liability for erection/ installation and efficient operation of the mobile Effluent Treatment Plant, dismantling prior to ILM for next location and maintaining the sample analysis report for both solid and liquid output conforming to standard of SPCB.
- e) In the event effluent / waste pit provided by the company, getting filled up in the normal course which can be prevented by contractor, the same shall be emptied completely or partially by the contractor using disposal pumps, to avoid overflow in the neighbouring areas or alternatively the company will provide additional pits at its cost. In case pits so constructed have seepage from the walls of the pit or bund of the pit, company will take remedial action to prevent the same at its cost.
- **DEMOBILISATION & RE-EXPORT**: The Contractor shall arrange for and 22.0 execute demobilization of the entire Workover package, Tools/ Equipment / Spare/ Accessories/Manpower etc. upon receipt of notice for demobilization from Company. Demobilisation shall mean completion / termination of the contract and shall include dismantling of the complete Workover package, its accessories/equipment, including the manpower and re-export of the complete Workover package (if re-exportable), its accessories/equipment, unutilized spares and consumables at the cost of the contractor. Demobilization shall be completed by Contractor within 21 days of issue of demobilization notice by Company. Immediately after re-exporting the Workover package, its accessories, equipment and the unused spares and consumables, Contractor shall submit the detail re-export documents to Company as documentary proof of reexporting the complete Workover package, its accessories, equipment and the unused spares and consumables. In case of failure to re-export any of the items as above within the allotted time period of 60 days except under circumstances relating to Force Majeure, Company reserves the right to withhold the estimated amount equivalent to the Customs Duty and/or penalty leviable by customs on such default in re-export from Contractor's final settlement of bills and Performance Security.
- 22.1 In the event all / part of the equipment etc. are transferred by Contractor within the country to an area where nil Customs Duty is not applicable and/or sold to a third party after obtaining permission from Company and other appropriate government clearances in India, then Contractor shall be fully liable for payment of the Customs Duty.

- 22.2 Contractor must furnish an undertaking that "the equipment imported and also spares & accessories which remained unutilized after the expiry of the contract, would be re-exported at their own cost after completion of contractual obligation after observing all the formalities/ rules as per Customs Act or any other relevant Act of Govt. of India applicable on the subject". In case of non-observance of formalities of any provisions of the Customs Act or any other Act of Govt. of India, the Contractor shall be held responsible for all the liabilities including the payment of Customs Duty and penalties to the Govt. on each issue. Non-compliance of these provisions will be treated as breach of contract and their Performance Bank Guarantee will be forfeited.
- In the event all / part of the equipment etc. are transferred by Contractor after expiry/termination of the contract within the country to another operator for providing services, and/or sold to a third party, Contractor shall obtain all necessary Govt. of India clearances including the Customs formalities for transferring to another operator and/or sale of the Rig package, its accessories, equipment and the unused spares and consumables to a third party. Company will not be responsible for any non-compliance of these formalities by Contractor. Payment of Customs Duty and penalties(if any) imposed by Govt. of India or Customs authorities for transferring the items in part or in full to an area where Nil Customs Duty is not applicable or sale of the items shall be borne by the Contractor and Contractor indemnifies Company from all such liabilities.
- **CONFIDENTIALITY:** Contractor agrees to be bound by professional secrecy and undertake to keep confidential any information obtained during the conduct of drilling operations, including, but not limited to, formations penetrated, results of coring, testing and surveying of the well. And to take all-reasonable steps to ensure the contractor's personnel likewise keep such information confidential.
- 23.1 This obligation shall keep in force even after the termination date and until such information will be disclosed by company.
- 23.2 Contractor shall handover to company all company's documents or drafts concerning operations carried out and which are still in its possession before transferring the Unit to another sphere.
- 23.3 Contractor shall forbid access to the Workover Unit to any people not involved in operations or not authorized by the company to have access to the Workover Unit, however, this provision is not applicable to any Government and/or police representative on duty.
- **24.0 RIGHTS AND PRIVILEGES OF COMPANY**: Company shall be entitled:
- 24.1 To check the Effluent Treatment Unit and Contractor's items before the commencement Date. If they are not found in good order or do not meet specifications as per Section II or in case of non-availability of some of the Contractor's items listed therein, the contractor may not be allowed for commencement until the contractor has remedied such default.
- To change the drilling locations, programme, mud programme, well depths to complete or abandon any well at any time.
- 24.3 To approve the choice of sub-contractors for any essential third party contract, concerning materials, equipment, personnel and services to be rendered by

- contractor. Sub-contract may be entered into by contractor only after Company's approval.
- To check, at all times, contractor's stock level, to inspect contractor's equipment and request for renovation or replacement thereof, if found in unsatisfactory condition or not conforming to regulations or specifications.
- 24.5 To order suspension of operations while and whenever:
 - a) Contractor's personnel is deemed by company to be not satisfactory, or
 - b) Contractor's equipment does not conform to regulations or to the specifications laid down in the Contract.
 - c) Contractor's equipment and practices turns into a danger to personnel on or around the rig or to the well, or
 - d) Contractor's insurance in connection with the operations hereunder is found by company not to conform with the requirements set forth in the contract.
 - e) Contractor fails to meet any of the provisions in the contract.
 - f) Any shortage in key/additional (compulsory) personnel and inadequacy of other personnel.
- 24.6 To reduce the rates reasonably, at which payments shall be made if the contractor is allowed to continue the operation despite having certain deficiency in meeting the requirements as per provision in the contract.

25.0 EMERGENCY:

- 25.1 Without prejudice to clause 18.0 hereof company shall be entitled in emergency (the existence of which shall be determined by company) at its own discretion, to take over the operations of the Workover unit, direct contractor's personnel in the event that company's interest will demand so. In such case, company will notify contractor of its action and within three (3) days confirm such notice in writing, setting forth the reasons for its action.
- In such event, company shall pay contractor in accordance with the terms of the contract as if contractor was carrying out the operations.
- All operations so conducted shall remain at the risk of contractor to the extent contractor is covered by insurance. When the well has been completed or when the conduct of the operations has been returned to the contractor, the equipment shall again be put at contractor's disposal in the same condition as at the time the operations were taken over by company, taking into account normal wear and tear and any inherent defects at the time of taking over by the company.
- **26.0 HEADINGS**: The headings of the clauses of the contract are for convenience only and shall not be used to interpret the provisions hereof.

DEFICIENCY: In the event of the contractor failure to strictly adhere in providing the minimum requirements of key personnel as set out in Section II, Clause 7.18, L, the penalty shall be levied at the following rates.

	FAILURE	PENALTY
a)	Failure to provide Rig Manager and tool pusher / Tour Pusher	At the rate of 5% of the operating day rate for the period of non-availability of the Rig Manager/Tour/Tool Pusher separately in each case.
b)	Failure to provide Driller and Asstt. Driller.	At the rate of 3% of the operating day rate for the period of non-availability of the Driller and Asstt. Driller separately in each case.
c)	Failure to provide other key personnel excepting those mentioned in 'a' & 'b' above.	1 0

NOTE:

- 1. The above penalty rates are applicable for the first five days. In case more than one key personnel are not available at a time, penalties applicable for such personnel will be levied simultaneously.
- 2. Beyond 5 days, the penalty will be levied at double the rates mentioned above for each day for non-availability of any key personnel.
- 3. Contractor will be paid for zero rate if operation is suspended for non-availability of key personnel.

28.0 INTER-LOCATION RIG MOVE STANDARD

- 28.1 Rig movement time for a distance upto 50 (Fifty) Kms will be six (6) days. For more kilometerage, the time allowed shall be in proportions of one (1) day for each 50 KM or part thereof. For Cluster location, rig movement time shall be limited to 3 days.
- 28.2 The time for inter-location movement suspended by force majeure, shall be extended by the period for which the Force majeure conditions last. No day rate will be payable for extended period due to force majeure conditions.
- 28.3 The ILM charge shall be discounted by 5% for each day's delay beyond the standard, as stipulated in 28.1 and 28.2, of total cost for inter-location movement rate payable for that particular rig movement, when the rig move is delayed beyond the standard.

29.0 PREVENTION OF FIRE AND BLOWOUTS

29.1 Contractor shall maintain all well control equipment in good condition at all times and shall take all possible steps to control and prevent the fire and blowouts to protect the hole. The Contractor shall be responsible for taking all

preventive and corrective measures for initial control of kick, inflow, fire and blowouts. After initial control of well, Contractor shall inform the Company's Representative about the well condition and finally well shall be killed after mutual discussion with Company's representative.

- 29.2 Contractor shall test the BOPs by making pressure test atleast once in every 7 days or such time as instructed by the Company Representative. However, the testing procedure and frequency must comply with the Mines Rule. Contractor shall record results of all such tests in the daily work over report.
- **DISCIPLINE**: The Contractor shall maintain strict discipline and good order among their respective employees and their respective Sub-contractors, if any, and shall abide by and conform to all rules and regulations promulgated by the Company and Contractor governing the operations at the assigned worksites. Should the Company feel with just cause that the conduct of any of the Contractor's personnel is detrimental to Company's interests; the Company shall notify Contractor in writing the reasons for requesting removal of such personnel. The Contractor shall remove and replace such employees at their expense within 7 days from the time of such instruction given by the Company.

31.0 EFFLUENT PIT BUNDS:

- i. Regular checks are to be made to ensure that there are no leakage/seepage/overflow of effluents from the pit into the surrounding areas.
- ii. The bunds/walls of the effluent pit are to be checked by Contractor for any breaches during the operation. Any imminent breach of effluent bunds and walls shall be informed by Contractor to Company's representative in time for taking corrective measures. In the event of any damages to the effluent pit and its bunds and walls including the surrounding area due to delayed information by Contractor to Company, Contractor shall be responsible.
- **COLLECTION OF USED/ BURNT LUBE OIL**: The used lube oils are to be collected separately in drums. Floating burnt oil, if any, in the effluent pit has to be lifted and collected into drums immediately.
- 33.0 The Contractor shall not make Company liable to reimburse the Contractor to the statutory increase in the wage rates of the contract labour appointed by the Contractor. Such statutory or any other increase in the wage rates of the contract labour shall be borne by the Contractor.
- Any permission from the Mines Directorate in connection with working in excess of 8 (eight) hours per day shift pattern by the Contractor shall have to be arranged by the Contractor before commencement of the Contract, in consultation with the Company. Moreover, since the Contractor's personnel engaged shall be working under the Mines Act and Oil Mines Regulations, the Contractor shall have to obtain any other relevant permission from the Mines Directorate to engage their employees in compliance with various procedures as per Mines Act. In case of any breach of procedures under Mines Act the Contractor shall be held responsible and they shall bear all expenses arising as a result thereof.

- 35.0 The Contractor shall not engage labour below 18 (eighteen) years of age under any circumstances. Persons above 60 years age also shall not be deployed.
- **36.0** Moreover, the Contractor should obtain and produce in advance to commencement of Work the following certificate / approvals:
 - (i) Approval from DGMS/ DDMS for shift patterns in excess of 8 hours.
 - (ii) Total manpower list.
 - (iii) License/ certificate from specified electrical authorities for the rig and camp electrical personnel, if required.
 - (iv) All certificates as per applicable laws including Mines Acts.
 - (v) Regional Labour certificate, if required.
- **WAIVERS AND AMENDMENTS**: It is fully understood and agreed that none of the terms and conditions of the contract shall be deemed waived or amended by either party unless such waiver or amendment is executed in writing by the duly authorized agents or representatives of such party. The failure of either party to execute any right of termination shall not act as a waiver or amendment of any right of such party provided hereunder.

38.0 WATER MANAGEMENT:

- i. Strict control has to be made in on the use of water. Wastage of water increases the effluent volume in the pit and may aggravate pollution problems.
- ii. The valves, glands, hoses etc. are to be checked for any leakage and the same to be informed immediately to the concerned for rectification.
- iii. Arrangements have to be made for pumping effluents into the nearest dry pit in case of emergency.

39.0 RECORD OF PERSONNEL PROTECTIVE EQUIPMENT (PPE):

- (i) Contractor shall issue PPE regularly to its personnel and a register shall be maintained at well site with endorsement by employee and indicating date of issue/replacement etc.
- (ii) However when a PPE is damaged during its legitimate use, it shall be immediately replaced by the contractor.
- (iii) Depending upon the risk, suitable protective equipment including eye protectors, ear protection, gloves and aprons.
- (iv) Contractor shall at all times maintain a sufficient stock of PPE in order to ensure immediate supply as and when need for the same arises.

40.0 MoEF [Ministry of Environment & Forest] GUIDELINES:

The overall noise level in and around the operational areas shall have to be kept within the standards by providing noise control measures including acoustic hoods, silencers, enclosures on all sources of noise generation. The ambient

noise level shall conform to standards prescribed under EPA rules, 1989 that is 75 dBA (daytime) and 70 dBA (night time).

41.0 PAYMENT OF WAGES:

- a) The Service Provider must make the Wages to all the personnel/Manpower deployed under the contract as per the Minimum wages act and it should be strictly adhered to the prevailing minimum wages as declared and made applicable from time to time by statutory authorities.
- b) All wages to the personnel should be made by 10th of each month and in case payments are not made regularly, subsequent invoices might be kept on hold.
- c) Wage slip to all the personnel deployed under the contract to be issued as per the THE CONTRACT LABOUR (REGULATION AND ABOLITION) CENTRAL RULES, 1971, Chapter VII, Section 78(1)(b) vide Form XIX.
- d) Employment card as per the CONTRACT LABOUR (REGULATION AND ABOLITION) CENTRAL RULES, 1971, vide form XIV.

42.0 IDENTITY CARDS:

The Contractor shall have to arrange for 'photo gate-passes', 'vehicle-passes', etc. for all his personnel, vehicles, etc. for working inside the installation and Township area premises, at his own cost and as per the rules of OIL and Security Guidelines including police verification.

43.0 GENERAL HSE POINTS:

- 43.1 It will be solely the Contractor's responsibility to fulfil all the legal formalities with respect to the Health, Safety and Environmental aspects of the entire job (namely; the person employed by him, the equipment, the environment, etc.) under the jurisdiction of the district of that state where it is operating. Ensure that all sub-contractors hired by him comply with the same requirement as the contractor himself and shall be liable for ensuring compliance all HSE laws by the sub or sub sub-contractors.
- Every person deployed by the contractor in a mine must wear safety gadgets to be provided by the contractor. The Contractor shall provide proper Personnel Protective Equipment as per the hazard identified and risk assessed for the job and conforming to statutory requirement and company PPE schedule. Safety appliances like protective footwear, Safety Helmet and Full Body harness has to be DGMS approved. Necessary supportive document shall have to be submitted as proof. If the Contractor fails to provide the safety items as mentioned above to the working personnel, the Contractor may apply to the Company (OIL) for providing the same. OIL will provide the safety items, if available. But in turn, OIL will recover the actual cost of the items by deducting from Contractor's Bill. However, it will be the Contractor's sole responsibility to ensure that the persons engaged by him in the mines use the proper PPE while at work. All the safety gears mentioned above are to be provided to the working personnel before commencement of the work.
- 43.3 The Contractor shall prepare written Safe Operating Procedure (SOP) for the work to be carried out, including an assessment of risk, wherever possible and

safe methods to deal with it/them. The SOP should clearly state the risk arising to men, machineries & material from the mining operation / operations to be done by the contractor and how it is to be managed.

- The contractor shall provide a copy of the SOP to the person designated by the mine owner who shall be supervising the contractor's work.
- Keep an up to date SOP and provide a copy of changes to a person designated by the Mine Owner/Agent/Manager.
- Contractor has to ensure that all work is carried out in accordance with the Statute and SOP and for the purpose he may deploy adequate qualified and competent personnel for the purpose of carrying out the job in a safe manner. For work of a specified scope/nature, he should develop and provide to the mine owner a site specific code of practice in line.
- 43.7 All persons deployed by the contractor for working in a mine must undergo Mines Vocational Training, initial medical examination, PME. They should be issued cards stating the name of the contractor and the work and its validity period, indicating status of MVT, IME & PME.
- 43.8 The contractor shall submit to DGMS returns indicating Name of his firm, Registration number, Name and address of person heading the firm, Nature of work, type of deployment of work persons, Number of work persons deployed, how many work persons hold MVT Certificate, how many work persons undergone IME and type of medical coverage given to the work persons.
- 43.9 The return shall be submitted quarterly (by 10th of April, July, October & January) for contracts of more than one year. However, for contracts of less than one year, returns shall be submitted monthly.
- 43.10 It will be entirely the responsibility of the Contractor/his Supervisor/representative to ensure strict adherence to all HSE measures and statutory rules during operation in OIL's installations and safety of workers engaged by him. The crew members will not refuse to follow any instruction given by company's Installation Manager / Safety Officer / Engineer / Official / Supervisor/Junior Engineer for safe operation.
- 43.11 Any compensation arising out of the job carried out by the Contractor whether related to pollution (attributable to the Contractor), Safety or Health will be paid by the contractor only.
- 43.12 Any compensation arising due to accident of the Contractor's personnel while carrying out the job, will be payable by the contractor.
- 43.13 The contractor shall have to report all incidents including near miss to Installation Manager / departmental representative of the concerned department of OIL.
- 43.14 The contractor has to keep a register of the persons employed by him/her. The contractor's supervisor shall take and maintain attendance of his men every day for the work, punctually.

- 43.15 If the company arranges any safety class / training for the working personnel at site (company employee, contractor worker, etc.) the contractor will not have any objection to any such training.
- 43.16 The health check-up of contractor's personnel is to be done by the contractor in authorized Health Centres as per OIL's requirement & proof of such test(s) is to be submitted to OIL. The frequency of periodic medical examinations should be every five years for the employees below 45 years of age and every three years for employees of 45 years of age and above.
- 43.17 To arrange daily tool box meeting and regular site safety meetings and maintain records.
- 43.18 Records of to be maintained in Form A (Part A, B), B, D & E (as per Ease of Compliance Gazette Notification No 126 dated 21.02.2017) by the contractor (Details in Clause 1.11).
- 43.19 A contractor employee must, while at work, take reasonable care for the health and safety of people who are at the employee's place of work and who may be affected by the employee's act or omissions at work.
- 43.20 A contractor employee must, while at work, cooperate with his or her employer or other persons so far as is necessary to enable compliance with any requirement under the act or the regulations that is imposed in the interest of health, safety and welfare of the employee or any other person.
- 43.21 Contractor's arrangements for health and safety management shall be consistent with those for the mine owner.
- 43.22 In case Contractor is found non-compliant of HSE laws as required company will have the right for directing the contractor to take action to comply with the requirements, and for further non-compliance, the contractor will be penalized prevailing relevant Acts/Rules/Regulations.
- When there is a significant risk to health, environment or safety of a person or place arising because of a non-compliance of HSE measures, company will have the right to direct the contractor to cease work until the non-compliance is corrected.
- The contractor should prevent the frequent change of his contractual employees as far as practicable.
- The contractor should frame a mutually agreed bridging document between OIL & the contractor with roles and responsibilities clearly defined.
- For any HSE matters not specified in the contract document, the contractor will abide the relevant and prevailing Acts/rules/regulations/ pertaining to Health, Safety and Environment.

- **44.0 HSE POLICY:** The contractor shall forward HSE policy to the Company along with the bid. On award of contract, the contractor shall submit comprehensive HSE manual & procedure and HSE plan for approval of OIL.
- **45.0 EMERGENCY RESPONSE PLAN**: The contractor shall maintain Rig Specific Emergency Response Plan (ERP) for onsite. The contractor shall also maintain risk register.

46.0 GOODS AND SERVICES TAX:

- In view of GST Implementation from 1st July 2017, all taxes and duties including Excise Duty, CST/VAT, Service tax, Entry Tax and other indirect taxes and duties have been submerged in GST. Accordingly reference of Excise Duty, Service Tax, VAT, Sales Tax, Entry Tax or any other form of indirect tax except of GST mentioned in the bidding document shall be ignored.
 - Bidders are required to submit copy of the GST Registration Certificate while submitting the bids wherever GST (CGST & SGST/UTGST or IGST) is applicable.
- 46.2 "GST" shall mean Goods and Services Tax charged on the supply of material(s) and services. The term "GST" shall be construed to include the Integrated Goods and Services Tax (hereinafter referred to as "IGST") or Central Goods and Services Tax (hereinafter referred to as "CGST") or State Goods and Services Tax (hereinafter referred to as "SGST") or Union Territory Goods and Services Tax (hereinafter referred to as "UTGST") depending upon the import / interstate or intrastate supplies, as the case may be. It shall also mean GST compensation Cess, if applicable.
- Quoted price/rate(s) should be inclusive of all taxes and duties, except GST (i.e. IGST or CGST and SGST/UTGST applicable in case of interstate supply or intra state supply respectively and cess on GST if applicable) on the final service. However, GST rate (including cess) to be provided in the respective places in the Price Bid .Please note that the responsibility of payment of GST (CGST & SGST or IGST or UTGST) lies with the Supplier of Goods/Services (Service Provider) only .Supplier of Goods/Services (Service Provider) providing taxable service shall issue an Invoice/Bill, as the case may be as per rules/regulation of GST. Further, returns and details required to be filled under GST laws & rules should be timely filed by Supplier of Goods/Services (Service Provider) with requisite details.
- 46.4 Bidder should also mention the Harmonised System of Nomenclature (HSN) and Service Accounting Codes (SAC) at the designated place in SOR.
- 46.5 Where the OIL is entitled to avail the input tax credit of GST:
 - OIL will reimburse the GST to the Supplier of Goods/Services (Service Provider) at actual against submission of Invoices as per format specified in rules/regulation of GST to enable OIL to claim input tax credit of GST paid. In case of any variation in the executed quantities, the amount on which the GST is applicable shall be modified in same proportion. Returns and details required

to be filled under GST laws &rules should be timely filed by supplier with requisite details.

The input tax credit of GST quoted shall be considered for evaluation of bids, as per evaluation criteria of tender document.

46.6 Where the OIL is not entitled to avail/take the full input tax credit of GST:

OIL will reimburse GST to the Supplier of Goods/Services (Service Provider) at actual against submission of Invoices as per format specified in rules/regulation of GST subject to the ceiling amount of GST as quoted by the bidder. In case of any variation in the executed quantities (If directed and/or certified by the In-Charge) the ceiling amount on which GST is applicable will be modified on pro-rata basis.

The bids will be evaluated based on total price including GST.

- 46.7 Payments to Service Provider for claiming GST amount will be made provided the above formalities are fulfilled. Further, OIL may seek copies of challan and certificate from Chartered Accountant for deposit of GST collected from OIL.
- 46.8 Contractor/Contractor shall be required to issue tax invoice in accordance with GST Act and/or Rules so that input credit can be availed by OIL. In the event that the contractor/Contractor fails to provide the invoice in the form and manner prescribed under the GST Act read with GST Invoicing Rules there under, OIL shall not be liable to make any payment on account of GST against such invoice.
- 46.9 GST shall be paid against receipt of tax invoice and proof of payment of GST to government. In case of non-receipt of tax invoice or non-payment of GST by the contractor/Contractor, OIL shall withhold the payment of GST.
- 46.10 GST payable under reverse charge mechanism for specified services or goods under GST act or rules, if any, shall not be paid to the contractor/Contractor but will be directly deposited to the government by OIL.
- 46.11 Where OIL has the obligation to discharge GST liability under reverse charge mechanism and OIL has paid or is/liable to pay GST to the Government on which interest or penalties becomes payable as per GST laws for any reason which is not attributable to OIL or ITC with respect to such payments is not available to OIL for any reason which is not attributable to OIL, then OIL shall be entitled to deduct/setoff/recover such amounts against any amounts paid or payable by OIL to Contractor/Supplier.
- 46.12 Notwithstanding anything contained anywhere in the Agreement, in the event that the input tax credit of the GST charged by the Contractor/Contractor is denied by the tax authorities to OIL for reasons attributable to Contractor/Contractor, OIL shall be entitled to recover such amount from the Contractor/Contractor by way of adjustment from the next invoice. In addition to the

amount of GST, OIL shall also be entitled to recover interest at the rate prescribed under GST Act and penalty, in case any penalty is imposed by the tax authorities on OIL.

- 46.13 TDS under GST, if applicable, shall be deducted from contractor's/Contractor's bill at applicable rate and a certificate as per rules for tax so deducted shall be provided to the contractor/Contractor.
- 46.14 The Contractor will be under obligation for charging correct rate of tax as prescribed under the respective tax laws. Further the Contractor shall avail and pass on benefits of all exemptions/concessions available under tax laws. Any error of interpretation of applicability of taxes/duties by the contractor shall be to contractor's account.
- 46.15 It is the responsibility of the bidder to quote the correct GST rate. The classification of goods/services as per GST (Goods & Service Tax) Act should be correctly done by the contractor to ensure that input tax credit on GST (Goods & Service Tax) is not lost to the OIL on account of any error on the part of the contractor.
- 46.16 In case, the quoted information related to various taxes, duties & levies subsequently proves wrong, incorrect or misleading, OIL will have no liability to reimburse the difference in the duty/tax, if the finally assessed amount is on the higher side and OIL will have to right to recover the difference and in case the rate of duty/taxes finally assessed is on the lower side.
- 46.17 Notwithstanding anything mentioned elsewhere in the Bidding Document the aggregate liability of OIL towards Payment of Taxes & Duties shall be limited to the volume of GST declared by the bidder in its bid & nothing shall be payable extra except for the statutory variation in taxes &duties.
- 46.18 Further, it is the responsibility of the bidders to make all possible efforts to make their accounting/IT system GST compliant in order to ensure availability of Input Tax Credit (ITC) to Oil India Ltd.
- 46.19 GST liability, if any on account of supply of free samples against any tender shall be to bidder's account.
- In case of statutory variation in GST, other than due to change in turnover, payable on the contract value during contract period, the Supplier of Goods/ Services (Service Provider) shall submit a copy of the 'Government Notification' to evidence the rate as applicable on the Bid due date and on the date of revision.
- 46.21 Beyond the contract period, in case OIL is not entitled for input tax credit of GST, then any increase in the rate of GST beyond the contractual delivery period shall be to Service provider's account whereas any decrease in the rate GST shall be passed on to the OIL.

- 46.22 Beyond the contract period, in case OIL is entitled for input tax credit of GST, then statutory variation in applicable GST on supply and on incidental services, shall be to OIL's account.
- 46.23 Claim for payment of GST/Statutory variation, should be raised within two [02] months from the date of issue of 'Government Notification' for payment of differential (in %) GST, otherwise claim in respect of above shall not be entertained for payment of arrears.
- The base date for the purpose of applying statutory variation shall be the Bid Opening Date.
- 46.25 The contractor will be liable to ensure to have registered with the respective tax authorities, wherever applicable and to submit self-attested copy of such registration certificate(s) and the Contractor will be responsible for procurement of material in its own registration (GSTIN) and also to issue its own Road Permit/E-way Bill, if applicable etc.
- In case the bidder is covered under Composition Scheme under GST laws, then bidder should quote the price inclusive of the GST (CGST & SGST/UTGST or IGST). Further, such bidder should mention "Cover under composition system" in column for GST (CGST & SGST/UTGST or IGST) of price schedule.
- 46.27 OIL will prefer to deal with registered supplier of goods/services under GST. Therefore, bidders are requested to get themselves registered under GST, if not registered yet. However, in case any unregistered bidder is submitting their bid, their prices will be loaded with applicable GST while evaluation of bid. Where OIL is entitled for input credit of GST, the same will be considered for evaluation of bid as per evaluation methodology of tender document.
- 46.28 Procurement of Specific Goods: Earlier, there is no tax incidence in case of import of specified goods (i.e. the goods covered under List-34 of Customs Notification no. 12/2012-Cus dated. 17.03.2012 as amended). Customs duty is not payable as per the policy. However, under GST regime, IGST Plus GST compensation cess (if applicable) would be leviable on such imports. Bidders should quote GST as inclusive considering IGST component for the imported Materials portion while quoting their prices on destination basis. However, GST rate to be specified in the price bid format.
- 46.29 Documentation requirement for GST

The Contractor will be under the obligation for invoicing correct tax rate of tax/duties as prescribed under the GST law to OIL, and pass on the benefits, if any, after availing input tax credit.

Any Invoice issued shall contain the following particulars:

- a) Name, address and GSTIN of the supplier;
- b) Serial number of the invoice;
- c) Date of issue;
- d) Name, address and GSTIN or UIN, if registered of the recipient;
- e) Name and address of the recipient and the address of the delivery, along with the State and its code,
- f) HSN code of goods or Accounting Code of services [SAC];
- g) Description of goods or services;
- h) Quantity in case of goods and unit or Unique Quantity Code thereof;
- i) Total value of supply of goods or services or both;
- j) Taxable value of supply of goods or services or both taking into discount or abatement if any;
- k) Rate of tax (IGST, CGST, SGST/ UTGST, cess);
- Amount of tax charged in respect of taxable goods or services (IGST, CGST, SGST/UTGST, cess);
- m) Place of supply along with the name of State, in case of supply in the course of interstate trade or commerce;
- n) Address of the delivery where the same is different from the place of supply and
- o) Signature or digital signature of the supplier or his authorised representative.

GST invoice shall be prepared in triplicate, in case of supply of goods, in the following manner:

- i) The original copy being marked as ORIGINAL FOR RECIPIENT;
- ii) The duplicate copy being marked as DUPLICATE FOR TRANSPORTER and
- iii) The triplicate copy being marked as TRIPLICATE FOR SUPPLIER.

In case of any advance given against any supplies contract, the supplier of the goods shall issue Receipt Voucher containing the details of details of advance taken along with particulars as mentioned in clause no. (a), (b), (c), (d), (g), (k), (l), (m) & (o) above.

46.30 Anti-profiteering clause

As per Clause 171 of GST Act it is mandatory to pass on the benefit due to reduction in rate of tax or from input tax credit to the consumer by way of commensurate reduction in prices. The Supplier of Goods/Services may note the above and quote their prices accordingly.

In case the GST rating of Contractor on the GST portal/Govt. official website is negative/black listed, then the bids may be rejected by OIL. Further, in case rating of bidder is negative/black listed after award of work for supply of goods/services, then OIL shall not be obligated or liable to pay or reimburse GST to such Contractor and shall also be entitled to deduct/recover such GST along with all penalties/interest, if any, incurred by OIL.

47.0 CUSTOMS DUTY:

47.1 In terms of Sl. No. 404 of the Customs Notification No.50/2017-Cus dated 30.06.2017, imports of the items specified in List 33 of the Notification are subject to levy of concessional rate of customs duty @5% (BCD Nil & IGST @5%) subject to conditions specified therein (Condition No. 48). However, this is subject to change as per Government guidelines and the provisions ruling at the time of tender closing will be applicable.

Similarly, the domestic supply of such goods would attract 5% GST (i.e. IGST or CGST & SGST/UTSGT) on submission of EC in terms of GST Notification No. 03/2017.

- 47.2 Bidder should provide the list of items to be imported by them under the Contract in the format specified in Proforma-A along with their bid for issuance of Recommendatory Letter to DGH. Contractor shall made written request to Company immediately after shipment of the goods indicated by them in Proforma-A, along with the Invoices and all shipping documents (with clear 15 working days' notice) requesting Company for issuance of the Recommendatory Letter. OIL shall issue the Recommendatory Letter provided all the documents submitted by the Contractor are found in order as per contract. It shall be however, Contractor's responsibility to obtain EC from DGH and clear the goods through customs. OIL shall not be liable in whatsoever manner for the rejection of their claims for zero customs duty by any of the authorities including DGH. Contractor shall indemnify OIL from all liabilities of Customs Duty.
- 47.3 All imports and import clearances under the contract shall be done by the contractor and OIL shall not provide any assistance in this regard.
- 47.4 However, in the event customs duty becomes leviable during the course of contract arising out of a change in the policy of the Government, Company shall be liable for payment of the customs duties leviable in India on Contractor's items as provided in Proforma-A or the actuals whichever is less, provided Contractor furnishes all necessary documents indicating the estimated customs duty at least 10 days in advance. Such payment of Customs Duty shall be arranged by Company and made available to the representatives of Contractor at Kolkata within 3 working days after Contractor submits the undisputed and clear necessary documents / duty assessment papers at Company's office at Kolkata. Contractor would be responsible for passing such payment to customs authorities at the port of entry. Company's obligation for Customs Duty payment shall be limited / restricted to the tariff rates as assessed by the Customs on the day of clearance, or as on the last day of the stipulated mobilisation period. In case of clearance thereafter, on the CIF value of items in Proforma-A will be frozen and any increase in Customs Duty on account of increase in value on these will be to the Contractor's account. Furthermore, in case the above CIF value is not acceptable to assessing Customs Officer and as a result if any excess Customs Duty becomes payable, it shall be to Contractor's account. Before filing Bill of lading, Bill of entry, the Contractor must consult the Company to avoid payment of excess Customs Duty.
- 47.5 Contractor shall, however, arrange clearance of such items from Customs and port authorities in India and shall pay all requisite demurrages, if any, clearance fees/charges, port fees, clearing and forwarding agent fees/ charges, inland

transport charges etc. Company shall provide all assistance by issuance of necessary letter of authority or other relevant documents and necessary help.

47.6 Contractor must ensure that the spares and consumables imported by them for providing the services under Contract are properly used in executing their job under the Contract in the PEL/ML areas of Company for which EC has been obtained. Contractor shall furnish to Company a certificate as and when the spares and consumables are used/consumed certifying that the spares and the consumables imported by them have been consumed in those ML and PEL areas under the contract for which ECs were obtained by them. In order to avoid any misuse of the spares and consumables imported by the Contractor for providing the services under the Contract, Contractor shall furnish an Undertaking similar to that being furnished by Company to Customs of suitable amount before issue of the Recommendatory Letter.

48.0 NOTICES:

48.1 Any notice given by one party to other, pursuant to this Contract shall be sent in writing or by telex or Fax and confirmed in writing to the applicable address specified below:

Company

a) For contractual matters

CGM (Contracts)
OIL INDIA LIMITED
PO DULIAJAN - 786602
ASSAM, INDIA
Fax No. 91-374-2803549
Email: contracts@oilindia.in

b) For technical matters

CGM (Drilling Service)
OIL INDIA LIMITED
PO Duliajan - 786602,
Assam, India
Fax No. 91-374-2804254
Email: drilling@oilindia.in

- 1	~ -		-4-	
c)	Co	ntra	CTO	r

Fax No.:

48.2 A notice shall be effective when delivered or on the notice's effective date, whichever is later.

END OF SECTION-III

Part-3 SECTION-IV SCHEDULE OF RATES (SOR)

The bidders must quote the following rates in their priced bids as per the format given in Proforma-B.

1.0 MOBILIZATION CHARGES (ONE TIME LUMP SUM CHARGES) (M)

In case the rig package is contemplated to be mobilized partly or fully from outside India then the breakup of the mobilization charges to 1st location must be furnished separately.

a) Mobilization charges "M" should include mobilization of equipment and manpower for 1(one) work over rig.

(Equipment includes self-propelled mobile work-over rig under Clause No. 7.1 of Section-II, well servicing pump, source water pump & pump for filter & blender unit under Clause No. 7.2 of Section-II, generating set under Clause No. 7.3 of Section-II, tankages under Clause No. 7.4 of Section-II, suction & delivery system under Clause No. 7.5 of Section-II, lighting system under Clause No. 7.6 of Section-II, other equipments under Clause No. 7.7 of Section-II, handling tools under Clause No. 7.8 of Section-II, Fishing tools under Clause No. 7.9 of Section-II, BOP under Clause No. 7.10 of Section-II, BOP Control unit under Clause No. 7.11 of section-II, Safety devices under Clause No. 7.15 of Section-II, Tubulars and cross over subs (one lot against two rigs) against clause no 7.17 a of Section - II, Two sets of Welding Machines (one set against each rig) against clause no. 7.12 of Section - II, one no 40 MT crane (one no against each rig) against clause no. 7.13 of Section - II, one no Light truck (against two rigs) against clause no. 7.17 b of Section - II, Man power under Clause No. 7.18 L of Section-II)

- b) Mobilization charges should cover local and foreign costs to be incurred by the Contractors to mobilize to the first location.
- c) The first location will be in and around Duliajan, Assam.
- d) Total 01(One)/02 (Two) work-over rigs shall be mobilized by the Contractor and accordingly mobilization charges shall be paid upon completing mobilization of each rig.

NOTE: Mobilization charges "M" should not exceed 7.1/2% of TCRO (i.e. the total estimated charges for operation of each rig for 03 years).

2.0 **DEMOBILIZATION CHARGES (LUMP SUM) (D)**

For each rig package from last drilling location

a) Demobilization charges "D" should include demobilization of all equipment and manpower attached with 1(one) work-over rig.

(Equipment includes self-propelled mobile work-over rig under clause No. 7.1 of Section-II, well servicing pump, source water pump & pump for filter & blender unit under Clause No. 7.2 of Section-II, generating set under Clause No. 7.3 of

Section-II, tankages under Clause No. 7.4 of Section-II, suction & delivery system under Clause No. 7.5 of Section-II, lighting system under Clause No. 7.6 of Section-II, other equipments under Clause No. 7.7 of Section-II, handling tools under Clause No. 7.8 of Section-II, Fishing tools under Clause No. 7.9 of Section-II, BOP under Clause No. 7.10 of Section-II, BOP Control unit under Clause No. 7.11 of Section-II, Safety devices under Clause No. 7.15 of Section-II, Tubulars and cross over subs (one lot against two rigs) against clause no. 7.17 a of Section - II, Two sets of Welding Machines (one set against each rig) against clause no. 7.12 of Section - II, one no . 40 MT crane (one no against each rig) against clause no. 7.13 of Section - II, one no Light truck (against two rigs) against clause no. 7.17 b of Section - II, Man power under Clause No. 7.18 L of Section-II).

b) Total 02(Two)/04 (Four) work-over rigs shall be mobilized by the Contractor and accordingly de-mobilization charges shall be paid upon demobilization of each rig.

3.0 OPERATING DAY RATE (Per 24 Hrs. day) (OC)

The Operating Day rate will become payable from the time the Rig is rigged up and made ready for killing the well, until the rig is released for movement to the next location during the following operations:

- (a) Tripping with Contractor's/ Operator's drill pipes/ tubings
- (b) Circulating with kill fluid
- (c) Making up and breaking down drill pipes, drill collars tubing and other tubulars
- (d) Drilling out/Clean out cement, Bridge Plug, Collar and Shoe
- (e) Milling/ Cleaning jobs with Mud Motor
- (f) Fishing operations
- (g) Casing running-in/Pulling-out and cementation
- (h) Mixing or conditioning mud with Contractor's drill pipe in the hole.
- (i) Swabbing operations
- (j) Retrieving casing
- (k) Any other operations as required for well completion
- (l) Assembling and dis-assembling of BOP and well head hook-up.

4.0 STANDBY DAY RATE (Per 24 Hrs. Day) (70% of OC)

The Standby day rate shall be 70% of the operating day rate.

The Standby by rate will be payable under the following conditions:

- A. Waiting on cement
- B. Electric logging and wire line operations (both open and cased hole)
- C. Production testing
- D. Waiting on order
- E. Waiting on Company's equipment, materials and services.
- F. For all time during which the Company at its option may suspend operations.
- G. Waiting for daylight for certain production testing operation.

5.0 REPAIR DAY RATE (Per 24 Hrs. day) (60% of OC)

a. The Repair Day rate shall be payable when operations are suspended due to break-down or repair of Contractor's equipment.

- b. The Contractor shall be paid repair day rate to a maximum of 30 cumulative hours per calendar month. Beyond the aforesaid 30 hours, no day rate will be payable until operations are resumed, at which time the applicable rate shall again come into force.
- c. This clause shall, however, not be applicable for routine inspections/lubrications. The time for regular inspection/lubrication is limited to 30 minutes for each shift.
- d. Payment towards rig repair day rate shall be 60% of the operating day rate.

6.0 FISHING DAY RATES (Per 24 Hrs. day)

- a) These rates are applicable in the event of Contractor fishing / dropping any tool/tubing/tubular/fish during the operation. This includes fishing due to mud cut/metallurgical problem of contractor's tools / tubulars. However, if fish occurs at the tubulars or BHA of OIL not attributable to the Contractor, fishing day rate shall not be applicable during the fishing period. Operating Day Rate shall be payable.
- b) During the restoration/fishing jobs through work-over rig following day rates shall be applicable:
- i) For 1st 15(fifteen) days 50% of OC
- ii) For the 16th to 30th day 25% of OC
- iii) From 31st day till completing/suspending fishing job- Zero rate

7.0 **INTER LOCATION MOVE RATE**:

a) Depending on the distance between the locations, separate rates will be applicable as mentioned below:

i) Fixed Charge (Lump sum) per rig move up to 50 KM	(LA)
ii) Kilometerage charges for rig movement in excess of 50 KM. This will be in addition to lump sum rate for ILM up to 50 KM as mentioned in 'b' above	(LB)
iii) Fixed Charge (Lump sum) for Cluster location. The spacing between wells at surface in cluster well plinth is around 15m or more	(LC)

b) Inter location movement operation will start from the moment the Company releases the Work-over Rig unit for rig down at previous location. Rig & all materials including the additional and optional items, if any, are to be transferred after rig down and rig up at the next location is completed and the well is ready for killing after preparation of killing fluid. The inter-location movement of Rig package should be completed within the period as specified under special terms and conditions.

- c) The Inter location movement operation will include the clearing of the Work-over location off all materials, rig parts and made free from all pollutants.
- d) No day rate under Para 3.0, 4.0, 5.0, 6.0 & 8.0 hereof will be payable when inter-location move rate is applicable. However, if ILM needs to be suspended by Company due to reasons not attributable to Contractor, 'Standby Day Rate' shall be payable to Contractor for this suspended period. For suspension of ILM, Company shall issue notice to Contractor and also shall advise for resumption of ILM.

8.0 FORCE MAJEURE DAY RATE (Per 24 Hrs. day) (50% of OC)

- a. The Force Majeure Day Rate shall be payable during the first 15 days period of force majeure. No payment shall accrue to the Contractor beyond the first 15 days period unless mutually agreed upon.
- b. Payment towards force majeure day rate shall be 50% of operating day rate.
- 9.0 **ZERO RATE & PENALTY**: 'Zero Rate' shall be applicable including but not limited to following situation:
 - (i) The Contractor shall have to bear the responsibility for their employment matters and any problem in this regard inclusive of employment of local people and other issues pertaining to the Contractor's . In case there is any disruption of work at the well site under such conditions as stated above, the Contractor shall be paid at "Zero" rate during the affected period. All environmental issues arising out of Contractors internal matters shall have to be resolved by Contractor within 72 Hrs. During this period "Zero rate" shall be applicable. Beyond 72 Hrs, penalty shall be levied on Contractor at the rate of 50% of Operating day rate per 24 Hrs and at Pro-rata basis in addition to the zero rate
 - (ii) Contractor shall be paid zero rates if operation is suspended for non availability of key personnel.
 - (iii) Proper Check-up/ maintenance/ lubrication equipments and machineries maintenance schedule and procedure are the essence of the contract. Zero rates shall be applicable for entire period of shut down if cause of break down is attributed to Contractor's negligence and deficiency beyond the allowable 'Rig repair' period.
 - (iv) 'Zero Rate' shall be applicable during the fishing period, if 'FISH' occurs due to negligence of the Contractor's personnel. Zero rates shall be applicable from the time of occurrence of 'FISH' till resumption of normal operation after fish recovery or till decision to abandon the well.

10.0 CHARGES FOR CATERING SERVICES:

Contractor shall provide catering services to Company's personnel and to various Service Providers of OIL as and when required on chargeable basis. Payment against the catering services shall be made at the rate of Rs. 400.00 (Rupees Four Hundred only) per person per day with following details:

- (i) Breakfast: Rs. 60.00 per day per person.
- (ii) Lunch: Rs. 150.00 per day per person.
- (iii) Evening tea/snacks : Rs. 40.00 per day per person.
- (iv) Dinner : Rs. 150.00 per day per person.

Following minimum items shall have to be included in the catering services:

- (i) Breakfast: Bread/butter/Egg OR puri sabji OR equivalent with milk/tea
- (ii) Lunch: Rice/Roti, quality dal and sabji, One non-veg item OR Veg special, pickle. Papad etc.
- (iii) Evening tea/snacks: Quality snacks like pakoda/veg chops etc. with Tea.
- (iv) Dinner: Rice/Roti, quality dal and sabji, One non-veg item OR Veg special, pickle, Papad etc.

Food arrangement for Company's personnel and to other Service Providers of OIL shall be arranged by the Contractor with prior intimation only.

END OF SECTION - IV

EQUIPMENT AND SERVICES TO BE FURNISHED BY CONTRACTOR OR COMPANY (OIL) FOR TWO/FOUR WORK OVER RIGS

The equipment machinery, tools, materials supplies, instruments, services and labour, including but not limited to those listed at the following terms shall be provided at the location by OIL or Contractor and the expenses of OIL or Contractor as designated hereunder by 'X' mark in the appropriate column:

S1. No.	ITEM	At Expense of		Supplied by	
1101		Contract or	OIL	Contract or	OIL
I.	EQUIPMENT:				
1.	Work over Unit complete with safety, hoisting, rotating & maintenance equipment according to international practice	Х		Х	
2.	BOP, its attachments & spares	X		X	
3.	Choke & kill unit & connections	X		X	
4	All Substitute	X		X	
5.	All Fishing tools as listed & their spares	X		X	
6.	a) Handling Tools for Drill pipe, tubing Drill collar, and other tubular (Elevators, Slips etc.)	Х		Х	
7.	Welding machine for normal operation with requisite electrodes	X		X	
8	Base/ Well site camp complete in all respect i.e. furniture / fixture etc.	X		Х	
9.	Well Logging Unit & Tools & Services for Logging Operations		X		X
10	Safety equipment including fire fighting equipment	X		X	
11.	Shut in valves	X		X	
12.	a) Crane for all work over & other operations.	X		Х	
	b) Sufficient number of vehicles for inter-location movement	X		X	
	c) Trailer with articulated tractor	X		X	
	d) 40 Ton crane	X		X	
	e) Truck to lift chemicals	X	X	X	\mathbf{X}
	f) Vehicles to lift bits	X		X	
	g) Vehicle to lift casing, tubing, well head etc.	X		X	
13	Equipment required for supplying water as per contract specification at work over site and camp	Х		Х	
14	Equipment required for generating electricity at the site, camp	X		X	
15	Rig lighting	X		X	

S1. No.	ITEM	At Expense of		Supplied by	
210.		Contract	OIL	Contract	OIL
16.	Lines / Chicksan / Fittings	X		X	
17.	Mud making/loading facilities at well site complete with reciprocating / centrifugal	X		Х	
	pumps, prime movers, hoppers tankages etc.				
18.	Tankages inclusive of acid and water storage tanks	Х		Х	
19.	Potable/drinking water, permanent provision at well site & camp	X		X	
20.	BOP control unit	X		X	
21	Well control accessories	X		X	
22.	Drill pipe, drill collar	X		X	
23.	Crossover substitutes of all sizes	X		X	
24.	Kelly	X		X	
25.	All sizes & capacity of elevators, slips, tongs, clamps, (manual & hydraulic)	X		Х	
26.	Elevator links	X		X	
27.	Air winch (s)	X		X	
28	Junk subs, impression blocks etc.	X		X	
29.	All sizes of casing scrapper	X		X	
30.	Tubing Circulating heads	X		X	
31.	Rig warehouse	X		X	
32.	Complete sets of tools and wrenches	X		X	
33.	Flow nipple and flow branch	X		X	
34.	Hydraulic power tubing tong	X		X	
35.	Tubing spinner	X		X	
36.	Store house	X		X	
37.	All rig instruments as per OMR 1984 & Recorder	X		X	
38.	Mud motors and spares	X		X	
39.	Fishing equipment & spares other than those mentioned in section –II (TOR)		X		
40.	Air, water electricity, fuel (HSD) and all lubricants	Х		Х	
41.	Accommodation for contractor personnel	X		X	
42.	Communication equipment as mentioned in the contract	X		X	
43.	Equipment and services not heretofore designated but required by contractor for normal operations	Х		Х	
44.	Equipment not heretofore designated but necessary to fulfil OIL's instruction		X		X
II.	CONSUMABLES:				
1.	Fuel for Work over Rig, all vehicles & entire Contractor's equipment including camp	X		X	
2.	Grease, Lube oil, Cleaning solvent & for all Contractor's equipment including accumulator charging gases (also for OIL's	Х		Х	

S1.	ITEM	At Expense		At Expense of Supplied	
		Contract	OIL	Contract or	OIL
	designated equipment on reimbursement basis)				
3.	Tubing thread lubricant & locking compound	Х		X	
4.	Mud chemicals and mud additives		X		X
5.	Salt & Chemicals for preparation of brine		X		X
0.	water during production testing				
6.	Welding consumables	Х		X	
7.	All BOP consumables including ring joint	X		X	
	gaskets				
8.	Spares for work over rig and accessories	X		X	
9.	Regular replacement of	Х		х	
- •	consumables of Contractor's equipment.				
10.	Maintaining adequate stock of	Х		X	
	consumables				
11.	Mud motor spares	X		X	
12	Fishing equipment, spares as per contract	X		X	
13	Replacement of Contractor's transport	X		X	
	fleet as and when necessary				
14	Fuel Lube oil and spares for transport	X		X	
	fleet as and when required				
15.	First Aid & medicine	X		X	
16.	Food	X		X	
17.	Materials required for up-keepment of	X		X	
	health and hygiene				
18.	i) Materials required for control of		X		X
	pollution	X		X	
	ii) Materials required for control of sound				
	/ noise pollution				
19.	Civil Engineering materials for				
	a) Camp maintenance	X		X	
	, -		X		\mathbf{X}
	b) Well site plinth maintenance				
20.	Replacement of electrical fittings as	X		X	
	& when necessary				
21.	Spares & consumables for	X		X	
	communication equipment				
22.	Replacement, spares & consumables	X		X	
	for fire- fighting equipments				
23.	Painting of mast & substructure as and	X		X	
	when necessary as per colour coding to be				
0.4	informed by OIL				
24.	All sizes of bits as and when necessary		X		X
25.	All sizes of mill	X		X	
26.	All kinds of chemical as and when		X		X
	necessary				
27.	Consumables not heretofore	X		X	
	designated but required by Contractor in				
	normal operation or				
	needed for the maintenance of				

S1. No.	ITEM	At Expense of		Supplied by	
110.		Contract or	OIL	Contract	OIL
	Contractor's equipment				
28.	Consumables not heretofore spelt out but necessary to fulfill OIL's instructions		X		X
29	Water for operation at well site	X		X	
30	Supply of LDO / LWC for mud preparation		X		X
III.	SERVICE AND PERSONNEL				
1.	Transportation of OIL's equipment & consumables attached to the rig	X		X	
2.	Handling (loading & unloading) and storage of OIL's, Contractor's & subcontractor's materials at work over well site	X		X	
3.	Transportation of entire Work over with accessories between locations (interlocation move)	Х		Х	
4.	Inter-location movement of Company's equipment attached with the rig	Х		Х	
5.	Transportation of personnel				
	a) Of OIL (Based at camp)		X		X
	b) Of Contractor	X		X	
6.	Collection of bits, light consumables and transportation of same including handling to well site.	X		X	
7.	a) Site preparation (levelling, base, waster pits, cellar pit, access roads according to the general lay out requirements of Contractor ingress and egress)		X		X
	b. Maintenance of well site plinth & well site approach road		X		X
	c) Store facility for bit and chemicals and other consumable at				
	i) Well site	X		X	
	ii) At Intermediate site	X		X	
	d) Erection and dismantling of Panel fencing at well site		X	X	
8.	Communication system (as specified in the IFB)	X		х	
9.	Cementing & cementing Services		X		X
10.	Water for drilling cementing and production testing	X		Х	
11.	Mud services facilities	X		X	
12.	Well head, control systems and their installation	X		X	
13.	Tripping of tubular	X		X	
14.	Medical facilities at well site	X	77	Х	77
15.	Furnish adequate roadway to location and the right of way		X		X

S1. No.	ITEM	At Expense of		of Supplied by	
NO.		Contract	OIL	Contract	OIL
16	Well head installation (BOP, Production and other equipments)	X		X	
17.	Welding materials & welding operations	X		X	
18	All personnel & supervision necessary to operate the Work over unit, including personnel necessary to handle all normal operations on work over wells	Х		х	
19	Food and lodging of Contractor's personnel (including 3rd party)	X		X	
20	Work Over operation as per OISD - 182	X		X	
20.	BOP testing services	X		X	
21.	Maintenance of Contractor's equipment.	X		X	
22.	Well killing services	X		X	
23	Fishing services	X		X	
24.	Production testing services (wellhead fitting/equipment shall be provided by OIL & well site services shall be provided by Contractor).	X	X		X
25	Effluent water disposal services		X		X
26	All Drilling services in line with good oil field practice	X		X	
27.	a. Pollution control services b. Sound pollution	x	X	x	X
28.	Computation and record keeping services	X		X	
29.	Mud motor services	X		X	
30.	Catering services	X		X	
31.	Medical Services	X		X	
32	Ambulance services	X		X	
33.	Fire fighting services	X		X	
34	Services of Personnel	X		X	
35	Various work sheet drawing, calculation dimensions as mentioned	Х		X	
36.	Services not heretofore designated but required by Contractor in normal operations or needed to maintain & operate Contractor's equipment	Х		х	
37.	Services not heretofore designated but required due to directions of the Company (OIL).		X	X(dependi ng upon the type of job)	X
38	All expenditure for Contractor's persons including inward and outward journey from well site	Х		X	

PROFORMA FOR BIO DATA OF KEY PERSONNEL

1. NAME

AFFIX PASSPORT SIZE PHOTOGRAPH

- 2. PRESENT ADDRESS
- 3. PERMANENT ADDRESS
- 4. FATHER'S NAME
- 5. NATIONALITY
- 6. PASSPORT NO.
 AND VALIDITY (IN
 CASE OF
 EXPATRIATE)
- 7. DESIGNATED POST
- 8. EDUCATIONAL QUALIFICATION
- 9. DATE OF BIRTH
- 10. EXPERIENCE IN REVERSE ORDER

NOTE: In case of replacement of the key personnel, the replacement personnel must have the requisite qualification and experience as per Terms of Reference (Section-II) and shall submit their credentials along with their recent photographs to Company for approval of Company.

$\frac{\textbf{DETAILS OF ELECTRICAL MACHINE USED IN WORKOVER}}{\textbf{RIG}}$

S1. No.	Name of Equipment/ Motor	Make	Maker's Sl. No.	Туре	DGMS Approval No.	Distance from Well head	Gas Group
					_		

ANNEXURE - IV

Details of all cables, light fittings, push button stations, plug & sockets, junction boxes, Motors, Starters etc. to be used in the offered rig

Sl. No.	Description	Make	Туре	DGMS/CMRI Approval	Gas Group

PROFORMA UNDERTAKING FROM CONTRACTORS PERSONNEL

I,	_ S/o		
having permanent residence at	S/o Dist as their employee. Now, I have been		
am working with M/s	as their employee. Now, I have been		
transferred by M/s	for carrying out the contract job under		
	which has been awarded in favour of my		
employer M/s	·		
	y claim for employment or any service benefit carrying out contract job in OIL by M/s.		
I am an employee of	for all practical act between OIL and me.		
Place:			
Date:			
SIGNATURE:			
NAME:			
DESIGNATION:			
DATE:			

To be Notarized

(Scanned copy to be uploaded along with technical bid e-tender portal & original to e submitted at the office of GM-Contracts)

TO **CGM- CONTRACTS**Oil India Ltd.,
P.O. Duliajan - 786602
Assam, India

Sub: OIL's Tender No. CDH5424L21

Undertaking of the offered Workover Rig(s) - Charter Hire of 550HP (Min.) - 750 HP (Max.) Capacity Workover Rig package under the subject Tender

Sir,		
	We M/s	do hereby confirm and declare the following:
1.0	Ç ,	te) / 02(Two) Rigs as available with us. The Rigs offered by us
are r	registered with the trans	sport Authorities with Registration No. as
&	(.	As applicable).
2.0	The Rig(s) offered by	us under the subject tender is readily available with us and
do h	ereby confirm to mobili	ze the offered Rigs within 60 days from the date of issue of
Lette	er of Award by OIL IND	A. In case of any delay or default on the mobilization of the
Rigs,	, we will be liable to pay	the Liquidated Damages as per T & C of the Tender.
3.0	The Rigs offered by us	s are less than 15 Years old vintage with date of Manufacture
	&	(as applicable) and we also hereby
		ports of the Rig prior to Mobilization of the Rigs.
4.0	The Rig(s) offered by	us under the subject tender is free of encumbrance and not
unde	er any litigation in India	or abroad.
5.0	We do hereby commit	to offer all the required services with Manpower & equipment
as sp	pelt out in the Technica	Scope of Work.
6.0	We do hereby accept t	hat OIL INDIA LTD. reserves the right to verify the documents

pertaining to the Rig(s) prior to Mobilization if called for.

- 7.0 We do hereby confirm that all the items required for one no. of Rig (as per the tender specification) will be provided by us in the event of order (if quoted for one no. of rig).
- 8.0 We do hereby confirm that we comply the financial criteria as per Clause No. A.2.0 of the BEC/BRC.

We hereby declare that the above declaration is true to the best of our Knowledge.

Yours Faithfully,

Authorised Signatory:	
Name: Designation:	
Seal of the Bidder:	

Note:

• This letter of authority shall be printed on the letterhead of the Bidder and shall be signed by a person competent and having the power of attorney (power of attorney shall be annexed) to bind such Bidder.

ANNEXURE-VII

CERTIFICATE OF ANNUAL TURNOVER, NET WORTH & WORKING CAPITAL

TO BE ISSUED BY PRA HEAD	CTISING CHARTERED	ACCOUNTANTS' F	IRM ON THEIR LETTER		
This is to certify that the following financial positions extracted from the audited financial statements of M/s(Name of the Bidder) for the last three (3) completed accounting years uptoare correct.					
YEAR	TURN OVER (in INR)	NET WORTH (in INR)	WORKING CAPITAL (in INR)		
		_			
Place: Date: Seal:					
Membership Code: Registration No. : Signature					

ANNEXURE-VIII

DECLARATION BY BIDDER REGARDING CONCURRENT COMMITMENT

I/We			age	son of	do	
hereb	y solemnly aff	irm and decl	are as fo	llows for and on	behalf of the Firm:	
LIST	OF EXISTING	COMMITMEN	NT AND C	ONGOING WORKS	3	
No. of Works Name & Order Value (INR) No. of Works Name & Order Value (INR) Value (INR) No. of Works Name & Order Submission of for executing the period of expiry of validity (INR) No. of Works Name & Order Value (INR) No. of Works Name & Order Value (INR) No. of Works No. of Works No. of Works No. of Work which submission of for executing the period of expiry of validity (INR)				work which may fall for execution during the period of 12 months from the date of expiry of the bid validity		
1	2	3	4	5	6	
	Balance commitments in 12 months from the date (INR) of expiry of the bid validity					
It is certified that the above particulars furnished are true and correct. If any information given is found to be misleading at a later date OIL will have the authority to take necessary action as per provision of the Contract and as per laid down procedure of the Company (OIL).						
	AND STAMP RNEY)	OF BIDDER	(AUTHOR	RISED SIGNATOR	Y HAVING POWER OF	

Note: Accuracy level of balance commitments as per total of column 6 above should be within +/- 10%

LIST OF ITEMS (Equipment, Tools, Accessories, Spares & consumable) TO BE IMPORTED IN CONNECTION WITH EXECUTION OF THE CONTRACT SHOWING CIF VALUE

Srl #	Item Descripti on	Qty/ Unit	Rate	Total	Freight & Insurance	CIF Value	Port & other charge	Landed Cost	Is it re- exportable ? YES or NO	Year of Mfg.	HSN Code
A	В	С	D	E = C x D	F	G = F + E	Н	I = G+H	J	К	L
										•	

- (1) The items which are not of consumable in nature and required to be reexported outside India after completion of the Contract should be indicated as "YES" in column "J".
- (2) The items, which are of consumable in nature should be indicated as "NO" in column "J".
- (3) For estimation of applicable customs duty, the bidders are required to indicate customs tariff code (i.e. HSN Code) of each item in column "L".

Authorised Person's Signature:	
Name:	-

Seal of the Bidder:

PROFORMA-B

PRICED BID FORMAT

THE PRICE BID FORMAT IS ATTACHED UNDER "NOTES AND ATTACHMENTS"
TAB OF THE E-TENDER PORTAL

BID FORM

To M/s. Oil India Limited, P.O. Duliajan, Assam, India

Sub: IFB No. CDH5424L21

<u> </u>	1	1		
Ger	1.T.I	en	ne.	n.,

Seal of the Bidder:

Gentlemen,
Having examined the General and Special Conditions of Contract and the Terms of Reference including all attachments thereto, the receipt of which is hereby duly acknowledged, we the undersigned offer to perform the services in conformity with the said conditions of Contract and Terms of Reference for the sum of (Total Bid Amount in words and figures) or such other sums as may be ascertained in accordance with the Schedule of Prices attached herewith and made part of this Bid.
We undertake, if our Bid is accepted, to commence the work within () days calculated from the date issue of LOA.
If our Bid is accepted, we will obtain the guarantee of a bank in a sum not exceeding for the due performance of the Contract.
We agree to abide by this Bid for a period of 120 days from the date fixed for Bid closing and it shall remain binding upon us and may be accepted at any time before the expiration of that period.
Until a formal Contract is prepared and executed, this Bid, together with your written acceptance thereof in your notification of award shall constitute a binding Contract between us.
We understand that you are not bound to accept the lowest or any Bid you may receive.
Dated this day of 2020.
Authorised Person's Signature:
Name:
Designation:

STATEMENT OF NON-COMPLIANCE (Only exceptions/deviations to be rendered)

1.0 The Bidder shall furnish detailed statement of **exceptions/deviations**, if any, to the tender stipulations, terms and conditions in respect of each Section of Bid Document in the following format:

Section No.	Clause No. (Page No.)	Non-Compliance	Remarks

Authorised Person's Signature:	
Name:	
Designation:	
Seal of the Bidder:	

NOTE: OIL INDIA LIMITED expects the bidders to fully accept the terms and conditions of the bid document. However, should the bidders still envisage some exceptions/deviations to the terms and conditions of the bid document, the same should be indicated as per above format and submit along with their bids. If the "**Statement of Non-Compliance**" in the above Proforma is left blank (or not submitted along with the technical bid), then it would be construed that the bidder has not taken any exception/deviation to the tender requirements.

FORM OF BID SECURITY (BANK GUARANTEE)

To:	
M/s. OIL INDIA LIMITED,	
CONTRACTS DEPARTMENT,	
DULIAJAN, ASSAM, INDIA, PIN-	786 602.

WHEREAS, (Name of Bidder)	(hereinafter called "the Bidder")
has submitted their offer Dated for the provi	ision of certain services (hereinafter
called "the Bid") against OIL INDIA LIMITED, Duliajar	n, Assam, India (hereinafter called the
Company)'s Tender NoKNOW ALL MEN	•
Bank) of (Name of Country)	-
(hereinafter called "Bank") are boun	
· · · · · · · · · · · · · · · · · · ·	to be made to Company, the Bank
binds itself, its successors and assignees by these pre-	
pro-	

SEALED with the said Bank this day of 20

THE CONDITIONS of these obligations are:

- 1. If the Bidder withdraws their Bid within its original/extended validity; or
- 2. The Bidder modifies/revises their bid suomoto; or
- 3. The Bidder does not accept the contract; or
- 4. The Bidder does not furnish Performance Security Deposit within the stipulated time as per tender/contract; or
- 5. If it is established that the Bidder has submitted fraudulent documents or has indulged into corrupt and fraudulent practice.

We undertake to pay to Company up to the above amount upon receipt of its first written demand (by way of letter/fax/cable), without Company having to substantiate its demand provided that in its demand Company will note that the amount claimed by it is due to it owing to the occurrence of any of the conditions, specifying the occurred condition or conditions.

This guarantee will remain in force up to and including the date (**) and any demand in respect thereof should reach the Bank not later than the above date.

The details of the Issuing Bank and Controlling Bank are as under:

A. Issuing Bank:

BANK FAX NO:

BANK EMAIL ID:

BANK TELEPHONE NO .:

IFSC CODE OF THE BANK:

B. Controlling Office:

Address of the Controlling Office of the BG issuing Bank:

Name of the Contact Person at the Controlling Office with Mobile No. and e-mail address:

SIGNATURE AND SEAL OF THE GUARANTORS
Name of Bank & Address
Witness Address
(Signature, Name and Address) Date: Place: * The Bidder should insert the amount of the guarantee in words and figures. ** Date of expiry of Bank Guarantee should be as specified in the tender document.
Note:
The Bank Guarantee issuing bank branch must ensure the following:
(a) The Bank Guarantee issued by the bank must be routed through SFMS platform as per the following details:
i) "MT 760 / MT 760 COV" for issuance of bank guarantee.
ii) "MT 760 / MT 767 COV" for amendment of bank guarantee.
The above message/intimation indicating the Tender No. CDH5424L21shall be sent through SFMS by the BG issuing bank branch to HDFC Bank, Duliajan Branch; IFS Code – HDFC0002118; SWIFT Code – HDFCINBBCAL; Branch Address: HDFC Bank Limited, Duliajan Branch, Utopia Complex, BOC Gate, Jayanagar, Duliajan, Dibrugarh, PIN – 786602.
(b) Bank Guarantee issued by a Scheduled Bank in India at the request of some other

(c) Further correspondence against BG towards Bid Security must contain the Tender Number.

FORM OF PERFORMANCE BANK GUARANTEE

CONT	OIL INDIA LIMITED, RACTS DEPARTMENT AJAN, ASSAM, INDIA, PIN - 786 602.
(herei	REAS
furnis	WHEREAS it has been stipulated by you in the said Contract that the Contractor shall h you with a Bank Guarantee as security for compliance with Contractor's obligations ordance with the Contract.
THER a to curren your f limits or rea	WHEREAS we have agreed to give the Contractor such a Bank Guarantee; NOW EFORE we hereby affirm that we are Guarantors on behalf of the Contractor, up to otal of (Amount of Guarantee in figures) (in words), such amount being payable in the types and proportions of notices in which the Contract price is payable, and we undertake to pay you, upon first written demand and without cavil or argument, any sum or sums within the of guarantee sum as aforesaid without your needing to prove or to show grounds asons for your demand for the sum specified therein. We hereby waive the necessity r demanding the said debt from the Contractor before presenting us with the demand.
Contr which liabili	further agree that no change or addition to or other modification of the terms of the act or the work to be performed thereunder or of any of the Contract documents may be made between you and the Contractor shall in any way cease us from any ty under this guarantee, and we hereby waive notice of such change, addition or ication.
This g	guarantee is valid until theday of
The d	etails of the Issuing Bank and Controlling Bank are as under:
A.	Issuing Bank: BANK FAX NO: BANK EMAIL ID: BANK TELEPHONE NO.: IFSC CODE OF THE BANK:
В.	Controlling Office: Address of the Controlling Office of the BG issuing Bank: Name of the Contact Person at the Controlling Office with Mobile No. and email address:

SIGNATURE AND SEAL OF THE GUARANT	TORS
Designation:	
Name of Bank:	
Address:	
Witness:	
Address:	
Date:	
Place:	

Note:

The Bank Guarantee issuing bank branch must ensure the following:

- (a) The Bank Guarantee issued by the bank must be routed through SFMS platform as per the following details:
 - i) "MT 760 / MT 760 COV for issuance of bank guarantee.
 - ii) "MT 760 / MT 767 COV for amendment of bank guarantee.

The above message/intimation indicating the Contract No.-----shall be sent through SFMS by the BG issuing bank branch to HDFC Bank, Duliajan Branch; IFS Code – HDFC0002118; SWIFT Code – HDFCINBBCAL; Branch Address: HDFC Bank Limited, Duliajan Branch, Utopia Complex, BOC Gate, Jayanagar, Duliajan, Dibrugarh, PIN – 786602.

- (b) Bank Guarantee issued by a Scheduled Bank in India at the request of some other Non-Scheduled Bank of India shall not be acceptable.
- (c) Further correspondence against BG towards Performance Security must contain the Contract Number.

AGREEMENT FORM

This Agreement is made on day of between Oil India Limited, a Government of India Enterprise, incorporated under the Companies Act 1956, having its registered office at Duliajan in the State of Assam, hereinafter called the "Company" which expression unless repugnant to the context shall include executors, administrators and assignees on the one part, and M/s (Name and address of Contractor) hereinafter called the "Contractor" which expression unless repugnant to the context shall include executors, administrators and assignees on the other part,
WHEREAS the Company desires that Services (brief description of services) should be provided by the Contractor as detailed hereinafter or as Company may requires;
WHEREAS, Contractor engaged themselves in the business of offering such services represents that they have adequate resources and equipment, material etc. in good working order and fully trained personnel capable of efficiently undertaking the operations and is ready, willing and able to carry out the said services for the Company as per Section-II attached herewith for this purpose; and
WHEREAS, Company had issued a firm Letter of Award No dated based on Offer No dated submitted by the Contractor against Company's IFB No. CDH5424L21 .
WHEREAS, Contractor accepted the above Letter of Award vide and submitted Performance Bank Guarantee No Dated valid till issued by(Bank's name with detailed address) for an amount of All these aforesaid documents shall be deemed to form and be read and construed as part of this agreement/contract. However, should there be any dispute arising out of interpretation of this contract in regard to the terms and conditions with those mentioned in Company's tender document and subsequent letters including the Letter of Intent and Contractor's offer and their subsequent letters, the terms and conditions attached hereto shall prevail. Changes, additions or deletions to the terms of the contract shall be authorized solely by an amendment to the contract executed in the same manner as this contract.
NOW WHEREAS, in consideration of the mutual covenants and agreements hereinafter contained, it is hereby agreed as follows -
1. In this Agreement words and expressions shall have the same meanings as are respectively assigned to them in the Conditions of Contract referred to.
2. In addition to documents herein above, the following Sections and Annexures attached herewith shall be deemed to form and be read and construed as part of this agreement viz.:
 (a) Section-I indicating the General Conditions of this Contract; (b) Section-II indicating the Terms of Reference; (c) Section-III indicating the Special Conditions of Contract; (d) Section-IV indicating the Schedule of Rates.

- 3. In consideration of the payments to be made by the Company to the Contractor as hereinafter mentioned, the Contractor hereby covenants with the Company to provide the Services and to remedy defects therein in conformity in all respect with the provisions of this Contract.
- 4. The Company hereby covenants to pay the Contractor in consideration of the provision of the Services and the remedying of defects therein, the Contract Price or such other sum as may become payable under the provisions of this Contract at the times and in the manner prescribed by this Contract.

IN WITNESS thereof, each party has executed this contract at Duliajan, Assam as of the date shown above.

Signed, Sealed and Delivered,

For and on behalf of Company (Oil India Limited)	for and on behalf of Contractor (M/s)		
Name:	Name:		
Status:	Status:		
In presence of	In presence of		
1.	1.		
2.	2.		

PROFORMA LETTER OF AUTHORITY

To:
CGM (CONTRACTS)
Oil India Ltd.,
P.O. Duliajan - 786 602
Assam, India
Sir,
Sub: OIL's IFB No. CDH5424L21
We (Name and address) as
authorised to represent us to Bid, negotiate and conclude the agreement on our behalf
with you against Tender Invitation No for hiring of services for
·
We confirm that we shall be bound by all and whatsoever our said representative
shall commit.
Yours Faithfully,
Tours Farmany,
Authorised Person's Signature:
Name:
Designation:
Seal of the Bidder:

Note: This letter of authority shall be on printed letter head of the Bidder and shall be signed by a person competent and having the power of attorney (power of attorney shall be annexed) to bind such Bidder. If signed by a consortium, it shall be signed by members of the consortium.

AUTHORISATION FOR ATTENDING BID OPENING

TO,	Date:		
CGM (CONTRACTS)			
Oil India Ltd.,			
P.O. Duliajan - 786 602			
Assam, India			
Sir,			
Sub: OIL's IFB No. CDF	I5424L21		
We authorise Mr. /Mrsopening of the above IFB due on	(Name and address) to be present at the time of at Duliajan on our behalf.		
Yours Faithfully,			
Authorised Person's Signature:			
Name:			
Designation:			
Seal of the Bidder:			
Note : This letter of authority shall be	e on printed letter head of the Bidder and shall be		

signed by a person who signs the bid.

8888888888

INTEGRITY PACT

Between

Oil India Limited (OIL) hereinafter referred to as "The Principal"

And

(Name of the bidder).....hereinafter referred to as "The Bidder/Contractor"

Preamble:

The Principal intends to award, under laid down organizational procedures, contract/s for **services under Tender No. CDH5424L21.**The Principal values full compliance with all relevant laws and regulations, and the principles of economic use of resources, and of fairness and transparency in its relations with its Bidder/s and Contractor/s.

In order to achieve these goals, the Principal cooperates with the renowned international Non-Governmental Organization "Transparency International" (TI). Following TI's national and international experience, the Principal will appoint an external independent Monitor who will monitor the tender process and the execution of the contract for compliance with the principles mentioned above.

Section: 1 -Commitments of the Principal

- (1) The Principal commits itself to take all measures necessary to prevent corruption and to observe the following principles:
 - 1. No employee of the Principal, personally or through family members, will in connection with the tender for, or the execution of a contract, demand, take a promise for or accept, for him/herself or third person, any material or immaterial benefit which he/she is not legally entitled to.
 - 2. The Principal will, during the tender process treat all Bidders with equity and reason. The Principal will in particular, before and during the tender process, provide to all Bidders the same information and will not provide to any Bidder confidential/additional information through which the Bidder could obtain an advantage in relation to the tender process or the contract execution.
 - 3. The Principal will exclude from the process all known prejudiced persons.
- (2) If the Principal obtains information on the conduct of any of its employees which is a criminal offence under the relevant Anti-Corruption Laws of India, or if there be a Page 2 of 6 substantive suspicions in this regard, the Principal will inform its Vigilance Office and in addition can initiate disciplinary actions.

Section: 2 -Commitments of the Bidder/Contractor

- (1) The Bidder/Contractor commits itself to take all measures necessary to prevent corruption. He commits himself to observe the following principles during his participation in the tender process and during the contract execution.
 - 1. The Bidder/Contractor will not, directly or through any other person or firm, offer, promise or give to any of the Principal's employees involved in the tender process or the execution of the contract or to any third person any material or immaterial benefit which he/she is not legally entitled to, in order to obtain in exchange any advantage of any kind whatsoever during the tender process or during the execution of the contract.
 - 2. The Bidder/Contractor will not enter with other Bidders into any undisclosed agreement or understanding, whether formal or informal. This applies in particular to prices, specifications, certifications, Subsidiary contracts, submission or non-submission of bids or any other actions to restrict competitiveness or to introduce cartelization in the bidding process.
 - 3. The Bidder/Contractor will not commit any offence under the relevant Anticorruption Laws of India; further the Bidder/Contractor will not use improperly, for purposes of competition or personal gain, or pass on to others, any information or document provided by the Principal as part of the business relationship, regarding plans, technical proposals and business details, including information contained or transmitted electronically.
 - 4. The Bidder/Contractor will, when presenting his bid, disclose any and all payments he has made, is committed to or intends to make to agents, brokers or any other intermediaries in connection with the award of the contract.
- **(2)** The Bidder/Contractor will not instigate third persons to commit offences outlined above or be an accessory to such offences.
- (3) The Bidder/Contractor signing Integrity Pact shall not approach the Courts while representing the matters to IEMs and he/she will await their decision in the matter.

Section 3 -Disqualification from tender process and exclusion from future Contracts

If the Bidder, before contract award has committed a transgression through a violation of Section 2 or in any other form such as to put his reliability or risibility as Bidder into question, the Principal is entitled to disqualify the Bidder from the tender process or to terminate the contract, if already signed, for such reason.

- 1. If the Bidder/Contractor has committed a transgression through a violation of Section 2 such as to put his reliability or credibility into question, the Principal is entitled also to exclude the Bidder/Contractor from future contract award processes. The imposition and duration of the exclusion will be determined by the severity of the transgression. The severity will be determined by the circumstances of the case, in particular the number of transgressions, the position of the transgressions within the company hierarchy of the Bidder and the amount of the damage. The exclusion will be imposed for a minimum of 6 months and maximum of 3 years.
- 2. The Bidder accepts and undertakes to respect and uphold the Principal's Absolute right to resort to and impose such exclusion and further accepts and undertakes not to challenge or question such exclusion on any ground, including

the lack of any hearing before the decision to resort to such exclusion is taken. This undertaking is given freely and after obtaining independent legal advice.

- 3. If the Bidder/Contractor can prove that he has restored/recouped the Damage caused by him and has installed a suitable corruption prevention system, the Principal may revoke the exclusion prematurely.
- 4. A transgression is considered to have occurred if in light of available evidence, no reasonable doubt is possible.
- 5. Integrity Pact, in respect of a particular contract, shall be operative from the date Integrity Pact is signed by both the parties till the final completion of the contract **or as mentioned in Section 9- Pact Duration whichever is later**. Any violation of the same would entail disqualification of the bidders and exclusion from future business dealings

Section 4 -Compensation for Damages

- 1. If the Principal has disqualified the Bidder from the tender process prior to the award according to Section 3, the Principal is entitled to demand and recover from the Bidder liquidated damages equivalent to Earnest Money Deposit / Bid Security.
- (2) If the Principal has terminated the contract according to Section 3, or if the Principal is entitled to terminate the contract according to Section 3, the principal shall be entitled to demand and recover from the Contractor liquidated damages equivalent to Security Deposit / Performance Bank Guarantee.
- 3. The bidder agrees and undertakes to pay the said amounts without protest or demur subject only to condition that if the Bidder/Contractor can prove and establish that the exclusion of the Bidder from the tender process or the termination of the contract after the contract award has caused no damage or less damage than the amount or the liquidated damages, the Bidder/Contractor shall compensate the Principal only to the extent of the damage in the amount proved.

Section 5 -Previous transgression

- 1. The Bidder declares that no previous transgression occurred in the last 3 years with any other Company in any country conforming to the TI approach or with any other Public Sector Enterprise in India that could justify his exclusion from the tender process.
- 2. If the Bidder makes incorrect statement on this subject, he can be disqualified from the tender process or the contract, if already awarded, can be terminated for such reason.

Section: 6 -Equal treatment of all Bidders/Contractor/Subcontractors

- 1. The Principal will enter into Pacts on identical terms with all bidders and contractors.
- 2. The Bidder / Contractor undertake(s) to procure from all subcontractors a commitment in conformity with this Integrity Pact. The Bidder/Contractor shall be responsible for any violation(s) of the provisions laid down in this agreement/Pact by any of its subcontractors/sub-vendors.

3. The Principal will disqualify from the tender process all bidders who do not sign this Pact or violate its provisions.

Section: 7 - Criminal charges against violating Bidders/Contractors/ Subcontractors

If the Principal obtains knowledge of conduct of a Bidder, Contractor or Subcontractor, or of an employee or a representative or an associate of a Bidder, Contractor or Subcontractor, which constitutes corruption, or if the Principal has substantive suspicion in this regard, the Principal will inform the Vigilance Office.

Section: 8 -External Independent Monitor/Monitors

- 1. The Principal appoints competent and credible external independent Monitor for this Pact. The task of the Monitor is to review independently and objectively, whether and to what extent the parties comply with the obligations under this agreement.
- 2. The Monitor is not subject to instructions by the representatives of the parties and performs his functions neutrally and independently. He reports to the Chairperson of the Board of the Principal.
- 3. The Contractor accepts that the Monitor has the right to access without restriction to all Project documentation of the Principal including that provided by the Contractor. The Contractor will also grant the Monitor, upon his request and demonstration of a valid interest, unrestricted and unconditional access to his project documentation. The same is applicable to Subcontractors. The Monitor is under contractual obligation to treat the information and documents of the Bidder/Contractor/Subcontractor with confidentiality.
- 4. The Principal will provide to the Monitor sufficient information about all meetings among the parties related to the Project provided such meetings could have an impact on the contractual relations between the Principal and the Contractor. The parties offer to the Monitor the option to participate in such meetings.
- 5. As soon as the Monitor notices, or believes to notice, a violation of this agreement, he will so inform the Management of the Principal and request the Management to discontinue or heal the violation, or to take other relevant action. The monitor can in this regard submit non-binding recommendations. Beyond this, the Monitor has no right to demand from the parties that they act in a specific manner, refrain from action or tolerate action. However, the Independent External Monitor shall give an opportunity to the bidder / contractor to present its case before making its recommendations to the Principal.
- 6. The Monitor will submit a written report to the Chairperson of the Board of the Principal within 8 to 10 weeks from the date of reference or intimation to him by the 'Principal' and, should the occasion arise, submit proposals for correcting problematic situations.
- 7. If the Monitor has reported to the Chairperson of the Board a Substantiated suspicion of an offence under relevant Anti-Corruption Laws of India, and the Chairperson has not, within reasonable time, taken visible action to proceed against such offence or reported it to the Vigilance Office, the Monitor may also transmit this information directly to the Central Vigilance Commissioner, Government of India.
- 8. The word 'Monitor' would include both singular and plural.

Section: 9 - Pact Duration

This Pact begins when both parties have legally signed it. It expires for the Contractor 12 months after the last payment under the respective contract, and for all other Bidders 6 months after the contract has been awarded.

If any claim is made/ lodged during this time, the same shall be binding and continue to be valid despite the lapse of this pact as specified above, unless it is discharged/determined by Chairperson of the Principal.

Section: 10 -Other provisions

- 1. This agreement is subject to Indian Law. Place of performance and jurisdiction is the Registered Office of the Principal, i.e. New Delhi. The Arbitration clause provided in the main tender document / contract shall not be applicable for any issue / dispute arising under Integrity Pact.
- 2. Changes and supplements as well as termination notices need to be made in writing. Side agreements have not been made.
- 3. If the Contractor is a partnership or a consortium, this agreement must be, signed by all partners or consortium members.
- 4. Should one or several provisions of this agreement turn out to be invalid, the remainder of this agreement remains valid. In this case, the parties will strive to come to an agreement to their original intensions.

For the Principal	For the Bidder/Contractor	
Place: Duliajan	Witness1:	
Date:2020	Witness 2:	

(Note: Uploading in the OIL's E-portal with digital signature will be construed that the same has been signed by the bidder's authorized signatory who has signed the bid).

88888

To CGM-CONTRACTS OIL INDIA LIMITED DULIAJAN-786602

SUB: SAFETY MEASURES FOR TENDER NO. CDH5424L21

DESCRIPTION OF WORK/ SERVICE:

	•		
	-		
. ¬			

We hereby confirm that we have fully understood the safety measures to be adopted during execution of the above contract and that the same have been explained to us by the concerned authorities. We also give the following assurances.

- a) Only experienced and competent persons shall be engaged by us for carrying out work under the said contract.
- b) The names of the authorised persons who would be supervising the jobs on day to day basis from our end are the following:

i) _	
ii) .	
iii)	

The above personnel are fully familiar with the nature of jobs assigned and safety precautions required.

- c) Due notice would be given for any change of personnel under item(b) above.
- d) We hereby accept the responsibility for the safety of all the personnel engaged by us and for the safety of the Company's personnel and property involved during the course of our working under this contract. We would ensure that all the provisions under the Oil Mines Regulations, 1984 and other safety rules related to execution of our work would be strictly followed by our personnel. Any violation pointed out by the Company's Engineers would be **rectified forthwith** or the work suspended till such time the rectification is completed by us and all expenditure towards this would be on our account.
- e) We confirm that all persons engaged by us would be provided with the necessary Safety Gears at our cost.
- f) All losses caused due to inadequate safety measures or lack of supervision on our part would be fully compensated by us and the Company will not be responsible for any lapses on our part in this regard.

(Seal)	
Date	Yours Faithfully
M/s	

FOR & ON BEHALF OF CONTRACTOR

ON THE OFFICIAL PAD OF THE BIDDER TO BE EXECUTED BY THE AUTHORIZED SIGNATORY OF THE BIDDER

Certificate of Compliance of FINANCIAL CRITERIA:

Ref Clause No. B.2.6 of the BEC of the Tender					
	the authorized signatory(s) ofess) do hereby solemnly affirm and declare / under				
The balance sheet/Financial Sta	atements for the financial year	_ (as			
the case may be) has actually no	t been audited as on the Original Bid Closing I	Date.			
Place:					
Date:	Signature of the authorized signatory	V			

<u>Note:</u> Please note that any declaration having date after the <u>Bid Closing Date</u> will not be considered and will be rejected. This certificate is to be issued only considering the time required for preparation of Financial Statements i.e. if the last date of preceding financial / accounting year falls within the preceding six months reckoned from the original bid closing date.

Format of undertaking by Bidders towards submission of authentic information/documents

(To be typed on the letter head of the bidder)

Ref. No	Date
To, CGM-CONTRACTS OIL INDIA LIMITED DULIAJAN-786602	
Sub: Undertaking of authenticit	y of information/documents submitted
Ref: Your tender No	Dated
Sir,	
With reference to our quotation against y that no fraudulent information/documer	your above-referred tender, we hereby undertakents have been submitted by us.
We take full responsibility for the subagainst the above cited bid.	bmission of authentic information/documents
information/documents submitted by u has right to reject our bid at any stage	ne tender/contract agreement, in case any of the s are found to be false/forged/fraudulent, OIL e including forfeiture of our EMD and/or PBG d/or carry out any other penal action on us, as
Yours faithfully,	
For (type name of the firm here)	
Signature of Authorised Signatory	
Name:	
Designation:	
Phone No.	
Place:	
Date: (Affix Seal of the Organization here, if ap-	nlicable)
mina sear of the Organization here, if ap	piicavicj

COMMERCIAL CHECK LIST

Bidder's Name:_		

TENDER NO. CDH5424L21

This Questionnaire duly filled in should be returned along with each copy of Unpriced Bid. Clauses confirmed hereunder should not be repeated in the Bid.

S1. No.	Description	Bidder's Confirmation
1.	Bidding structure	
2	Bidder's name and address:	
3.	It is noted that deviations to Terms & Conditions shall lead to rejection of offer, as specified in the Tender.	
4.	Ensure and confirm that prices quoted in 'Schedule of Rates', are for complete scope of work as defined in the tender	
5.	Indicate SAC Code Indicate rate of GST applicable.	SAC Code: GST%
6.	EMD Details: EMD No., Issuing bank, amount	

	1	
	with currency and Validity	
7.	Confirm to Submit PBG as per Tender requirement	
8.	Confirm that the offer shall remain valid for acceptance up to hundred and twenty (120) days from final Bid Due Date/Date of opening of bids.	
9.	Whether Mobilization and Completion period of contract is complied?	
10.	Whether Integrity Pact Submitted?	
11.	Confirm that currency of quoted prices: (The same will be finally converted to Indian Rupees for evaluation).	
12.	Confirm that quoted prices shall remain firm and fixed until completion of the contract.	
13.	Confirm that you have submitted all documents as mentioned in the Tender/Annexures	
14.	Confirm acceptance to all terms & conditions of the Tender.	
15.	Confirm that all correspondence must be in English Language only.	
16.	Indicate Name & Contact No. (Telephone/Fax/E-	Name:

	mail) of person signing the bid.	Contact No.: Fax: Email:
17.	Confirm that all Bank charges associated with Bidder's Bank shall be borne by Bidder.	
18.	Please indicate the following: (i) PAN No. (ii) GST Regn. No.	

Bidder confirms that in case of conflicting version of various terms & conditions at different places, the confirmation furnished as above shall be considered over-riding and final and any other deviation indicated elsewhere shall be treated as redundant.

Signature
Name
Designation
Office Stamp

CHECKLIST FOR BEC

Bidders to mark ($\sqrt{}$) Provided or Not Provided along with the Reference File No. and page No. whichever is applicable

Clause No.	Description	Reference File No. and Page No. of Bidder's Quote	Provided	Not Provided
В.	TECHNICAL:			
	Bidder must meet the following minimum criteria failing which offer shall be rejected:			
	This tender is being floated on limited tendering basis to the shortlisted vendors as mentioned herein with a provision for other potential bidders meeting the following BEC Criteria to submit their bids along with all supporting documents.			
	The Bidders to whom this tender has been issued as mentioned in the NIT should only give an undertaking (as per ANNEXURE-VI) towards fulfilment of the Clause Nos. 1.0 to 7.0. However, bidders other than the ones listed in the NIT are required to submit all the requisite supporting documents towards fulfilment of the following clauses, along with their bids. Notwithstanding above, OIL reserves the right to seek clarifications including submission of any or all documents even from the already shortlisted bidders to evaluate and ascertain suitability of their bids.			
1.0	The bidder shall have at least 2(two) years experience of providing Drilling / Work-over services to oil (E&P) Company with charter hired rig in the last 7 years as on the Bid Closing Date (Technical).			
2.0	Financial Criteria			
2.1	The bidder must have minimum annual financial turnover as mentioned below in any of preceding three financial/accounting years reckoned from the original bid closing			

	date as per the	Audited Annual Reports:	
	No. of	Annual Financial]
	Rigs offered	Turnover	
	1 No.	INR 3,96,50,000.00	-
	2 Nos.	INR 7,93,00,000.00	
2.2		dder for the accounting y original bid closing d	
	should be mini	mum:	
	No. of	Net Worth	$\neg \mid$
	Rigs offered		
	1 No.	INR 1,19,00,000.00	$\dashv \parallel$
	2 Nos.	INR 2,38,00,000.00	$\dashv \mid$
			_
	-	all mean: " Share capita ted out of profits a	
	securities Pren	nium – Aggregate value	of
		osses - account (exclud erves) – deferred expendit	_
		s Expenditure to the ext and carried forward Los	
		ed out of write back	
	depreciation an	d amalgamation" .]	
2.3		tal: The Bidder should	
		king capital as mention ecounting year preceding	
	original bid clos		
	No. of	Working Capital	
	Rigs offered		
	1 No.	INR 1,19,00,000.00	
	2 Nos.	INR 2,38,00,000.00	
		Capital shall mean "Curr	
		Current liabilities" as adited consolidated ann	-
	Financial State		ual
2.4		The bidding capacity of	
	the following:	ıld be equal to or more th	an
	No. of Rigs	Bid Capacity	
	offered		
	1 No. 2 Nos.	INR 7,93,50,000.00 INR 15,87,00,000.00	
	4 NOS.	14K 15,67,00,000.00	

The bidding capacity shall be worked out by the following formula:			
Bidding Capacity = $[A \times 1.5] - B$			
Where, A = Maximum annual turnover in any one of the preceding three financial years. B = Commitments in next twelve months from the date of expiry of the bid validity as per Annexure-VIII .			
(a) Documentary evidence(s) in the form of relevant pages of the contract(s) executed showing detailed address(es) of client(s), scope of work and work order(s) along with completion certificate(s)/payment certificate(s) issued by the client(s) or any other document(s) which supports the 03 (Three) years' experience.			
Debt equity ratio : Debt equity ratio of the			
Debt equity ratio shall mean long term borrowings/ Net-worth.			
preparation of Financial Statements, if the last date of preceding financial / accounting year falls within the preceding six months reckoned from the original bid closing date and the Financial Statements of the preceding financial / accounting year are not available with the BIDDER, then the financial turnover of the previous three financial/accounting years excluding the preceding financial / accounting year will be considered. In such cases, the Net worth of the previous financial/ accounting year excluding the preceding financial / accounting year will be considered. However, the BIDDER has to submit an affidavit/undertaking certifying that the balance sheet/Financial Statements for the financial year (as the			
	the following formula: Bidding Capacity = [A x 1.5] - B Where, A = Maximum annual turnover in any one of the preceding three financial years. B = Commitments in next twelve months from the date of expiry of the bid validity as per Annexure-VIII. (a) Documentary evidence(s) in the form of relevant pages of the contract(s) executed showing detailed address(es) of client(s), scope of work and work order(s) along with completion certificate(s)/payment certificate(s) issued by the client(s) or any other document(s) which supports the 03 (Three) years' experience. Debt equity ratio: Debt equity ratio of the bidder should not be more than 2:1. Debt equity ratio shall mean long term borrowings/ Net-worth. Considering the time required for preparation of Financial Statements, if the last date of preceding financial / accounting year falls within the preceding six months reckoned from the original bid closing date and the Financial Statements of the preceding financial / accounting year are not available with the BIDDER, then the financial turnover of the previous three financial/accounting years excluding the preceding financial / accounting year will be considered. In such cases, the Net worth of the previous financial/accounting year excluding the preceding financial / accounting year excluding the preceding financial / accounting year will be considered. However, the BIDDER has to submit an affidavit/undertaking certifying that the balance sheet/Financial Statements for the	the following formula: Bidding Capacity = [A x 1.5] - B Where, A = Maximum annual turnover in any one of the preceding three financial years. B = Commitments in next twelve months from the date of expiry of the bid validity as per Annexure-VIII. (a) Documentary evidence(s) in the form of relevant pages of the contract(s) executed showing detailed address(es) of client(s), scope of work and work order(s) along with completion certificate(s)/payment certificate(s) issued by the client(s) or any other document(s) which supports the 03 (Three) years' experience. Debt equity ratio: Debt equity ratio of the bidder should not be more than 2:1. Debt equity ratio shall mean long term borrowings/ Net-worth. Considering the time required for preparation of Financial Statements, if the last date of preceding financial / accounting year falls within the preceding six months reckoned from the original bid closing date and the Financial Statements of the preceding financial / accounting year are not available with the BIDDER, then the financial turnover of the previous three financial/accounting years excluding the preceding financial / accounting year will be considered. In such cases, the Net worth of the previous financial/ accounting year excluding the preceding financial / accounting year excluding the preceding financial / accounting year will be considered. However, the BIDDER has to submit an affidavit/undertaking certifying that the balance sheet/Financial Statements for the financial year (as the	the following formula: Bidding Capacity = [A x 1.5] - B Where, A = Maximum annual turnover in any one of the preceding three financial years. B = Commitments in next twelve months from the date of expiry of the bid validity as per Annexure-VIII. (a) Documentary evidence(s) in the form of relevant pages of the contract(s) executed showing detailed address(es) of client(s), scope of work and work order(s) along with completion certificate(s)/payment certificate(s) issued by the client(s) or any other document(s) which supports the 03 (Three) years' experience. Debt equity ratio: Debt equity ratio of the bidder should not be more than 2:1. Debt equity ratio shall mean long term borrowings/ Net-worth. Considering the time required for preparation of Financial Statements, if the last date of preceding financial / accounting year falls within the preceding six months reckoned from the original bid closing date and the Financial Statements of the preceding financial / accounting year are not available with the BIDDER, then the financial turnover of the previous three financial/accounting years excluding the preceding financial / accounting year will be considered. In such cases, the Net worth of the previous financial/ accounting year excluding the preceding financial / accounting year excluding the preceding financial / accounting year excluding the preceding financial / accounting year will be considered. However, the BIDDER has to submit an affidavit/undertaking certifying that the balance sheet/Financial Statements for the financial year

	as on the Original bid closing date as per format.		
	Notes:		
	(a) For proof of Annual Turnover & Net worth any one of the following documents must be submitted along with the bid:		
	(i) A certificate issued by a practicing Chartered/Cost Accountant (with Membership Number and Firm Registration Number), certifying the Annual turnover & Net worth as per format prescribed in ANNEXURE-B.		
	OR		
	(ii) Audited Balance Sheet along with Profit & Loss account. In case of foreign bidders, self-attested/digitally signed printed published accounts are also acceptable.		
	(b) In case the bidder is a Central Govt. Organization/PSU /State Govt. Organization / Semi-State Govt. Organization or any other Central/State Govt. Undertaking, where the auditor is appointed only after the approval of Comptroller and Auditor General of India and the Central Government, their certificates may be accepted even though FRN is not available. However, bidder has to provide documentary evidence for the same.		
3.0	WORKOVER RIG:		
3.1	The bidder shall be in possession of the rigs offered.		
3.2	Identification of rig:		
	i) All the bidders are required to identify the rigs at the time of submission of bid with documentary proof thereof, confirming availability of the rigs for this contract.		
	ii) In case owner of the rigs himself is the bidder, the certificate confirming availability of the rigs for this contract, shall be furnished by owner himself along with the bid.		

3.3	The horsepower rating of the rigs offered		
	should be between 550 HP (Minimum)- 750 HP (Maximum). Further, the rigs offered		
	should be self elevating mast and sub- structure (as per API standard). The details		
	of the rigs are given in Section-II, Terms of Reference and Technical Specification.		
3.4	Vintage: The Work-over Rig units including		
	the accessories and equipment offered should not be older than 15(Fifteen) years from the date of original bid closing date.		
3.5	Bidder must confirm to provide 1(one) or 2 (two) complete rig packages as specified under Section-II of the bidding document.		
4.0	Bidder while submitting the documents in support of their experience vide Clause 1.0 above shall also submit details of experience and past performance or the collaborator (in case of collaboration) or of joint venture partner (in case of a joint venture), or Leader of the consortium (in case of Consortium bid) on works/jobs done		
	of similar nature in the past along with the technical bid. Also, details of current work in hand and other contractual commitments of the bidder (indicating areas and clients) are to be submitted along with documentary experience in the technical		
	bid in support of the experience laid down in Para 1.0 above.		
5.0	The bidder must confirm to provide the key personnel with requisite experience and qualification as specified in Clause 7.18 L (personnel to be deployed) under Section-II, Terms of Reference/Technical Specification.		
6.0	Offers indicating mobilization time of more than 60 days from the date of issuance of LOA (Letter of Award) will be summarily rejected.		
7.0	DOCUMENTS:		
7.1	Bidders must furnish documentary evidences in support of fulfilling all the above requirement as under:		
	(a) Rigs offered - documents relating to rigs already in possession along with technical specifications / details.		
	(b) Vintage of the offered rig as per Para 3.4 above.		

	(c) Drilling/Workover experience of bidder-Statement to be furnished by bidder in a tabular form along with copies of contracts / work orders (with detailed scope of work and contract duration), completion certificates / payment certificates issued by the clients.	
	(d) Financial turnover of bidder- Audited balance sheets / profit and loss accounts etc.	
	All documents submitted with bid must be self-certified by the bidder's authorized person signing the bid.	
8.0	VERIFICATION AND CERTIFICATION OF DOCUMENTS BY INDEPENDENT THIRD PARTY INSPECTION AGENCIES	
C)	COMMERCIAL BID EVALUATION:	
1.0	Bids shall be submitted under Composite Bid system i.e. Technical Bid and Priced Bid together in the OIL's e-Tender portal. The Technical Bid is to be uploaded as per Scope of Work & Technical Specification of the tender in "Technical RFx Response" Tab and Priced Bid as per Proforma-B uploaded in the "Notes & Attachments" Tab.	
2.0	Bidder shall offer firm prices. Price quoted by the successful bidder must remain firm during the execution of the contract and not subject to variation on any account.	
3.0	Bids should be valid for 120 days. Bids with shorter validity will be rejected as being non-responsive.	
4.0	The Integrity Pact must be uploaded in OIL's E-Procurement portal along with the Technical Bid digitally signed by the same signatory who digitally signed the Bid i.e. who is duly authorized to sign the Bid. If any bidder refuses to sign Integrity Pact or declines to submit the Integrity Pact, their bid will be rejected.	
5.0	Bids submitted after the Bid Closing Date and Time will be rejected.	
6.0	Bids received through the e-procurement portal shall only be accepted. Bids received in any other form shall not be accepted.	

7.0	The bid documents are non-transferable. Bid can only be submitted in the name of the bidder in whose name the User ID and Password have been issued. Unsolicited bids will not be considered and will be straightway rejected.	
8.0	Bid documents shall be typed or written in indelible ink and shall be digitally signed by the bidder or his authorised representative.	
9.0	Any physical documents wherever called for, submitted by bidders shall contain no interlineations, white fluid erasures or overwriting except as necessary to correct errors made by the Bidder, in which case such correction shall be initialled by the person or persons who has/have digitally signed the Bid.	
10.0	Any Bid containing false statement will be rejected.	
11.0	Bidders must quote clearly and strictly in accordance with the price schedule outlined in "Price Bid Format" of Bid Document, otherwise the Bid will be summarily rejected.	
12.0	Bidder must accept and comply with the following clauses as given in the Bid Document in toto failing which bid will be rejected: i) Performance Guarantee Clause ii) Force Majeure Clause iii) Tax Liabilities Clause iv) Arbitration Clause v) Acceptance of Jurisdiction and Applicable Law vi) Liquidated damage and penalty clause vii) Safety, Environment & Labour Law viii) Termination Clause ix) Integrity Pact	
13.0	The Bids and all uploaded documents must be digitally signed using "Class 3" digital certificate [e-commerce application (Certificate with personal verification and Organization name)] as per Indian IT Act obtained from the licensed Certifying Authorities operating under the Root Certifying Authority of India (RCAI), Controller of Certifying Authorities (CCA) of India.	

END OF TENDER DOCUMENT