

**OIL INDIA LIMITED
KG BASIN PROJECT
KAKINADA**

BID CORRIGENDUM-1

Bid Number: GEM/2026/B/7922319

Hiring of Shore Based Services for supporting Drilling Operations in Offshore Andaman OALP Blocks i.e. AN-OSHP-2018/1 and AN-OSHP-2018/2 and Offshore KG DSF Block for a period of 6 (Six) months, with provision for an extension by a maximum of 6 (Six) months or part thereof at same rate, terms and conditions.

1.0 The following terms and conditions shall be addition to all existing “Buyer added Bid Specific Terms and conditions” given in the bid document or any previous corrigendum. Prospective bidders are advised to bid as per following Terms and Conditions:

Terms and conditions, of the Bidding Document shall stand modified to the extent indicated here below under column “Amended Clause” of Annexure- I to BID CORRIGENDUM-1

2.0 All other terms and conditions of the tender remain unaltered.

**Oil India Limited
KG Basin Project**

**Annexure- I to
BID CORRIGENDUM-1**

**Terms and conditions of the Bidding Document shall stand modified to the extent indicated here
below under column “Amended Clause”**

Sl. No.	CLAUSE No.	ORIGINAL CLAUSE		AMENDED CLAUSE									
1	Scope of Work Exhibit-1 Clause No 2.4.1	Closed Warehouse of minimum 1,500 Sqm area		Closed Warehouse of minimum 1,000 Sqm area									
2	Scope of Work Exhibit-1 Clause No 2.4.2	Liquid Mud Plant of minimum 1600 sqm area and Dry Bulk Plant of minimum 1000 Sqm area, preferably in proximity to jetty		Liquid Mud Plant of minimum 1,000 sqm area and Dry Bulk Plant of minimum 700 Sqm area, preferably in proximity to jetty									
3	Scope of Work Exhibit-1 Clause No 6.9	Turn-Round-Time (TRT) of the marine vessel has to be within 12 hours, from berthing to cast off, including security check, customs, ROB survey, port & statutory clearance, etc..		Turn-Round-Time (TRT) of the marine vessel has to be within 24 hours, from berthing to cast off, including security check, customs, ROB survey, port & statutory clearance, etc..									
4	Scope of Work Exhibit-1 Clause No 11.1.5	Contractor can deploy suitable capacity Mobile Bulklers for loading without compromising on vessel Turn-Round-Time of 12 hrs.		Contractor can deploy suitable capacity Mobile Bulklers for loading without compromising on vessel Turn-Round-Time of 24 hrs.									
5	Scope of Work Exhibit-1 Clause No 11.1.8	Liquid mud plant Mud plant in the port will need 1000 sq. meter open space to accommodate following:- • Base Oil Storage Tanks – 5 nos (Each 430 BBL) • Brine storage Tanks – 7 nos (Each 430 BBL) • Brine Mixing tanks – 2nos (Each 230 BBL) • Mud Preparations Tanks – 2nos (Each 230 BBL) • Cutting Hoppers – 2nos • Mobile trucks to transport the fluid and pump to the supply vessels - 4 nos • Manpower to operate the Mud Plant		Liquid mud plant Mud plant in the port will need 1000 sq. meter open space to accommodate following:- • Base Oil Storage Tanks – 4 nos (Each 430 BBL) • Brine storage Tanks – 6 nos (Each 430 BBL) • SOBM (Synthetic Oil-Based Mud) Storage Tanks- 05 nos (Each 430 BBL) • Brine Mixing tanks – 2nos (Each 230 BBL) • Mud Preparations Tanks – 2nos (Each 230 BBL) • Cutting Hoppers – 2nos • Mobile trucks to transport the fluid and pump to the supply vessels - 4 nos • Manpower to operate the Mud Plant									
6	Scope of Work Exhibit-1 Clause No 12.1 (i)	Crane (01) one at OIL’s OCTG yard (Rough Terrain Hydraulic Boom Crane capacity 40 ton) in compliance to BS EN 13000 and 13001. The open yard crane may be used as stand-by to cater to any exigencies at wharf.		Crane (01) one at OIL’s OCTG yard (Rough Terrain Hydraulic Boom Crane capacity 70-80 ton) in compliance to BS EN 13000 and 13001. The open yard crane may be used as stand-by to cater to any exigencies at wharf.									
7	Scope of Work Exhibit-1 Attachment-III	<table><tr><th>SL NO</th><th>Category</th></tr><tr><td>1</td><td>Tyre Mounted Hydraulic Crane telescopic boom SWL 40T</td></tr></table>		SL NO	Category	1	Tyre Mounted Hydraulic Crane telescopic boom SWL 40T	<table><tr><th>SL NO</th><th>Category</th></tr><tr><td>1</td><td>Tyre Mounted Hydraulic Crane telescopic boom SWL 70-80T</td></tr></table>		SL NO	Category	1	Tyre Mounted Hydraulic Crane telescopic boom SWL 70-80T
SL NO	Category												
1	Tyre Mounted Hydraulic Crane telescopic boom SWL 40T												
SL NO	Category												
1	Tyre Mounted Hydraulic Crane telescopic boom SWL 70-80T												